

# Cavity Frequency Measurement and Initial Tuning at FLASH

V. Ayvazyan, T. Delfs, Z. Geng, W. Koprek, G. Kreps

FLASH Seminar, DESY, Hamburg, 02 Nov. 2010

# Goals

- Remote cavity tuning at FLASH and test stands
  - Remote and simultaneous frequency measurement of all cavities (no need to go into the tunnel)
  - Make use of standard RF distribution system, klystron, LLRF system, Master Oscillator etc.
- Check tuner step motors under warm conditions to exclude mistakes of connectors, wires and software
- Tuning of the cavities at the 1.3 GHz after cool down
- Relax the cavities to initial frequencies before warming up
- Test of the procedure with warm SC cavity
  - low power from klystron
  - checking the frequency range and resolution
- FLASH commissioning in March/April 2010
  - Check of tuner motors
  - Tuning of the cold cavities


# Measurement conditions

	Warm	Cold
Quality Factor	1.0e4	3.0e6
Frequency range [MHz]	1298.0 +/-0.4	1300.0 +/-0.4
Frequency step from pulse to pulse [kHz]	10	0.5
Measurement points (RF pulses)	80	1600
Frequency sensitivity [kHz]	25	1


# Requirements for the Frequency Sweeping System

- Sweeping with constant reference frequency – 1.3GHz from Master Oscillator
- Frequency range from -2.4 MHz to +0.4 MHz relative to 1.3GHz
- Frequency resolution at least 0.5 kHz
- Standard methods for field detection by diagnostic ADCs using DOOCS

# Schematic of the RF Station




# Hardware and Software of the Measurement Setup



# Measurements: Warm SC Cavity on a Table


Frequency sweep (-2MHz; -20MHz) with step 10kHz




# Measurements: Warm SC Cavity on a Table

Frequency sweep (-2MHz; -10MHz) with step 10kHz

Matlab interface




DOOCS panel





# Integration with LLRF Control System

- New version of firmware for frequency sweeping
- Created DOOCS frequency sweeping procedure server
- Operator Interface
- Automated data logging



## Configuration set-up

**Probe Signal Range**

Start  $\uparrow \downarrow \uparrow \downarrow$  + 20.0

Stop  $\uparrow \downarrow \uparrow \downarrow$  + 2000.0

Sweep enable
Sweep reset
Save spectrum



Firmware file (Tune)	flash_cav_tun_v50_250k_0x24.ufp
Firmware file (Control)	flash_master_v50_250k_0x32.ufp
Load firmware (Tune)	Load firmware (Control)

Cavity	Path
Cavity 1	TTF2.RF/LLRF.MONITORING/C1.ACC1.PROBE/AMPL.TD
Cavity 2	TTF2.RF/LLRF.MONITORING/C2.ACC1.PROBE/AMPL.TD
Cavity 3	TTF2.RF/LLRF.MONITORING/C3.ACC1.PROBE/AMPL.TD
Cavity 4	TTF2.RF/LLRF.MONITORING/C4.ACC1.PROBE/AMPL.TD
Cavity 5	TTF2.RF/LLRF.MONITORING/C5.ACC1.PROBE/AMPL.TD
Cavity 6	TTF2.RF/LLRF.MONITORING/C6.ACC1.PROBE/AMPL.TD
Cavity 7	TTF2.RF/LLRF.MONITORING/C7.ACC1.PROBE/AMPL.TD
Cavity 8	TTF2.RF/LLRF.MONITORING/C8.ACC1.PROBE/AMPL.TD
Cavity 9	TTF2.RF/LLRF.MONITORING/C1.ACC1.PROBE/AMPL.TD
Cavity 10	TTF2.RF/LLRF.MONITORING/C2.ACC1.PROBE/AMPL.TD
Cavity 11	TTF2.RF/LLRF.MONITORING/C3.ACC1.PROBE/AMPL.TD
Cavity 12	TTF2.RF/LLRF.MONITORING/C4.ACC1.PROBE/AMPL.TD
Cavity 13	TTF2.RF/LLRF.MONITORING/C5.ACC1.PROBE/AMPL.TD
Cavity 14	TTF2.RF/LLRF.MONITORING/C6.ACC1.PROBE/AMPL.TD
Cavity 15	TTF2.RF/LLRF.MONITORING/C7.ACC1.PROBE/AMPL.TD
Cavity 16	TTF2.RF/LLRF.MONITORING/C8.ACC1.PROBE/AMPL.TD


# FLASH Commissioning: ACC1

- Cavities 3 & 4 no change of frequency
- Motor current needs to be raised 40%

ACC1 spectrum, initial sweep



ACC1 spectrum after fine adjustment





First RF on ACC1 after cavity tuning, 07.04.2010

# FLASH Commissioning: ACC23

The frequencies are mirrored with respect to 1.3GHz (i. e. wrong sign)

ACC23 spectrum, initial sweep





Frequency spread range: 74kHz - 430kHz

# FLASH Commissioning: ACC45

- ACC4 is OK
- ACC5: cavities 2 & 8 no changes on frequency
- Motor current needs to be raised 50%

ACC45 spectrum, initial sweep




First RF on ACC5 after cavity tuning, 09.04.2010




# FLASH Commissioning: ACC67

- ACC6 is OK
- ACC7: bad signals, wrong cabling
- ACC7: cavity 3 and cavity 6 are interchanged

ACC67 spectrum before tuning



ACC67 spectrum after fine adjustment



# Documentation

- Complete and detailed commissioning documentation has been done
- Excel document with links to FLASH logbook
- User Manual: <http://msk.desy.de>

-273.15 °C.  
0 K

## ACC2 04/2010 commissioning

31000 steps will cause a difference of 25 kHz

	Date	Iso-Vac.	Beam-pipe	Temp	CAV 1	CAV 2	CAV 3	CAV 4	CAV 5	CAV 6	CAV 7	CAV 8
	TT.MM.JJJJ	y / n	status	K (elvin)	kHz	kHz	kHz	kHz	kHz	kHz	kHz	kHz
Tuner-resonance-run												
act. value of steps					70400	70400	70400	70400	70400	70400	70400	70400
1 act. frequency	08.04.2010	y	borrowed	2K	1299673	1299783	1299727	1299618	1299567	1299623	1299681	1299764
2 run to abs. stepvalue					0	0	0	0	0	0	0	0
3 frequency after run					1299673	1299783	1299727	1299618	1299567	1299623	1299681	1299764
4 Δ F					-11	-47	-60	-49	-52	-49	-52	-41
5 run to abs. stepvalue					477200	372200	456100	607100	542500	600900	522800	390300
6 frequency after run					1300005	1300005	1299999	1299988	1299987	1299994	1299965	1300040
7 Δ F					343	269	332	419	372	420	356	317
8 run to abs. stepvalue					483800	379400	454800	590200	523100	59200	501300	447300
9 frequency after run					1300348	1300348	1300348	1300348	1300348	1300348	1300348	1300348
10 Δ F					-5	-5	1	12	13	6	15	-40

Measured frequency(difference to 1.3 GHz) are mirrored, i.e. wrong sign.  
After correction of sign

-273.15 °C.  
0 K

## ACC5 04/2010 commissioning

31000 steps will cause a difference of 25 kHz

	Date	Iso-Vac.	Beam-pipe	Temp	CAV 1	CAV 2	CAV 3	CAV 4	CAV 5	CAV 6	CAV 7	CAV 8
	TT.MM.JJJJ	y / n	status	K (elvin)	kHz	kHz	kHz	kHz	kHz	kHz	kHz	kHz
Tuner-resonance-run												
act. value of steps					70400	70400	70400	70400	70400	70400	70400	70400
1 act. frequency	08.04.2010	y	borrowed	2K	1300129	1300155	1300240	1300178	1300245	1300241	1300352	1300180
2 run to abs. stepvalue					110400	140400	110400	140400	110400	140400	110400	140400
3 frequency after run					1300298	1300139	1300211	1300145	1300214	1300189	1300275	1300164
4 Δ F					-31	-16	-29	-32	-31	-52	-77	-16
5 run to abs. stepvalue					249500	35700	408800	346300	412000	407800	497700	432400
6 frequency after run					1299996	1299992	1299992	1299993	1299991	1299992	1300037	1299993
7 Δ F					-102	-147	-219	-153	-223	-198	-238	-171
8 run to abs. stepvalue					243500	345500	397300	335400	398600	395600	550800	422700
9 frequency after run					1300099	1300099	1300099	1300099	1300099	1300099	1300099	1300099
10 Δ F					4	8	8	8	9	9	-37	7

CAV 2: 8 no change of frequency. Raise of motor current needed to 50 %.

# Conclusions

- Automated and simultaneous scan of many cavities speed up setup of FLASH, and modules were commissioned within two days including software debugging
- Developed important procedure for large scale machines like XFEL & ILC
- Cavity characterization in wide range of frequency  $\pm 20$  MHz with high resolution 0.1 kHz
- Safe solution for warm cavities – possible measurement of very small field gradient (only 10kW forward power per cavity at CHECHIA and CMTB)
- No need for hardware change for the sweeping procedure (RF reference signal from MO)

# Acknowledgements

We want to express our thanks to our colleagues for the advise and help:

C.Albrecht, C.Gindler, O.Hensler, F.Hoffmann, M.Hoffmann,  
D.Kostin, G.Moeller, P.Pototzki