

TESLA - COLLABORATION

Transparencies from the
TESLA Meeting, March 1-3, 1999 at DESY

DESY



April 1999, TESLA 99-06

TESLA Meeting March 1 - 3, 1999 at DESY

Table of Contents TESLA Report 99-06

Introduction and Future Planning - <i>D. Trines</i> -----	1	
Summary of Cavity Tests - <i>M. Pekeler</i> -----	3	
FNAL Gun Status - <i>H. Edwards</i> -----	16	
Linac Operation Experience - <i>M. Geitz</i> -----	28	
RF Operation of two Cryomodules - <i>G. v. Walter</i> -----	39	
RF Transmitter for TTF - <i>J. Kahl</i> -----	54	
Modulator and Klystron Procurement - <i>A. Gamp</i> -----	61	
Status of Cryogenics - <i>B. Petersen</i> -----	62	
 News from Collaborating Institutes		
Saclay/Orsay - <i>B. Aune</i> -----	71	
INFN - <i>C. Pagani</i> -----	79	
FNAL - <i>D. Edwards</i> -----	84	
CERN - <i>D. Bloess</i> -----	85	
Univ. Wuppertal - <i>G. Müller</i> -----	88	
BINP - <i>V. Balakin</i> -----	90	
FZ Karlsruhe - <i>K.P. Jüngst</i> -----	95	
Univ. Rostock - <i>H.-W. Glock</i> -----	96	
Argonne - <i>M. White</i> -----	107	
TU Darmstadt - <i>A. Novokhatski, M. Timm, T. Weiland</i> -----	108	
INFN Lagnaro - <i>V. Palmieri</i> -----	118	
 Undulator Status - <i>J. Pflüger</i> -----		120
Collimator Section - <i>H. Schlarb</i> -----	127	
Electron Diagnostics - <i>P. Castro-Garcia</i> -----	139	
Photon Diagnostics - <i>J. Feldhaus</i> -----	150	
 Summary of WG Cavities and Auxiliaries - <i>B. Aune</i> -----		158
TESLA Waveguide Coupler - <i>M. Dohlus et al.</i> -----	161	
Measure of the Superheating Magnetic Field - <i>M. Fouaidy et al.</i> -----	170	
Status of Cavities R&D at LAL Orsay - <i>L. Grandsire et al.</i> -----	197	
HOM Measurements at TTF - <i>N. Baboi et al.</i> -----	206	
.. 4 x7-Cell Superstructure - <i>J. Sekutowicz</i> -----	214	
Waveguide Input Coupler for Accelerating System - <i>A. Zavadtsev</i> -----	221	
Field Measurements for a 4-Cavities Chain - <i>N. Baboi</i> -----	232	
FE-Measurements at Univ. of Wuppertal - <i>B. Günther et al.</i> -----	238	
Electropolishing of Cavities (CEA-CERN-DESY) - <i>L. Lilje</i> -----	245	
Summary of WG Linac Operation and FEL Commissioning - <i>S. Reiche</i> -----	258	
Schedule for Installation and Commissioning 99 - <i>G. Schmidt</i> -----	261	
 Agenda-----		267

Proposal for Time Table of TTF II and FEL

Status of present Linac operations will be given in several presentations this morning
Cavities of module #3 are ready to be combined to string 6 out 8 couplers have been preconditioned with RF
Proposal: Spend 1 more week to condition couplers #7 and #8
Proposal for Linac operation:
End run as planned March 15th
Schedule for installation will be presented by G.Schmidt
Stay with start-up date for proof of principle experiment for FEL July 15th

Module #1 will be replaced by Module #3

Module #1 will be equipped with better cavities and cryostat will be modified.

ready as #1* for reinstallation

end October 99

Proposal: Linac operation

from July 15th

to end October

Install module #1*

resume Linac operation February 1st 2000

Linac operation until end of

November 2000

End of TTF stage I

!!! need 10 MW klystron plus modulator to operate three modules

EXPO 2000 at DESY runs from beginning of JUNE to end OCTOBER

Module #4 (NEW CRYOSTAT!!) will be ready

mid December 99

will be used as exhibition part for EXPO 2000

Material for 32 standard cavities is being ordered

Fabrication order for 24 + 8 cavities is on call for tender

Earliest dates for completion of

module #5 end of May 2000

module #6 end of July 2000


module #7 mid September 2000 ???????

Problem superstructure

If design report based on superstructure beam test would be important

→ has to be done in phase I

1999 2000 2001 2002



2
↓ TECHNICAL DESIGN REPORT

Summary of cavity tests

Michael Pekeler
TTF Collaboration Meeting
DESY, 1st - 3rd March 1999

- Overview above tested TESLA 9-cell cavities
- Performance of cavities installed in module 2
- Test results of new cavity production
- Cavities for module 3
- Field emission
- Test result of Rossendorf gun

Overview above tested TESLA 9-cell cavities

50 cavities arrived at TTF
(+ 5 cavities for Schwetman
+ 6 cavities for Rossendorf)

44 cavities got HT 1400 C
(+ 6 cavities for Rossendorf)

42 cavities tested in vertical cryostat
(+ 5 cavities for Schwetman
+ 2 cavities for Rossendorf)

28 cavities equipped with He vessel

18 cavities tested in horizontal cryostat
CHECHIA

13 cavities installed in the linac
(+ 8 cavities will be installed now)

In addition 4 single cell cavities, one 2-cell cavity, one 4-cell cavity, one 5 cell cavity and one 1/2 cell (gun)-cavity have been treated.

How much have we done in one year


activity	1996	1997	1998	9 weeks 1999
cavities arrived	7	12	27	3
inner surface removal [mm]	1.2	1.7	4.0	1.3
cavities HT 1400	8	5	24	8
cavities got first vertical test	10	8	20	4
total number of vertical tests	29	45	46	7
He vessel welded	8	3	14	2
CHECHIA tests	8	1	5	4

How much time do we need now for cavity test and preparation

activity	now [days]	personal estimation for mass production [days]
mech. + RF check	3	1
BCP before HT	3	1
HT 800 C	4	2
HT 1400 C	5	5
BCP after HT	3	1
tuning	1	1
preparation vert. test	5	3
vertical test	4	3
He vessel welding	12	4
preparation for CHECHIA	7	3
CHECHIA test	9	5
total	59	29


only working days were counted

Maximum gradients reached in 9-cell cavities



1998: we normally reach gradients between 20 and 30 MV/m.
But there are also cavities with quenches in that region.
We need to find the quench locations, reduce field emission and study the Qdrop without xrays

We have observed now the Qdrop without or with very low xrays.



1. Cavity production

cavity	E_{acc} [MV/m]	Q_0 [10 ⁹]	used In/as	comment
P1	>29.1	6	EP at KEK	Prototype
P2	16.3	22	stored	Prototype
C19	22.1	2	capture cy	
D1	24.7	17	module 1	defect weld defect weld defect weld defect weld defect
D2	21.9	4	module 1	
D3	25.6	29	module 1	
D4	13.5	16	module 1	
S7	13.8	8	module 1	
S8	12.5	12	module 1	weld defect weld defect weld defect weld defect weld defect
S10	14.2	16	module 1	
S11	13.5	13	module 1	
A15	>23.0	4	module 2	
C21	>29.3	8	module 2	
C22	20.2	21	module 2	weld defect
C23	>25.3	8	module 2	
C24	>19.7	5	module 2	
C25	>28.4	9	module 2	
C26	>21.4	4	module 2	
C27	>26.7	8	module 2	
S12	12.6	13	cap. cy (FNAL)	weld defect
D5	8.6	24	cy 4 tuner test	defect
D6	13.6	12	cut	defect
S9	11.4	11	stored	weld defect
A13	3.4	10	museum	strong weld defects
A14	6.4	11	stored	weld defect
A16	20.8	6		needs new test
A17				not tested yet
A18				not tested yet
avg.	18.9			

2. Cavity production (scanned material)

cavity	E _{acc} [MV/m]	Q ₀ [10 ⁹]	will be used in	comment
S28	>25.3	6	-> module 3	
S29	>26.7	6	-> module 3	
S30	>28.4	7	-> module 3	
S32	>26.5	7	-> module 3	
D39	>25.2	7	-> module 3	
D40	>22.8	5	-> module 3	
D41	>23.3	5	-> module 3	
D42	24.6	7	-> module 3	
S31	(28.1)	4	(-> module 4)	new test necessary
C44	>25.5	6	-> module 4	He vessel welded
S33	23.9	7		Q _{drop} without x-rays
S34	>14.4	2		field emission
Z49	>18.0	4		field emission
D37	20.3	5		BD
D38	19.5	3		BD
C43	12.9	20		BD, weld defect
S35				HT 1400 done
S36				HT 1400 done
C45				HT 1400 done
C46				HT 800 done
C47				HT 800 done
C48				just arrived
Z50 - Z54				under production at Zanon
avg.	22.9			

Performance of cavities installed in module 2

cavity	vert. test [MV/m]	hor. test [MV/m]	comment
C21	29.3 *	18.3	new HPR after hor. test
C22	20.2	18.1	new HPR after hor. test
C23	25.3 *	33.0	
C25	28.4 *	24.0 **	
A15	23.0 *	26.4 **	
C24	19.7 *		no hor. test
C26	21.4 *		no hor. test
C27	26.7 *		no hor. test
avg.:	24.3	23.4	

* limited by field emission and available cw RF power
 ** limited by coupler in horizontal test

2 cavities had problem:

- C22 quench @ 20.2 MV/m, quench at repaired whole in equator weld
- C24 had accident during HPR, nozzle of HPR system scratched inner surface, no grinding was applied, only 20 µm BCP.

What did we reach with module 2 ?

All cavities get the same incident power, the Q_{ext} of the input coupler vary by $\pm 10\%$

Without beam up to now 20.8 MV/m were reached with 1 Hz operation and 500 μs rise + 500 μs flat-top time.

In addition cryo losses were measured with 10 Hz and 500 μs rise time, 800 μs flat-top time operation.

18.8 MV/m, $P_{cryo}=14.2$ W $\rightarrow Q = 2.7$ E9
19.7 MV/m, $P_{cryo}=20.8$ W $\rightarrow Q = 2.0$ E9

With beam up to now 18.5 MV/m were reached with 500 μs rise + 100 μs flat-top time.

The warm part of the coupler is the limiting factor $\rightarrow$ still needs more processing time.

Test results of new cavity production

3 cavities showed quench below or close to 20 MV/m:


- D37 @ 20.3 MV/m, reason not known
- D38 @ 19.5 MV/m, suspicion: bad weld preparation
- C43 @ 12.9 MV/m, quench at repaired whole in equator weld

cavity D42 shows quench @ 24.6 MV/m, reason not known.
cavity S33 shows quench @ 23.9 MV/m, reason not known


All other cavities are limited by field emission and available amplifier power

+


2. cavity production from ACCEL:
9 ordered, 9 arrived, 7 tested, 4(+1) > 25 MV/m




2. cavity production from DORNIER:
6 ordered, 6 arrived, 6 tested, 4 >~ 25 MV/m



2. cavity production from CERCA:
6 ordered, 6 arrived, 2 tested, 1 > 25 MV/m



2. cavity production from ZANON:
6 ordered, 1 arrived, 1 tested



Cavities for module 3

4 cavities from ACCEL (S28, S29, S30, S32) and 4 cavities from Dornier (D39, D40, D41, D42) selected for module 3.

Average gradient in the vertical test was:
25.4 MV/m


All cavities are equipped with He vessel

4 cavities are equipped with processed cold part of main coupler



3 (+1) cavities have been tested in CHECHIA

2 additional main coupler are processed and 2 more additional main coupler are under processing -> all cavities will be equipped with a processed cold window

vertical test of cavities selected for module 3



Comparison of vertical to CHECHIA test for module 3 cavities




Field emission

Still the vertical test results suffer a lot from field emission


There was a hint that drying by laminar flow gives better results than drying by pumping. In the moment, we use drying by laminar flow.

We have a new HPP coupler to fight field emission, but we have no klystron to use it in the moment.

We reduced a cavity by applying HPP with 10 Hz without having a good interlock system ---> We did not do HPP for a long time, so we partially forgot how to do it right




-24-



History of cavity S31

-22-



Test result of Rossendorf gun

Idea to use a superconducting cavity as a photo injector

We have tested this cavity called RG1 with and without cathode


Parameters:

	TESLA 9cell	RG1 without cathode	RG1 with cathode
R/Q [Ω]	1036	67.9	68.3
Hpeak/Eacc [mT/MV/m]	4.26	3.17	3.17
Epeak/Eacc	2.0	2.0	1.5


Results:

	RG1 without cathode	RG1 with cathode
Eacc [MV/m]	18.2	28.5
Hpeak [mT]	57.7	90.3
Epeak [MV/m]	36.1	43.6
Ecathode [MV/m]		31.8

Hpeak = 90.3 mT in a TESLA 9cell cavity would correspond to an accelerating gradient of 21 MV/m.



Rossendorf gun 1/2 cell cavity



The Lasersystem

Performance


- Energy:
 - up to 30 μJ per Micropulse, largely sufficient for 8nC
 - stability (shot to shot/within train) better than 5% rms
- Phase:
 - stability better than 1 ps
 - drift seen with short pulses, fixed by forcing laser phase to 0 using the phase feedback system
 - occasional drift of resonator length
- Transverse profile:
 - flat top, uniformity not satisfactory yet
 - spatial filter in UV to be included, conversion green to UV to be optimized
- μ Pulse length:
 - phase scans suggested a long pulse, confirmed by streak camera and autocorrelation measurements ($\sigma = 15\text{ ps}$ in UV)
 - fixed by replacing the oscillator laser head
 - now: $\sigma = 9\text{ ps}$ in IR, estimate 5 to 8 ps in UV

The Lasersystem II: Reliability


- Uptime:
 - is running since mid December (except Xmas)
 - in total 1600 hours with 1 Hz or 5.8.10⁶ shots
 - uptime 99%, available for beam 97.5%
- Failures
 - flashlamps of pulse train oscillator (PTO) exchanged after 8.10⁶ shots
 - lost 4 hours + 2 shifts with very unstable conditions
 - complete PTO laser head exchanged to cure pulse length
 - Sparc cpu in laser VME had to be replaced
- Server:
 - laser server and control program is running smoothly and stable
 - laser cpu was heavily effected once by Desy network problems, reboot was required
- Interlocks
 - no failure of personal laser safety interlock
 - access to tunnel with laser beam on is not yet established in a way, that operators could make use of it.
 - no failure of technical laser safety this time (we had one failure in May 1998), SPS is working fine

Autocorrelation trace ($\lambda=1047\text{nm}$)


before




after exchange of laser head



28.Feb.99 23:33.01










gun Power to $> 3 \text{ MW}$


$2.2 \text{ MW} \Rightarrow 35 \text{ MV/m}$ cathode.

operates to 2.7 MW . some trips
(needs console used)





4INJ1 at 27/2/99-h11:58:26



gun phase scan.

16 deg FWHM.

2.14 ps/deg

0.3 mm/ps

34 ps FWHM 14.6 ps σ

4.3 mm σ

flare-measurement.

now

IR $\sigma \approx 9.5$ ps was 18.5 σ

UV (exp. 5-9 ps) was 15.

Design




Colby - TTF report. 13-28 ps FWHM.


thesis 8-10 ps FWHM.

Best Effort Request? 5-10 ps σ


or 12-23 ps FWHM.


Sect Emittance Deter.






TTFOIR2@MAC, FEB26/11:13






TTFOIR2@MAC, FEB26/13:33




TTFOIR2@MAC, FEB26/11:00

Col. projection 170_93_cut_2



TTFOTR2@MAC, FEB26/14:52

170_93_cut_2



24

TTFOTR2@MAC, FEB26/13:40

Data. Plots

1 NE

Spot FWHM 12 p (5.1 p σ)

Slit FWHM 6.3 p (2.7 p σ)

$$X X' = \frac{12 \times 6.3}{385} \times \frac{(0.6)^2}{(2.35)^2} = 0.125$$

$$Z = 385 \text{ mm} \quad p \# c k = p = 0.06 \text{ mm}$$


log book

Spot σ 8.9 p

Slit σ 3.6 p

$$X X' = \frac{8.9 \times 3.6 \times (0.6)^2}{385} = 0.3$$

Correction for beam convergence?




Correction $\sim \frac{1}{0.7}$ from slit spacing
we think

$$E_0 \approx \rightarrow \frac{0.125}{0.7} \times 33 = 5.9 \text{ MeV}$$

$$\rightarrow \frac{0.3}{0.7} \times 33 = 14 \text{ MeV}$$

$$p_c = 16.5 \text{ MeV} \quad \uparrow \gamma$$

image from memory



To Do - (this, next week)

- Try to see beam through slit as move focus forward.
- Set up and measure δn_c .
- Compare with Mark.
- Get Energy spectrum vs ϕ
- See how ϵ changes with focus.
- Dark current check

INL

SL45


image from memory



3

LFROM

slits#2_175_95_-38.11FF



27

LINAC OPERATION JAN/FEB 93


MAIN GOAL:

- PREPARATION OF THE LINAC FOR THE INSTALLATION OF THE FEL
- COMMISSIONING OF NEW BEAMLINE ELEMENTS
 - (i) FINAL RF GUN
 - (ii) BUNCH COMPRESSOR II
 - (iii) CRYO MODULE II
- COMMISSIONING OF DIAGNOSTICS
- " " OPTICS
- MEASUREMENTS IMPORTANT FOR THE HIGH ENERGY COLLIDER
 - HDH
 - RF STEERING

1) INJECTOR STATUS

- ENERGY WITHOUT CAPTURE CAVITY
 $E \approx 4.5 \text{ MeV}$
- INJECTOR ENERGY $E > 16.5 \text{ MeV}$
- ENERGY SPREAD
 $Q = 1 \text{ mC} \rightarrow \frac{\Delta E}{E} \approx 4.3\%$
 $Q = 8 \text{ nC} \rightarrow \frac{\Delta E}{E} \approx 1\%$
 (UPPER ESTIMATE $\rightarrow$ SCRAMPL)
- ENTRANCE: $1 \text{ mC} \rightarrow (12 \pm 6) \cdot 10^{-6}$
 (THERMALLY) $8 \text{ nC} \rightarrow (50 \pm 10) \cdot 10^{-6}$
 (PEPPER POT): $1 \text{ mC} \rightarrow (3 \pm 4) \cdot 10^{-6}$
- L GUN SEENOIDI MUCH SMALLER THAN EXPECTED.
- DARK CURRENT: $7-14 \mu\text{A}$
- CATHODE LIFETIME: $\approx 1 \text{ month}$
- LASER PULSE LENGTH:
 $\delta_2 \approx 20 \text{ ps} \rightarrow \delta_2 \approx 10 \text{ ps}$
- ELECTRON PULSE LENGTH
 $\delta_1 \leq \delta_2 \leq 15 \text{ ps}$

Secondary Solenoid (A)




Primary Solenoid Field (A)




Emittance, x (mm mrad)

Primary Solenoid Field (A)



Emittance, y (mm mrad)

Primary Solenoid Current (A)







Primary Solenoid = 166 A

$\beta = 1mc$

Emittance x,y (mm mrad)

Secondary Solenoid (A)

Transverse phase space distribution at the TTFL Injector II



Normalized emittance: (12 ± 6) mm mrad
 Twiss parameters: $\beta = (1.2 \pm 0.3)$ m
 $\alpha = (0.1 \pm 0.3)$

H. Edwards

D. B. B. B.

Plot 20 Chan 1

distance

(6)-(1) = 81-35 = 46 Pixels (± 2)

assume 60 μm /Pixel $\rightarrow$ (6)-(1) = 0.06 mm, 46 = 2.7 $\pm$ 0.1 mm

$\rightarrow$ distance of slit images, 0.55 $\pm$ 0.02 mm

$\rightarrow$ reasonable to assume slit distance of 0.5 mm

196, 64, 2.7 HU

q₉ 110, Dec 101




($\pm$ beam width at slit)

$\sigma_x = \frac{0.5}{0.15} \cdot (1.3 \pm 1.2) \cdot 0.06 \frac{\text{mm}}{\text{Pixel}} = (0.70 \pm 0.1) \text{ mm}$

beam divergence at slit: $\frac{\sigma_x}{\text{dist}} = \sigma_{x'} = \frac{0.70 \pm 0.1 \text{ mm}}{3.85 \text{ mm}} = (0.18 \pm 0.02) \text{ rad}$


$\gamma \approx 34$

$\gamma \sigma_{x'} = \epsilon'' \approx (0.7 \pm 0.1)(0.1 \pm 0.02) 34 \text{ mm mrad} = (9.5 \pm 4) \text{ mm mrad}$




2) LINAC

- ENERGY DURING STABLE OPERATION WITH KLYSTRON II: $E \approx 160-180$ MeV
- ENERGY SPREAD: $\Delta E/E \approx 0.3\%$ (INC) (OTR SCREEN EXP 3)
- ENTRANCE: (EXP1, 2C2)
 - $\epsilon_x \approx 8 \cdot 10^{-6}$ $\epsilon_y \approx 30 \cdot 10^{-6}$
 - ERROR ESTIMATE $\approx 50\%$
 - $\hookrightarrow$ HAS TO BE CONFIRMED BY DIFFERENT ANALYSIS.
- BEST "OPTICS APPROXIMATION"
 - $\hookrightarrow$ SO-CALLED "LINBERG" OPTICS
- MUCH HIGHER DRAIN CURRENT FROM MODULE 2 THAN MODULE 1
 - $\hookrightarrow$ SOURCE 8.4 CAVITY
- DIAGNOSTICS:
 - TOROIDS NOW OPERATIONAL
 - BPM, NOW OPERATIONAL
 - ~~EXPRESS~~
 - SYNCHROTRON LIGHT EXP 3 AVAILABLE




Straight-through optics for ^{13}C
with space-charge effects circled off



W11 FROM SOLARIS, JAN 27, 1994

TF-FEL optics straight through
for $q = 1\text{ nC}$ (bc2 and sband tripled off) 27.1.99



SPECIFIC EXPERIMENT

1) HIGHEST GRADIENT MODULE II

• 'FORWARD POWER' MEASUREMENTS

$$E^2 = R_0 \cdot 4 \cdot Q_L \cdot P_1 (1 - e^{-5/3})$$

$$L, 20.8 \text{ MV/m} = E_{AC}$$

$$L, \text{PARTY}$$

• BEAM MEASUREMENT (2 MLYSTRONS)

→ MODULE I $E = 85 \text{ MeV}$

→ MODULE II $E_{AC} = 18 \text{ MV/m}$,
LIMITED BY COUPLER VACUUM

→ 1 WEEK-END OPERATION TO OBTAIN HIGHER VALUES

→ ACHIEVED GRADIENT CONSTANTLY GROWING TO:



$$E_{AC} = 18.1 \text{ MV/m}$$

$$T = 600 \text{ pS}$$

WITH FULL TRANSM.

STILL LIMITED BY CARRIER VACUUM

→ CONSISTENT NOW WITH RF CALC/B.



13.4.99

1245 ~~1245~~ We want to do exp. on measurements on CHECHIT

Therefore in order to have low loss from this module, I reduce the power to 80 kW

2100 we start now with $FT: 400 + 100 \mu s / 1 Hz$

→ goal: find E_{acc} max at this pulse form.

2200 150 kW = 18.4 MV/m
 2205 155 kW = 19.0 MV/m
 2207 160 " 19.56 MV/m
 2212 178 " 20.0 MV/m IL @ 204 / #10

pulse 500 + 100 μs / 1 Hz

2235
 2236 180 kW 19.4 kW MV/m
 2237 180 kW 19.0 " "
 2238 180 " 19.85 " "
 2239 180 " 19.96 MV/m IL @ 204 / #10
 2242 180 kW 20.8 14 V/m / data Telegramm
 2256 160 kW IL @ 204 / #15

500 + 300 μs / 1 Hz

180 kW 19.4 MV/m IL @ 204 / #75
 All e- beamware IL thresholds to 3V


now script: produce FT 20 MV, SCR

Power 150 kW, 500 μs rise time @ 20 MV/m

for 500 + 300 μs
 500 + 300 μs







500 + 300 μs

Programme worked up to a pulse length of 500 + 500 μs at a repetition rate of 1 Hz up to a power of 140 kW
 This is 20.6 MV/m at $R_{eff} = 2.4 \cdot 10^6$ and 500 μs rise time



2) HIGHER ORDER MODES

- FOUND THE SAME "TRAPPED MODE" THAN LAST YEAR (20845 GHz)
- OBSERVATION OF HIGH INSTABILITY
- SEE SPECIAL WORKING GROUP PRESENTATION.




3) BUNCH COMPRESSION II



- COMPRESSION OBSERVED
- BUNCH LENGTH MEASURED
 $\delta_z \approx 2.3 \text{ pV}$ (BEFORE LAYER TRANSFER)
 $\delta_z \approx 1.6 \text{ pV}$ (AFTER ")
 (REMEMBER + 50% ERROR)
- QUALITATIVE SCAN OF HOW WE CHOOSE TO OPTIMIZE COMPRESSION
- PROBLEM DURING OPERATION (LAST 2 WEEKS)
- (i) TRANSVERSE INSTABILITY IN THE INJECTOR, PERHAPS CHARGING
- (ii) STRONG FLUCTUATIONS IN ENERGY APPEARED $\rightarrow$ VISIBLE IN BCL
 (NEW EFFECT, NEED TO BE INVESTIGATED)

Pyro. Detector 0


1st Sand compression b.c.2



Pyro. Detector 1



Pyro Signal



CONCLUSION

- RF GUN OPERATIONAL
- MODULE II DE = 18,1 MV/cm CAPLER LIMITED
- COMPRESSOR II JHELED COMPRESSION
- DIAGNOSTICS FINALLY WORKING

STEPS TO GO

- OPTIMIZE ENTRANCE OF RF GUN FOR FEL OPERATION
- CONDITIONING OF MODULE CAPLER
- MORE WORK ON RC2 NEEDED TO OBTAIN $E_2 \approx 250 \mu m$.

RF Operation

Two Cryomodules and the RF Gun
Run 1/99

Guido von Walter

- The Linac LLRF System
- Module 2 RF commissioning
- The RF Gun
- Conclusion and Outlook

G. von Walter

usr/tt/svr2/gwalter/frame/RFOperation/tile

26 February 1999 9:21 pm

TTF

LLRF Team

Valeri Ayvazyan
Alex Gamp

Serguei Goloborodko

Henning Insieke

Andrei Kholodnyi

Tomasz Plawski

Kay Rehlich

Stefan Simrock

Yurij Tchernouso

Guido von Walter

with support of

MHF-P

MHF-SL

FD ET

TTF Collaboration

S. Simrock

/usr/tt/svr2/simrock/doc/frame/tt_meeting/tt_meet_nov_98/ttf_team.doc

November 8, 1998 3:01 pm

The Linac LLRF System



New DSP System

- New hardware, faster DSPs, input channels for the control of 24 cavities
- Features Kalman Filter and Smith Predictor
- Exception handling DSP
- Ready for three module operation

New DSP server software

- Parameter based operation, tables calculated by server
- Operator interface integrated into DOOCS control system

G. von Walter




DSP server features

Parameter driven table generator

Tables and feedback operation data are derived from the RF operational parameters:

- Setpoint:
 - Voltage (calibrated)
 - Phase (relative to beam)
 - Fill time
 - Delay time
 - Flat top duration



G. von Walter

71F

DSP server features (2)

- Feedforward:
 - derived from setpoint table
 - Fill to flat top ratio
 - Amplitude scaling
 - Phase offset
- Beam compensation:
 - Beam current
 - Beam phase
 - Beam start time
 - Beam duration
- System Gain

$\log G_{\text{gain}}$

G. von Walter

DOOCS Operator interface

System selection:

TT/RF/DSP/LINAC1/

Update: ☒ Norm ☐ Fast ☐ Slow

Startup:

TT/RF/DSP/LINAC1/

Update: ☒ Norm ☐ Fast ☐ Slow

Linac LLRF operation panel:

TT/RF/DSP/LINAC1/

SP Voltage, MV
▲▲▲▲▲▲ ▲▲
+ 160.00
▼▼▼▼▼▼ ▼▼

SP Phase rel. beam
▲▲▲ ▲▲▲
+ 0.00
▼▼▼ ▼▼▼

☒ Feedback
Loop Gain
▲▲▲▲ ▲▲
+ 20.00
▼▼▼ ▼▼

☒ Feedforward

☐ Beam Comp.
Current
▲▲▲ ▲▲
+ 2.20
▼▼▼ ▼▼

G. von Walter

11F

LLRF Utility software

Support applications integrated into DOOCS environment:


llrf_tools_menu

Loop phase	Beam phase	Ripple
Adaptive FF	Vector sum	Calibration

G. von Walter

Loop phase


- compensates phase offsets from klystron and phase shifter (in BC operation)
- required for stable feedback operation



G. von Walter

Beam phase

- measures phase of beam with respect to RF acceleration
- allows simple adjustment for 'on crest'




System identification, Dipl. Techn. M. Henning

G. von Walter

Ripple table

- enables a correction scheme for the systematic error from down conversion to 250kHz IF
- replaces simpler filtering schemes and allows feedback with higher gain



7% error is amplified by feedback loop

G. von Walter

Adaptive Feedforward

- controls the calculation of FF tables with correction for pulse-to-pulse repetitive errors


Run		Stop		Setpoint begin [usec]:		Setpoint end [usec]:	
				Number of steps:			
				Step height:			
				Max rms error [%]:			
				Pause [s]:			
				Max ff change:			
				Max vector sum:			
				Max ff value [bit]:			
				Delay + x [usec]:			
Quit Response matrix New ff table							
performance start of program rms amp rms phase							

*Dipol. Tuck M. Lipe
adaptive FF improves feedforward by a factor of 10*

G. von Walter


Vector sum display

- monitors vector sum of modules separately




Calibration

- assists in beam based calibration of gradients



RF System Diagram with Bunch Compressor



G. von Walter

/usr/ttfsvr2/gwalter/frame/RFOperation/layout_rf1

25 February 1999 10:14 pm

Module RF commissioning

1. Phase adjustment

- Three stub tuners used to adjust phases and loaded Q
- improvement from $\pm 50^\circ$ to $\pm 3^\circ$
- one tuner (cavity 8 of module 1) fitted with motor drive

2. Beam based calibration

- good beam required to get sufficient signal/noise ratio (8nC, 30ns for 1MV/m gradient)

3. Gradient calibration

- preliminary calibration (to 10%)
- used as current measurement to improve transmission between modules

G. von Walter

/usr/ttfsvr2/gwalter/frame/RFOperation/Module


28 February 1999 9:34 pm

WG (M1, C1) = 30mm

(M1, C2... C8) = 0mm (all stubs)
(M2, C1... C8) = 30mm (all stubs)

Changed positions as shown below

Module 2



1,3,8 → 30 mm to M2 = (10,15,10)

2,4,5,6,7 = 30mm to M1 = 0mm
1,3,8 = 0mm to M2 = 0mm

Stub positions for measurement


M1 (C2,3,6,7) = 0mm M1 (C1,4,5,8) = 30mm

M2 (C1,3,8) = 0mm M2 (C2,4,5,6,7) = 30mm

M1 = 0mm (WG to Module 1)

M2 = 0mm (WG to Module 2)

Module 1



1,4,5,8 = 30mm 2,3,6,7 = 0mm

to M1 = 0mm
to M2 = 0mm


1730 Change stub positions to

M1, C1,3,8 → 30mm


to M2 = (10,15,10)

THE

Beam Based Gradient Calibration

for $\Delta t \ll \tau_{\text{cav}}$:

$$\Delta V_{ind} = I \cdot \Delta t \cdot \left(\frac{r}{Q} \right) \cdot \pi \cdot f$$



28.4. 550 42C

Module 1

0.041593

0.020796

0.013249-

330

25
15
10
5


25-1

Case: 2015-423

Module RF commissioning (2)

4. Operation

- Stepper motor driver induced crashes resolved, stable operation since then
- vacuum interlocks due to slow ramping of modulator with feedback enabled (will be addressed by exception handling DSP)
- Microphonics measurement $\sigma_{\Delta f} < 5 \text{ Hz}$
- Lorentz force detuning measurement




Module RF commissioning (3)


Module 2 at high gradients

- connect modules to Klystrons 1 and 2
- control module 1 from Linac DSP
- control module 2 from Checcia DSP (Feedforward only)
- 3 days processing without beam

- gradients of 18MV/m per cavity reached (after increasing fill time)
- maximum beam energy 240MeV
- high field emission from cavity 8
- limited by couplers 2 and 6 (vacuum and photomultipliers)
- reduced power to couplers 2+6
- > limited by 1 and 3, field breakdown in cavity 8 during flat top



RF System Diagram for high gradient operation



G. von Walter


/usr/tttsvr2/gwaller/frame/RFOperation/layout_rf2

25 February 1999 10:18 pm

RF Gun

System overview

- identical DSP software, identical control software
- two DSPs
- no use made of feedback loop due to short time constant of normal conducting cavity ($Q_l = 22000$)
- control by adjusting feedforward table between pulses



G. von Walter

/usr/tttsvr2/gwaller/frame/RFOperation/RFGun

28 February 1999 9:47 pm

RF Gun Operation

Operation

- temperature drift of water cooling (0.5°C) results in a detuning (25kHz per °C)
-> Phase changes by 15°
- Phase and amplitude drift regulated between pulses
temperature pulse
- cannot predict fluctuations from pulse to pulse
- regulation on mean value, there is a slope left, during operation the stability is around $\pm 3^\circ$
- Tests with new downconverter boards have been made to improve signal quality and reduce 250kHz noise

G. von Walter

Conclusion + Outlook


LLRF achievements:

- 24 cavity Linac RF system operational
- New LLRF operator interface
- RF Gun system

Future developments

- Integrate **exception handling** into the interlock system, provide a fast shut off of the klystron
- **State machine** will simplify operator's perception of the system
provides automated startup state transitions (on/off, interlock, mode changes) can be programmed
- Increase RF Gun pulse length and change DSP code to perform correction during flat top

G. von Walter



Author		Sheet 1
Joachim Kahl	RF-transmitter for TTF	Date 03.03.99

Subject foramtion

1. Historical summery
2. Some impressions of the RF-Transmitters
3. Situation at moment
4. Projects in future

Author		Sheet 2
Joachim Kahl	RF-transmitter for TTF	Date 03.03.99

Presentation of the RF-transmitter:

Manufacturer	Type	Nation
Saclay	RF-transmitter	Fr
Orsay	cavite de capture	
Fermi National Acece- lerator Laboratory	RF-transmitter	USA
	1 - 3	


Author	Sheet 3	
Joachim Kahl	RF-transmitter for TTF	
		Date
		03.03.99

Presentation of the RF-transmitters:




RF-transmitter Nr.1 for the cavity testing

Author	Sheet 4	
Joachim Kahl	RF-transmitter for TTF	
		Date
		03.03.99




RF-transmitter Nr.2 server for the module 1 and 2

Author	Sheet 5	
Joachim Kahl	RF-transmitter for TTF	
		Date
		03.03.99



RF-transmitter Nr.3 server for the gun

Author	Sheet 6	
Joachim Kahl	RF-transmitter for TTF	
		Date
		03.03.99



RF-transmitter-Fr provide the capture cavity

Author		Sheet 7
Joachim Kahl	RF-transmitter for TTF	Date 03.03.99

Author		Sheet 8
Joachim Kahl	RF-transmitter for TTF	Date 03.03.99

Historical summery of the 3. RF-transmitter:

1.

Historical summary

41-42 week

RF-transmitter destructed at Fermi National Accelerator Laboratory

RF-transmitter reseived at Desy with a small damage on cabinet No.1

47. week

mounting of the Klystron

48. week

connection to the Main Power 400V-AC

49. week

voltage safty tested

51. week


first high voltage

52. week

conditioning the Klystron

15

Author	Sheet 9	
Joachim Kahl	RF-transmitter for TTF	
		Date
		03.03.99



Author	Sheet 10	
Joachim Kahl	RF-transmitter for TTF	
		Date
		03.03.99

Some impression of the 3. RF-transmitter

Author		Sheet 11
Joachim Kahl	RF-transmitter for TTF	Date 03.03.99

3. A situation at the moment.

When everything is working, nobody takes any notice of the RF-transmitter, but whenever there are small mistakes, caused by using, they realize that there are RF-transmitters. In the beginning of this year they had to realize more than once that there are RF-transmitters.

As the electronic parts, installed into the RF-transmitters, partly used up to their limit, it might happen that they stop working.

Author		Sheet 12
Joachim Kahl	RF-transmitter for TTF	Date 03.03.99

The RF-transmitter stopped working, as it did not stand the requirements. Just by the immediat helpful support of **Peter Prieto** and **Mike Kucera** it became possible to keep the period of not working limited.

The RF-transmitter of the capture cavity had a runstop because of their using up. I want to thank the developer **Michel Desmons** very much that he supported me whenever he could. Michel Demont left his electronic parts to me, which enable us to eliminate the damage rather soon.

Author		Sheet 13
Joachim Kahl	RF-transmitter for TTF	Date 03.03.99

4. Future projects

In the near future we want to prepare the RF-transmitters for remote control more then it now exists. We want do this with new equipments.
That means an improvement of the remote control as well as automatic of service-functions.

For example we want to mention the calibration of the pervarance with a microcontroller system.

Another pointe is to diagnose instabilities which might be found in the system. By this diagnosis we will be able to react of endurance limits and to improve the working of the mechaines.

Author		Sheet 14
Joachim Kahl	RF-transmitter for TTF	Date 03.03.99

At the time we are discussing about the development and the construction of a fourth RF-transmitter. This RF-transmitter will be delivered by the factory Puls-Plasmatechnik.

Modulator and Klystron Procurement

Multibeamklystron:

RF Performance was ok.

A leak has occurred. This opportunity is used to implement improvements in the gun.

Testing at Thomson foreseen for June. Delivery to DESY foreseen for **September 99.**

The following items have been ordered:

Two additional 5 MW Klystrons. There is already one reserve tube.
Expected **December 99 and January 00.**

Two vertical MBKs.
Expected **April 00 and July 00.**

One Modulator.
Expected **May 00.**

Call for tender for **two additional modulators** is out. These modulators could be here by **December 00.**

SMES will hopefully be at DESY in the **first half of 00.**

The pulse transformer for SMES has been delivered to DESY **end of December 98**

Status of Cryogenics

Overview:

(Extended TTF / FEL-Supply)

**TESLA Meeting
1.-3. March 1999**

**DESY-MKS-
B.Petersen**

**Status of the TTF – 900W-plant
Objectives of the extended supply
Concept of the extended supply
Redundancy
Status of the main components
Concept for a Module Test Stand**

Status of the TTF-900 W Plant

The plant is operable as projected in 1993
(vertical dewars 1,2,3; CHECHIA; LINAC)

still missing:

third cryo module, large heat exchanger

still room for improvements:
capacities for parallel operation of dewars
changes in tubing

(vertical dewars are cooled down and filled
with liquid in about 1 h - still too slow !!!)

maintenance in week 12:

2 screw compressors (C101 > 60 000 h !)
vacuum compressors (> 16 000 h)

remember:

- the 900 W plant was projected as a test facility
- main parts of the equipment older than 15 y
- screw compressors are 'individual prototype' machines – the manufacturer is no longer interested in big repairs
- cooling water supply of screws 'superannuated'

Extended Cryogenic Supply Main Components

HERA-FEL-Valve-Box (operable)

HERA-FEL-Transfer-Line (installation end of March)

HERA-FEL-Line of Construction (critical!)
(delayed – installation in March)

FEL-Subcooler-Box (under fabrication)

2 nd set of Vacuum Compressors (order in March)

FEL-Cryo-Building (ready)

SMES-Transfer-Line (see schedule)

TTF-Transfer-Line-Connection (order in March)

Single-Module-Test (some ideas –see schedule)

2 nd BCBTL (start of layout - see schedule)

Warm-Gas-Tubing (call for tender)

Low Pressure HEN (delivery in July)

The Concept of the Extended Cryogenic System

the heat loads of the TTF / FEL – linac will exceed the capacities of the existing 900 W / 4.5 K TTF refrigerator

the helium distribution system of the TTF / FEL – linac will be connected to the HERA helium refrigeration plant

the helium distribution system of the linac will be maintained as designed for the operation of the original TTF – linac
(consisting of three cryo modules)

the existing TTF-900 W / 4.5 K helium refrigerator and the 1st set of vacuum compressors will supply the TTF test plant for single cavities (four cryostats)

a 2nd set of vacuum compressors will be added to the system for the supply of the TTF / FEL – linac

Objectives of the Extended Supply:

Cryogenic supply of

the 1 GeV TTF / FEL-Linac consisting of 6 – 10 TESLA cryo modules (2 K, 4.5 K and 40 / 80 K temperature levels)

a Superconducting Magnetic Energy Storage Cryostat (SMES)
(4.5 K and 40 / 80 K temperature levels)

a test for single cryo modules
(2 K, 4.5 K and 40 / 80 K temperature levels)

and optional


the supply of the TESLA Test Facility for the test of single cavities (2 K, 4.5 K and 40 / 80 K temperature levels)

further advantages:


Decoupling of the 2K Supply of Linac and Test Plant ! (Heat Load Measurements !!!)



Redundant supply of the TTF / FEL-Linac

HERA-FEL - Line - of - Construction



BLOCK DIAGRAM of the EXTENDED CRYOGENIC SYSTEM





Single Cryo-Module-Test: Proposal for a Test Program

(input from W.D.Moeller / M.Pekeler)

no Beam !

Mechanical check of the components

Leak tests of the vacuum systems

Conditioning of the main RF-couplers (cavities off resonance)

Conditioning with resonant cavities (check of tuning systems)

Measurement of the dynamic cryogenic loads of the cavities (Q versus E_{acc} characteristics of the cavities)

HPP-treatment of the cavities



Test of the superconducting quadrupole

Measurement of the static cryogenic heat loads

Measurement of the alignment of the cavities during cool down and warm up

Nr.	Vorgangsname
77	Fertigung
78	Ablatmetall
79	Betriebbereit
80	2.BCBL
81	Einwurf
82	Spezifikation
83	Ausarbeitung
84	Auftragvergabe
86	Design
87	Fertigung
88	Ablatmetall
89	Betriebbereit
90	Warme Verrohrung
91	HERA-FEL
92	Spezifikation
93	Ausarbeitung
94	Auftragvergabe
96	Montage
97	Halle 3 / Kryobau
98	Entwurf
99	Annehmen Auszeichnung
100	Annehmen Auftraggeber
101	Annehmen Lieferung
102	Rohmontage
103	TTF-Wärmetauscher
104	Druckprobe bei IHEP
105	Fertigung der Einbauteile
106	Zusammenbau
107	Ablatmetall IHEP
108	Lieferung IHEP-DESYS
109	Erbau Halle 3

status: 26-2-99
B. Petersen



Nr.	Vorgangsname	3. OR	4. OR	1. OR	2. OR	3. OR	4. OR	1. OR	2. OR	3. OR	4. OR	1. OR	2. OR	3. OR	4. OR
38	Fertigung FEL-Vorhänkebox	10/28	4/18												
40	Werkstatt	4/18	5/28												
41	Montage FEL-Vorhänkebox	6/1	7/28												
42	Inbetriebnahme FEL-Vorhänkebox	7/28	8/30												
43	FEL-Vorhänkebox betriebsbereit	8/30													
44	Heilungspumpen 2. Satz														
45	Spezifikation Heilungspumpen	10/18													
46	Ausschreibung Heilungspumpen	10/18	12/31												
47	Auftragserstellung Heilungspumpen	1/1	3/21												
48	Design Heilungspumpen	4/1	5/14												
49	Fertigung Pumpen	5/14	2/18												
50	Montage Heilungspumpen	2/21	3/6												
51	Inbetriebnahme Heilungspumpen	3/7	3/20												
52	Betriebsbereitschaft Heilungspumpen	3/20													
53	Bauten														
54	Planung Bauten														
55	Ausschreibung Bauten														
56	Baueinführung	10/30													
57	Bauten fertig	10/30													
58	SANES-Transfer														
59	Transfer Design	5/3	6/30												
60	Transfer Bau	10/1	2/3												
61	Montage DESY	3/1	4/28												
62	Inbetriebnahme	4/1	5/29												
63	TTE-Transfer-Verbindung														
64	Spezifikation	11/2	1/7												
65	Ausschreibung	1/18	2/15												
66	Auftragserstellung	2/15	3/28												
67	Design	3/28	5/1												
68	Fertigung	6/1	8/31												
69	Montage	8/1	11/23												
70	Inbetriebnahme	11/23	12/14												
71	Modultest														
72	Entwurf	10/1	2/28												
73	Spezifikation	3/1	3/20												
74	Ausschreibung	3/21	6/30												
75	Auftragserstellung	7/3	8/31												
76	Design	8/1	2/18												

Status:
26.7.99
P. Plosser
- 21151 -

SACLAY / ORSAY

x R/D SRF

x E.P.

— KEK
— CERN, DESY

x Cu / Nb

x New techniques of fabrication
x Measurement of H_{sh}

x LIUAC

x Experiments

x BPH, Toroids.

x Input couplers.

M.FOUAIDY

Test	Test-cell Samples	Nb RRR * and Cu & Nb thickness	$R_0(K.m^2/W)$ @ 1.8 K	$\Delta R_0(K.m^2/W)$ @ 1.8 K	Remarks
1	4 rods ($\Phi 8$)	100 *	$5.6 \cdot 10^{-4}$		OK
1	4 rods ($\Phi 8$)	e_{Cu} : 1-1.5 mm or 2- 2.5 mm	$6.5 - 7.5 \cdot 10^{-4}$	$0.9 \pm 1.9 \cdot 10^{-4}$	OK
2	2 Nb Cabot disks, BCP 50 μ m	30-40 * $e_{Nb} = 1.96$ mm	$1.46 \cdot 10^{-3}$		OK
2	2 Nb cabot disks, BCP 50 μ m with APS bonding alloy and APS Cu coating (Mallard)	$e_{Nb} = 1.96$ mm $e_{Cu} = 2.5$ mm	$2.07 \cdot 10^{-3}$	$6.2 \cdot 10^{-4}$	permeability test to be performed on the APS Cu coating disk
3	2 Nb Plansee disks, BCP 40 μ m	30-40 * $e_{Nb} = 2$ mm	$6.32 \cdot 10^{-4}$		OK
3	2 Nb Plansee disks BCP40 μ m with APS bonding alloy	$e_{Nb} = 2$ mm $e_{Al} = 0.2$ mm	$1.27 \cdot 10^{-3}$	$6.4 \cdot 10^{-4}$	OK
4	2 Nb Wah-Chang disks BCP 50 μ m	30-40 * $e_{Nb} = 0.5$ mm	$3.84 \cdot 10^{-4}$		Nb k(T) not yet measured (without HT : Ti @ 1200 °C).
4	2 Nb Wah-CHang disks, BCP 50 μ m with APS bonding alloy and APS Cu coating (Mallard)	$e_{Nb} = 0.5$ mm $e_{Cu} = 2.2$ mm	$7.48 \cdot 10^{-4}$	$3.6 \cdot 10^{-4}$	permeability test to be performed on the APS Cu coating disk
5	2 Nb disks Wah-Chang machined on the lathe	200 * $e_{Nb} = 2.02$ mm	$5.6 \cdot 10^{-4}$		Nb k(T) not yet measured
5	2 Nb disks Wah-Chang machined on the lathe with CAPS (Argon) Cu coating.(CEA/DAM)	$e_{Nb} = 1.85$ mm $e_{Cu} = 2.0$ mm	$5.6 \cdot 10^{-4}$	≈ 0	Nb/Cu interface analyzed by US, Micrograph to be done (after second test ?).

TABLE I: OVERALL THERMAL RESISTANCE R_0 OF ALL Nb and Nb/Cu SAMPLES TESTED UP TO NOW

Fabrication and test of monocell and multicell cavities

- 3GHz cavities (number: 7)
- Five 1.3GHz monocelle cavities
- Two 1.3GHz Tri cell cavities
- Nb sheets supplied by Heraeus RRR = 140
Thickness: 4mm
- Coat cavities with thermally sprayed deposit
- Coating thickness: 2-3mm
- " Material: to be decided After Mechanical and thermal tests on samples
- coating technique: APS or VPS or HVOF
To be chosen according to several criteria:
 - High Bonding strength
 - High Young modulus
 - Good thermal performance
 - Best mechanical properties (low Temp.)

Measure of the superheating magnetic field

C.Thomas (PhD), G.Bienvenu, M.Fouaidy*, H.Sun**

- Direct measuring H_{sh} in High Power RF Short Pulsed mode
- $H_{sh} = f(\lambda/\xi) H_c$
– Measuring λ on cavity

LAL - ORSAY

CAVITIES R&D


- Hydroforming
- hot forming
- plasma spraying of copper
- E.B. welding
- non destructive controls
- mechanical tests

more tomorrow.....

grandsir@lal.in2p3.fr

1





EXPERIMENTS SATCLAY / KER on Electro Polishing

- 3 single cell cavities (CECA) tested at
Satclay, then sent to KER for EP and test.

1/ Summary:

		Enx.Satclay	Enx.KER/EP
S1	RER 300 HT 1300°	25 / slope	32 } no
S2	RER 200 HT 1000°	26 / slope	32 } slope
S3	RER 300 no HT	15	33


2/ on cavity S3:

- After further EP (70µm) →


$$\boxed{37 \text{ MV}/\mu \text{m} \sim 2 \cdot 10^{10}}$$

- BCP 60µm → 28 MV/µm + slope
- BCP 70µm → 24 MV/µm + slope

Test Results at Saclay





Three Saclay's Cavities



★ New Results

S-3 / C103 Cavity



or the KEENRANT BPM
ON THE HIGH CHARGE BEAM
OF TTF.

M. LALOT
C. MAGNE
B. PHUNG
J. NOVO

Sacky

H. SCHWARB


Desy

- A BPM designed to achieve both:
- HIGH RESOLUTION (RF cavity, reentrant shape, cylindrical symmetry)
- WIDE BAND measurements

(antennae coupled
to $Q \sim 3$
 $\Rightarrow BW \sim 200 \text{ MHz}$)


RESOLUTION OF THE REENRANT BPM
ESTIMATED FROM THE SIGNAL/NOISE RATIO.

$10 \mu\text{m}$ @ 3 nC/bunch



noise 30 mV $\Rightarrow$ 11 μm


@ 3 nC



capture cavity off
gun 2 MW module 1 on

DARK CURRENT = 14 μ A @ CARCAV

ON ~~the~~ Friday 26/02/99 The DARK
current was measured at BC2:
200 nA for gun: 2.9 MW @ BC2




- After delays Timing system (beam)

TOROIDS w/ INJECTOR II

- Signals out of pre-amplifier


++



TTFDIAG/ADC/INJADCA/CH00

Beam Current: 1.79 nC


[nC] ADC/INJ.ADC4/CH00.TD



TTFDIAG/ADC/INJADCA/CH01

Beam Current: 1.88 nC


[nC] ADC/INJ.ADC4/CH01.TD



TTFDIAG/ADC/INJADCA/CH02

Beam Current: 1.85 nC


[nC] ADC/INJ.ADC4/CH02.TD



TTFDIAG/ADC/INJADCA/CH01

Beam Current: 1.74 nC



[nC] ADC/INJ.ADC5/CH01.TD



TTFDIAG/ADC/INJADCA/CH02

Beam Current: 1.75 nC

[nC] ADC/INJ.ADC5/CH02.TD



News on TTF Activities at INFN


(LNF, LNL, Milano & Roma2)

Presented by Carlo Pagani

1) Cryostat Design & Cryomodule Assembly

- Cryostats # 2 & # 3 - including WPMs
 - 2nd Cryomodule in operation successfully
 - 3rd Cryomodule assembly: starts this month
- Cryostat # 1 to # 1* order close to be sent out
 - From May to October 99: cavities and shields replaced
- Cryostats # 4 to # 8 - # 4 & # 5 in fabrication
 - Final drawings at ZANON since end 98
 - Expected delivery at DESY: October 99
 - Composite posts (FNAL design) in fabrication
- New Assembling Tools - order close to be sent out
 - New assembling tools compatible with Cryo # 1 to # 3
 - Design has been defined
 - Tooling due by September '99




Cooldown of TTF Module #2
Y Displacements



2nd Generation Cryostat


Active element movements for a 1000 N force at the edges

Cooldown of TTF Module #2
X Displacements



3rd Generation Cryostat

Active element movements for a 1000 N force at the edges



2) Photocathodes (P. Michelato)

- TTF Injector II Cathode System
- INFN Photocathodes in operation at DESY and FNAL
- Cathodes prepared at Milano transported to DESY
- R&D Activity
- "New" photoemissive materials: K-Te & K-Cs-Te
- Poisoning and life tests on new cathodes
- Low energy electron spectrometer for thermal emittance

3) Beam Diagnostics (LNF & Roma 2 groups)


- Diagnostics instrumentation
- Actuators for new OTR screens
- Actuators for the pepper pot screen
- New fast electronics modules for the strip-lines
- Beam parameter measurements with OTR
- Emittance and energy spread measurements
- Emittance measurements with pepper pot

4) Cavity Fabrication


- Standard Cavities - A13 to A18 delivered
- A15 in module # 2: 26.4 MV/m @ 1.2 W (800 μ s - 10Hz)
- New Technologies - Spinning at LNL

5) Theoretical activity (M. Ferrario)

- Beam behavior in Superstructures
- quasi-on line calculations for RF Gun optimization



TTFOIR2@MAC, FEB26/1406



Fermilab Report

Don Edwards

1 March 1999

There are two activities underway at Fermilab that may be of potential interest to the TESLA Collaboration.

The Photoinjector

The equipment installed in service building A0 is very similar to Injector II in Halle 3. The RF gun is the twin of the one at DESY, the capture cavity is S12 from DESY installed in the cryostat of ORSAY design. The bunch compressor following the capture cavity is identical, as is the INFN Milan cathode preparation chamber.

The schedule for Halle 3 shown earlier today by Dieter Trines is quite ambitious. The program at Fermilab has considerable overlap in the study of the RF gun, of space charge dominated beams, and of related diagnostics for the investigation of the 3 d-o-f emittance. It is quite possible that the A0 work can be helpful as regards schedule.

RF Separated Kaon Beam

The old (1970 vintage) Main Ring at Fermilab has been replaced by the Main Injector, a 120–150 GeV proton synchrotron in a separate tunnel. While performing its role as particle source for the Tevatron collider, it can also deliver beam to a fixed-target physics program in simultaneous operation. When the Main Injector was proposed over ten years ago, a kaon physics effort was to be part of the fixed-target activity.

The spill duty factor of the Main Injector is one second out of three. A separator system for kaons must therefore employ superconducting cavities. I commented on the possibility of such a project at the collaboration meeting in Zeuthen during November 1997. Last year, we developed a design report, which was reviewed last October. Now, in the last few days, initial funding is in place.

Kaon economy favors high frequency; the rise of surface resistivity with frequency as well as concern for unreasonable extrapolation from experience argues for caution. Our conclusion is that 4 GHz is an upper limit. Taking 25 MV/m as a given for TESLA style resonators, in the deflecting mode considered here the corresponding figure is 5 MV/m with the assumption that surface magnetic field is the limiting factor.

Two remarks are in order. The development of deflecting mode structures in this frequency range may find application for beam splitting toward several FEL's at some stage in the TESLA program. And, it is important to recognize that because of the past seven years of the TESLA development program, it has become possible to approach the kaon separator project with some confidence that the goals can be achieved.

TESLA Electropolishing of single cells

C. Antoine, B. Aune, D. Bloess, J.P. Charrier, E. Chiaveri,
L. Ferreira, E. Hæbel, L. Lilje, J. P. Popov, H. Sata, B. Thony,

CEA-CERN-DESY

1 Electropolishing of Half Cells

Is working. 10 half-cells have been polished. However, copper dissolved from cooling circuits and from cathode and got deposited onto niobium. Copper deposit was effectively removed with nitric acid.

In two hours 100µm polished. For an example of surface finish see the transparents of L. Lilje.

2 Electron Beam Welding

No rhombic raster. Welding from outside in two passages (warming and then welding)

However, much improved vacuum: better than 10^{-6} m.b.

Ten half cells have been successfully been welded.

3 Electropolishing of Single Cells

Installation will be ready beginning April

Instead of copper electrodes niobium electrodes will be used, and then e baked after electropolishing in order to outgass the hydrogen

The cooling circuits will be made from PFA with longer pipes to compensate for less efficiency.

4 Measurements

The first Measurements have been done at CEA without any surface or thermal treatment after welding. A thin niobium film deposited by evaporation during welding explains the moderate results. However, no effect from hydrogen has been observed.

Another installation for measurements is ready at CERN. This will permit more measurements to be done.

5 Oven Treatment

Single cells can be treated at Temperature up to 1500°C
Quantitative degassing measurements can be done

6 Improvement of HP-rinsing

An adapter for the LEP cavity HPR installation is being built to permit high quality rinsing at pressures of 100 bar for 1.3 and 1.5 GHz cavities
Will be ready in April

7 Niobium-copper Cavities

Breakthrough

The slope has been very much reduced
Residual resistance 2-4 nOhm
Still many electrons (see 6)

1.5 GHz Nb/Cu R & D

(Benvenuti Calatroni Danilato
Arbet-Engels Peck Valente) Feb '99

Current Status

- We are now routinely producing "slope-free" cavities having a residual resistance which does not increase with RF field by more than $1 \text{ n}\Omega / \text{MVm}^{-1}$ (this would contribute a Q of 10^{10} at 30 MVm^{-1}).


- However the accelerating field is currently limited typically to 10 MVm^{-1} as a result of field emission, even if it did reach 20 MVm^{-1} in some occasions.

Experimental evidence exists that this limitation can be postponed to 25 MVm^{-1} by improving cavity rinsing and handling

- Current effort is on
 - commissioning our modified double cathode sputtering system and chasing an unexplained "pollution" at the 30 to 50 nΩ level.
 - constructing a new high pressure firing station which should be in operation before the end of March
- We have completed or nearly completed studies on:
 - trapped magnetic flux induced losses and pinning mechanism.
 - hydrogen pollution and hydride precipitation in filings
 - influence of the interface. film-substrate on the film properties
 - factors contributing to the residual resistance.

IMLS

Planar diode configuration



- Pressure 10^{-7} mbar
- Spacer thickness $10 - 100 \mu\text{m}$ (Teflon foil)
- Maximal anode Voltage $2 \text{ kV} \Rightarrow E_p \leq 200 \text{ MV/m}$
- I-U measurement with PC

FE-measurements at University of Wuppertal

B. Günther, T. Habermann, G. Müller

Outline


- DC field emission measurements with a new planar I-U measurement technique configuration with a luminescent ITO screen (IMLS)
 - Measurement configuration
 - First results on niobium samples
 - Comparison of FESM and IMLS
- Investigation of enhanced field emission due to etching defects
 - Etching of niobium cavities
 - FESM scans of differently etched niobium samples

Samples prepared at TTF by D. Reschke

Comparison of IMLS and FESM

IMLS	FESM (field emission scanning microscope)
Advantages - simple and cheap apparatus - fast sample investigations (2h): - onset of FE : $E_{on}(I=0,5nA)$ - integral I-U measurements - imaging of strongest emitters - long term current- and gasprocessing possible	Advantages - very high spatial resolution (100nm) - in situ SEM for emitter analysis - single emitter investigations (E_{on}, Fowler-Nordheim : β, S) - reliable non-destructive Fe measurements - UHV 10^{-10} mbar - in situ AES, Ion gun
Disadvantages - limited spatial resolution ($\approx 100 \mu m$) - reidentification of emitters impossible - no single emitter investigations - danger of (multi-) discharges due to switch on effects	Disadvantages - slow Fe investigations (1 day/sample) - complex and expensive measurement system

First tests of IMLS on a niobium sample



sample area of $1 \times 1 \text{ cm}^2$

$U = 880 \text{ V}$; $I = 50 \mu A$; $d = 50 \mu m$

7 light spots visible at 17.6 MV/m

(mechanically bad prepared sample)

BNP activity in TESLA project

1. Measurements of the tapped higher order modes for two polarization in the superconducting cavities of the TTF linac.

2. Studying of microbunch-to-microbunch jitter, using BPM's with submicron resolution.

3. Measurements of vibrations of the superconducting quadrupoles in the cryogenic modules of the TTF linac.

4. Experimental study of the fast feedback system on TTF linac, using this equipment (fast kickers, BPM's, etc.)


5. Development of a new SC accelerating structure with a high gradient for TESLA project.

New configuration of accelerating structure for TESLA

V. Balakin


Branch of the Institute of Nuclear Physics
Protvino, Russia

A new proposed accelerating structure consists of two standing wave coupling resonator systems



The accelerating resonators of each systems are coupled by two cut-off waveguides.

The resonant coupling on π -mode is formed by two stubs inside waveguide. π -mode frequency is equal to operating frequency f_0 .



Advantages of new configuration

1. High accelerating gradient

$$\text{Acc.gradient}_{\text{New config}} \approx 2 * \text{Acc.gradient}_{\text{TESLA}}$$

2. No problem with trapped modes

- a) transverse
- b) longitudinal

3. Easy tolerance (according to P. Avrahovs simulations)


$$\downarrow 8m \downarrow \gamma_m$$

$$0.5 \div 1 \text{ MHz} - \text{for accelerating resonators}$$

$$4 \div 8 \text{ MHz} - \text{for coupling resonators}$$

4. Few input couplers (1 per 8 meters)

Equivalent circuit for one of two chains of resonantly coupled cavities.



Structure simulations carried out by P. Avrahovs (Branch of INP) show that for a practically realizable structure the coupling coefficients


$$K_1 \approx 10\%$$

$$K_2 \approx 30\%$$


$$K_3 \approx 10\%$$

can be achieved.


Cavity manufacture




Pressing
(not precise)




Squeezing
(not precise)




Hydroforming
(precise)




Machine-cutting
of coupling slots



Stamping waveguide
with stabs and slots



Welding



Problems

1. Short-range wake-fields because of small aperture ($\varnothing \cong 30 \text{ mm}$)

Solutions

1. Bunch charge should be reduced two times because of two times higher accelerating gradient (Luminosity can be kept by changing of repetition rate)
2. Due to waveguides the structure is more rigid. It means alignment can be better.
3. Signal from waveguides can be used for the alignment.

- II. Accidental breakdowns can damage a structure surface because of big storage energy and high group velocity.

Solutions

1. Experiment
2. Reduction of group velocity

- III. Electron multipacting in complex cavity geometry.

Solutions

1. Experiment
2. Computer simulation

Forschungszentrum Karlsruhe Technik und Umwelt

OVERVIEW OF THE "SMES" MODULATOR DEVELOPMENT (Feb 26, 1999)

STATUS		SCHEDULE	
POWER SUPPLIES FOR SMES AND CAPACITOR	ORDERED	10/99	DELIVERY
POWER PULSE FORMER UNIT	BEING ORDERED BY COMPONENTS	11/99	DELIVERY
PULSE TRANSFORMER	DELIVERED	1/99	DELIVERY
SAFETY SYSTEM	SPECIFICATIONS READY	11/99	DELIVERY
CONTROL SYSTEM	UNDER WORK	11/99	DELIVERY
SC MAGNET SYSTEM	MODEL COIL SUCCESSFULLY TESTED	9/99	DELIVERY
CRYOSTAT incl. CURRENT LEADS	BEING ORDERED	10/99	DELIVERY
MODULATOR CONSTRUCTION		12/99 - 2/00	
SYSTEM TEST AT FZK	PREPARATIONS	3/00 - 4/00	
TRANSPORT & MOUNTING		5/00	
SYSTEM TEST AT DESY		6/00	



2.585 GHz - Mode in Three Cavities:

Experimental Results and Numerical Uncertainties

TESLA-Meeting
DESY, 1.-3.3.99


D. Hecht, U. van Rienen, K. Rothenmund, H.-W. Glock

Institut für Allgemeine Elektrotechnik, Universität Rostock

2.585 GHz - Mode in Three Cavities (Mod 1 Cav 3, 6; Mod 2 Cav 5) Summary of Experimental Results

(N. Baboi, S. Fartoukh, H.-W. Glock, G. Kreps, F. Marthausen,
O. Napoly, H. Schlarb, S. Simrock, G. v. Walter ... and many else)

- Spectral position of passbands is shifted upwards at least ≈ 10 MHz.
- Transmission measured with a network analyzer between different pairs of HOM couplers leads to certain pattern of field distribution/coupling:



- Beam induced HOM-coupler signal measured with spectrum analyzer **confirms this pattern** (Cav 6, Mod 1 not measured).
- Mode causes relevant beam deflection; measured with resonant excitation (Cav 6, Mod 1 not measured).

















96

Conclusion:

Beam relevant field pattern exists, coupling three cavities.
Astonishingly high amplitude spread (> 30 dB) in neighbouring HOM-couplers.

Aim:

Identify cause in order to avoid.
Try to simulate.



2.585 GHz - Mode in Three Cavities (Mod 1 Cav 3, 6; Mod 2 Cav 5)

Attempts of Explanation

- Type of cavity or coupler?
 - Not likely: M1C3 and M1C6: Saccay-type cavities and HOM-couplers, but not the only ones in M1.
 - But: M2C5 is the only A-type cavity in module 2.
- Special beam-pipe length?
 - Yes: Allows for beam-pipe-centered mode, which is beam relevant.
 - But: Variation of length in a reasonable range does neither change the character of the mode ensemble nor the order of beam relevance - so why not elsewhere?
- And: How to explain very weak coupling of one of the HOM-couplers at each pipe?
 - Maybe: On each side of a "dangerous" cavity only couplers of one polarization talk to each other.
 - But: Polarization changes across "dangerous" cavity, i.e. rotation of about at least 60° - why?
- Polarization effect?
 - Maybe: On each side of a "dangerous" cavity only couplers of one polarization talk to each other.
 - But: Polarization changes across "dangerous" cavity, i.e. rotation of about at least 60° - why?
- Beam pipe bellows?
 - No. (Very slight change in S-parameters due to bellow.)
- Not a dipole field?
 - No. (Neither monopole nor quadrupole modes near this frequency.)
- Strange field pattern, caused by different passband frequencies?
 - If yes, not found yet: The only field geometry somewhat similar depends very sensitively on tuning. Furthermore there is no explanation of weak coupling of one HOM-coupler.

All models neglecting the influence of the couplers on the field geometry may be insufficient.

Attempt of S-parameter description of combined 2D/3D-structure:

Module 1

No. Cav.


HOM-Coupler Imp.-Coupl.

1	03	DES	FNRL
2	S8	Saclay	DES
3	S10	Saclay	DES
4	01	DES	FNRL
5	02	DES	FNRL
6	S11	Saclay	DES
7	04	DES	FNRL
8	S7	Saclay	FNRL


Module 2

1	C22	Saclay	FNRL
2	C21	Saclay	"
3	C25	Saclay	"
4	C23	Saclay	"
5	H15	DES	"
6	C26	Saclay	"
7	C27	Saclay	"
8	C24	Saclay	"


Frequency shift of cavity-localized mode in symmetrical cavity vs. common length scaling factor



Setup for calculations:



MAFIA-Calculations of 9-cell cavity with 3/2-cell-length beam pipes





2.5748 GHz, $k_{\text{loss}} = 3.965 \cdot 10^{14} \text{ V}/(\text{As m}^2)$
located inside the cavity



2.5862 GHz,
 $k_{\text{loss}} = 6.068 \cdot 10^{14} \text{ V}/(\text{As m}^2)$
located in the beam pipe





MAFIA



FRAME: 11	22/02/99 - 15:51:18	VERSION[V4.015]	HOM.DRD
			TESLA COUPLEUR H.O.M.
3D. PLOT OF THE MATERIAL DISTRIBUTION IN THE MESH			

P--:4015

#VOLUME

COORDINATES/M
FULL RANGE / WINDOW
X [-0.040000, 0.040000]
Y [-0.040000, 0.040000]
Z [-0.040000, 0.126000]
X [-0.040000, 0.126000]
Y [-0.040000, 0.126000]
Z [-0.025000, 0.025000]
X [-0.025000, 0.025000]

SYMBOL: UNDEFINE
TIME: -3.95000E-02
MATERIALS: 1.



MAFIA

FRAME: 11	27/02/99 - 10:42:17	VERSION[V4.015]	HOM.DRD
			TESLA COUPLEUR H.O.M.

#ARROW


COORDINATES/M
FULL RANGE / WINDOW
X [-0.040000, 0.040000]
Y [-0.040000, 0.040000]
Z [-0.040000, 0.126000]
X [-0.040000, 0.079889]
Y [-0.040000, 0.079889]
Z [-0.025000, 0.025000]
X [0.0000, 0.0000]

SYMBOL = EDL_LAST_VOL
Z-MESHLINE: 21
CUT AT Z/M: 3.90313E-18
INTERPOLATE.= 1
LOGSCALE....= 0.
MAX ARROW = 2.15262E-02

4.000E-02

2.776E-17

-4.000E-02



-4.000E-02

1.994E-02

7.989E-02



MAFIA

FRAME: 13	27/02/99 - 10:42:17	VERSION[V4.015]	HOM.DRD
			TESLA COUPLEUR H.O.M.

#ARROW

COORDINATES / M
FULL RANGE / WINDOW
X: -0.040000, 0.040000
Y: -0.040000, 0.040000
Z: -0.040000, 0.126000
X: -0.040000, 0.126000
Y: -0.079889, 0.126000
Z: -0.025000, 0.025000
X: 0.0000, 0.0000

SYMBOL = EDI_LAST_VOL
Z-MESHLINE: 21
CUT AT Z/M: 3.90313E-16
INTERPOLATE: 1
LOGSCALE: 0
MAX ARROW = 8.03203E-02



MAFIA

FRAME: 15	28/02/99 - 19:15:35	VERSION[V4.015]	HOM.DRD
			TESLA COUPLEUR H.O.M.
[WGR2AM_OUT*[AFACOR]]/[KOAM_IN*[BFACOR]]			


P--:4015

#1DGRAPH

ORDINATE: SWR2KAM
COMPONENT: -
FIXED COORDINATES:
DIM.....MESHLINE

ABSCISSA: GEOMTIME_F_17
(BASE OF SWR2KAM)

REFERENCE COORDINATE: F
VARY.....MESHLINE
FROM 0
TO 131071



MAFIA

FRAME: 14	28/02/99 - 19:15:35	VERSION[V4.015]	HOM.DRD
			TESLA COUPLEUR H.O.M.
			[WGRIAM_OUT*[AFACOR]]/[KOAM_IN*[BFACOR]]

P--:4015


#1DGRAPH

ORDINATE: SWRIKAM
COMPONENT: -

FIXED COORDINATES:
DIM.....MESHLINE

ABSCISSA: GEOMTIME_F_17
(BASE OF SWRIKAM)

REFERENCE COORDINATE: P
VARY.....MESHLINE
FROM 0
TO 131071



MAFIA


FRAME: 66	22/02/99 - 11:22:38	VERSION[V4.015]	HOMS.DRD
			3D PLOT OF THE MATERIAL DISTRIBUTION IN THE MESH

M--:4015

#VOLUME

COORDINATES/M
FULL RANGE / WINDOW
X [-0.040000, 0.109000]
Y [-0.040000, 0.109000]
Z [-0.040000, 0.040000]
X [-0.040000, 0.040000]
Y [-0.025000, 0.025000]
Z [-0.025000, 0.025000]

SYMBOL: CCONE_1
TIME: 1.0000
MATERIALS: 1,




Y
X
Z

V
W
U

Eigenmode Calculation of RF-Structures using S-Parameters



- structure too complex to calculate eigenmodes directly
- subdivide structure and calculate S-parameters of each part
- define boundary conditions



- get S-parameter matrix of the whole structure
- calculate eigenmodes and -frequencies ...

A First Test

- two equal sections linked together: wave guide with iris
- calculate s-parameters



- $S_{11}, S_{12}, S_{22} \Rightarrow |S_{11}^{(t)}|, \varphi_{11}^{(t)}, \varphi_{12}^{(t)}$

The Eigenvalue Problem

- boundary condition: $a_1 = r_1(\omega)b_1$, $a_2 = r_2(\omega)b_2$
- $\Rightarrow$ find non-trivial solution of


$$\begin{pmatrix} b_1 \\ b_2 \end{pmatrix} = \begin{pmatrix} S_{11}^{(t)}(\omega) & S_{12}^{(t)}(\omega) \\ S_{21}^{(t)}(\omega) & S_{22}^{(t)}(\omega) \end{pmatrix} \begin{pmatrix} r_1(\omega) & 0 \\ 0 & r_2(\omega) \end{pmatrix} \begin{pmatrix} b_1 \\ b_2 \end{pmatrix}$$

- with (for instance) electric short: $r_1 = r_2 = -1$
- and assumptions: the structure is
 1. reciprocal: $S_{mn} = S_{nm}$
 2. loss-free: $\mathbf{S}^* \mathbf{S} = \mathbf{E}$
- $\Rightarrow$ resonance frequencies ω_0 are solutions of

$$\sin(\varphi_{12}^{(t)}(\omega_0)) - |S_{11}^{(t)}(\omega_0)| * \sin(\varphi_{11}^{(t)}(\omega_0) - \varphi_{12}^{(t)}(\omega_0)) = 0$$


- solve

$$\sin(\varphi_{12}^{(t)}(\omega_0)) = |S_{11}^{(t)}(\omega_0)| \sin(\varphi_{11}^{(t)}(\omega_0) - \varphi_{12}^{(t)}(\omega_0))$$



eigen frequencies:

S-parameters	MAFIA E-mod.	$\Delta\%$
1.243639 GHz	1.243016 GHz	0.50
1.283487 GHz	1.283967 GHz	-0.04
1.363857 GHz	1.363793 GHz	0.005
1.419875 GHz	1.420691 GHz	-0.06
1.461280 GHz	1.459711 GHz	0.11
1.588825 GHz	1.589970 GHz	-0.07



Prospects

- advantage
 - eigenmode calculation of complex structures possible
 - exploit symmetry of each subsection
 - “re-use” calculation of repeated subsections
- future plans: use this procedure on “real” structures like
 - TESLA-modules with cavities, beam pipes, coupler
 - bunch compressor section

Advanced Photon Source

TTF Undulator Vacuum Chamber Cleaning:

Flush rinse with 2% Ridoline-18* detergent in DI water

Immerse in ultrasonic bath for 10 minutes at 65° C
with 2% Ridoline-18 detergent in DI water.

Water is purified by a de-ionizing bed and an activated
carbon bed, then particle-filtered to 20 μ m.

Flush rinse with DI water.

The rinse water is filtered to 0.5 μ m by a particle filter

Rinse with ethyl alcohol.

Blow-dry with dry nitrogen that has been
filtered to 0.5 μ m by a particle filter

*Many tests were done in the early days of APS construction to
find the best detergent for cleaning aluminum. Ridoline-18 is an
alkaline detergent; it etches the native oxide and rebuilds the
thinnest oxide layer of any detergent we tested. It is also
environmentally friendly enough to pour down the drain.

Argonne Nat'l Laboratory

Advanced Photon Source

Lab Report

M. White

Electropolishing -

The chambers with BPMs were electropolished to eliminate burrs in the BPM holes.


Proprietary process - no details were given out.

Success at removing burrs from BPM holes was verified with a boroscope.

A sample of the electropolished profile remains at ANL.


It will be cut and the surface will be measured to determine whether the electropolishing process also decreased the surface roughness.

Chambers measured 24 Feb for packing crate. Should arrive at DESY in a couple of weeks.







4 Feb 99 Prep for BPM
Installation



~4.5 meters
if 3mm



107-4



ADP-5

Advanced Photon Source

Cavity Fabrication - Learning Process

Made two single-cell copper cavities.

Beta version of the new bead-pull system exists
is being used for cavity measurements
[next version will be better].

Making aluminum end and center salad bowls that can be
mechanically combined as desired to form a cavity.

Making two Type-1 Nb single-cell cavities.


Plan to make a RRR300 single-cell cavity
before end of the summer.




1.3-GHz 1-Cell Copper Cavity #1

Monopole Modes


Monopole	f (MHz)	(R/Q) Ω at $R_0 = 0.0$ m	Q	f(measured)	Q(measured)	(R/Q) Ω measured
TM0-EE- 1	1292.33	17.29	29490	1295.95	25900	10.51
TM0-EE- 2	2386.09	37.960	31510	2468.24	28900	26.30
TM0-EE- 3	2698.21	0.227	44230	2720.31	35900	
TM0-EE- 4	3314.54	0.026	26930	above cut-off	N/A	
TM0-EE- 5	3360.80	0.644	23940			



107-7



TP#1



107-8

Advanced Photon Source

Vacuum Seal Studies


Investigation of a gasketless vacuum sealing method is underway to see if it could be suitable for Nb cavities. In tests, the seals are able to go from cryogenic temperatures to 550C without problems. It could be very cost-efficient if it works.

Nb Material studies:

Ordered single-crystal Nb pieces - delivered at DESY soon.


Reference for lifetime and magnetic studies.





PRINCIPLE

Tube torque and metal friction on assembly are eliminated by transforming the standard perpendicular force into two balanced axial opposed forces.



ADVANTAGES

- Optimal conduit continuity
- No dead volume
- Metal-to-metal sealing (only on joining plane)
- Excellent performance at high pressure 9,425 PSI (650 bar) under Helium pressure and 27,530 PSI (1,900 bar) under oil pressure
- No metal-to-metal rubbing on assembly
- Multiple assembly and disassembly without loss of efficiency
- Easy assembly and disassembly (3 or 4 mm CHC key)
- No male and female end fittings
- No gasket
- Reduced foot print
- Axial tightening (no torque on the tubes)
- Accurate alignment of the glands by centering ring

Leak test: $< 1.10^{-10}$ atm.cm³/s Helium with the protection rings -100°C to +180°C degree and without protection rings, to 550°C. CETIM Report Recorder # 6022404/681/4A.

Two RHP fittings tested n° 6 Ø 1/4" and n° 16 Ø 3/8".

Temperature and pressure	Fitting RHP ref.	Leak atm.cm ³ /s
+20° C, 80 bars	N° 6	$< 1.10^{-10}$
+20° C, 200 bars	N° 6	$< 1.10^{-10}$
+180° C, 80 bars	N° 6	$< 1.10^{-10}$
+20° C, 80 bars	N° 16	$< 1.10^{-10}$
+20° C, 200 bars	N° 16	$< 1.10^{-10}$
+180° C, 80 bars	N° 16	$< 1.10^{-10}$

Tests were carried out after temperature has been kept stable for at least one hour.

Another test has been carried out for these 2 fittings at 650 bars, +20° C.

Temperature and pressure	Fitting RHP ref.	Leak atm.cm ³ /s
+20° C, 650 bars	N° 6	$< 1.10^{-10}$
+20° C, 650 bars	N° 16	$< 1.10^{-10}$

Tests were carried out after temperature has been kept stable for at least one hour.

3.3 HIGH PRESSURE OIL TEST (UP TO BURST)

RHP fitting N° 8 Ø 1/4"

Pressure (bars)	Observation
300	no detected leak
400	no detected leak
500	no detected leak
600	no detected leak
700	no detected leak
800	no detected leak
900	no detected leak
1000	no detected leak
1100	no detected leak
1200	no detected leak
1300	no detected leak
1400	no detected leak
1500	no detected leak
1600	no detected leak
1700	no detected leak
1800	no detected leak
1900	no detected leak

RHP fitting N° 18 Ø 3/8"

Pressure (bars)	Observation
300	no detected leak
400	no detected leak
500	no detected leak
600	no detected leak
700	no detected leak
800	no detected leak
900	no detected leak
1000	no detected leak
1100	no detected leak
1200	no detected leak
1300	no detected leak
1400	no detected leak
1500	no detected leak
1600	burst pipe

DYNAMIC TEST OF FLOWMECA KHP CONNECTION

Prepared by:



C.E.T.I.M. : 74 Route de la Jonelière - BP 957 - 44076 NANTES Cedex 03

1 WHERE WERE THE TESTS PERFORMED?

CETIM Mechanical Industries Technical Center. Tests have been carried out on March 25 th, 1994

FINAL REPORT RECORDER N° 6 022404/681/4A

2 HOW WERE THE TESTS CARRIED OUT?

2.1 LEAK TEST

Test has been carried out on a spectrometer type ASM181T (ALCATEL) under Helium pressure.
Fitting assembly was tested.

2.2 TEMPERATURE TEST

Test has been carried out on a PYROX feature type CETIM 911772.
(temperature scale: between - 150° C and + 300° C).
For higher temperatures, tests have been carried out on a PYROX feature type N° CETIM 901673.

3 THE TESTS

3.1 VACUUM TEST

3.1.1 VACUUM TESTS WITH PROTECTION RINGS

Two RHP fittings tested n°2 Ø 1/4" and n°12 Ø 3/8".

Temperature °C	Fitting RHP ref.	Leak dm ³ /s
+20° C	N° 2	< 1.10 ⁻¹⁰
-100° C	N° 2	< 1.10 ⁻¹⁰
+180° C	N° 2	< 1.10 ⁻¹⁰
+20° C	N° 12	< 1.10 ⁻¹⁰
-100° C	N° 12	< 1.10 ⁻¹⁰
+180° C	N° 12	< 1.10 ⁻¹⁰

Tests were carried out after temperature has been kept
stable for at least one hour.

3.1.2 VACUUM TEST WITHOUT PROTECTION RING

Two RHP fittings tested n°4 Ø 1/4" and n°14 Ø 3/8".

Temperature °C	Fitting RHP ref.	Leak dm ³ /s
+20° C	N° 4	< 1.10 ⁻¹⁰
-100° C	N° 4	< 1.10 ⁻¹⁰
+550° C	N° 4	< 1.10 ⁻¹⁰
+20° C	N° 14	< 1.10 ⁻¹⁰
-100° C	N° 14	< 1.10 ⁻¹⁰
+550° C	N° 14	< 1.10 ⁻¹⁰

Tests were carried out after temperature has been kept
stable for at least one hour.


DRAFT

Single Bunch Energy Spread in a TESLA Cryomodule

Alexandre Novokhatski, Martin Timm and Thomas Weiland
 Fachgebiet Theorie Elektromagnetischer Felder
 Technische Universität Darmstadt
 Schloßgartenstraße 8, D-64289, Darmstadt
 February 26, 1999

Abstract


The present paper is a compilation of results of the wake field calculation of single Gaussian bunches with different length ($700\mu\text{m}$, $250\mu\text{m}$ and $50\mu\text{m}$) in the TESLA Cryomodules. In order to take the transition dynamics into account, the wake fields are calculated in a sequence of two TESLA Cryomodules, including bellows and drift tubes. The single bunch energy spread is calculated as the rms-deviation from the average energy gain of the bunch. It is derived for the combination of accelerating voltage and wake fields. The energy spread is computed for acceleration with maximum energy gain. Furthermore the minimum energy spread achievable for different bunch charges and bunch length is calculated. The resulting phase and thus the energy gain at this phase are given.



TESLA cryomodule, cavity and bellows


Wakes in the TESLA cryomodules

Bunch: 50μ Distance between modules 7λ



Wakes in the cavities of the TESLA cryomodule

Bunch 250μ



1 Energy spread and Integral parameters of the Wake fields

The energy spread (squared) $(\Delta U)^2$ in the bunch is

$$(\Delta U)^2 = U_0^2(\Delta V)^2 + Q^2(\Delta W)^2 + 2U_0Q(\langle V(s)W(s) \rangle - \langle V \rangle \langle W \rangle)$$

The energy spread due to the accelerating voltage $(\Delta V)^2$

$$(\Delta V)^2 = \frac{1}{2}(1 - e^{-(k\sigma)^2})(1 - \cos(2\phi)e^{-(k\sigma)^2})$$

Integral parameters of the wake field:

The energy spread (squared) caused by the wake fields is

$$(\Delta W)^2 = \int_{-\infty}^{+\infty} q(s)W(s) - K_\sigma)^2 ds \quad (1)$$

Introducing the Cosine-Fourier part

$$I_{cos} = \int_{-\infty}^{+\infty} q(s)W(s)(\cos(ks) - e^{-(k\sigma)^2/2})ds \quad (2)$$

and the Sine-Fourier part

$$I_{sin} = \int_{-\infty}^{+\infty} q(s)W(s)\sin(ks)ds \quad (3)$$

we finally get the total energy spread

$$(\Delta U)^2 = U_0^2(\Delta V)^2 + Q^2(\Delta W)^2 + 2U_0Q(I_{cos}\cos(\phi) - I_{sin}\sin(\phi))$$

Integral parameters in [V/pC] for the wakes of 700 μ m and 250 μ m long Gaussian bunches in one cryomodule are given in table 1. The wakes of a 50 μ m long Gaussian bunch are given for first and second cryomodules in the same table. For the wavelength of the accelerating field $\lambda = 230.768$ nm was taken.

σ	k_σ	I_{wv}	I_{wv}	$\sqrt{(\Delta W)^2}$
700 μ	-98.33152	-0.2461643F-02	-0.8492748	47.49361
250 μ	-125.8672	-0.3346571E-03	-0.3944211	60.83610
50 μ (1)	-198.2546	-0.4340105E-04	-0.0960391	79.86720
50 μ (2)	-153.2351	-0.5752997E-05	-0.1107154	82.82798

Table 1: Integral parameters for the wakes of 700 μ m, 250 μ m and 50 μ m Gaussian bunches in the TESLA cryomodule

The relative energy spread $\Delta U/\langle U \rangle$ and the energy gain $\langle U \rangle$ upon the phase degree are shown in Fig.1 and Fig.2 for $U_0 = 120$ MeV, $\sigma = 250\mu$ m and $Q = 8nC$.

The same parameters, but for the charge of $Q = 1nC$ are shown in Fig.3 and Fig.4

From the pictures we can see, that there is an optimal phase, where the bunch gets the minimum energy spread. Energy distributions for such cases are shown on Fig.5($Q = 8nC$, $\phi = -32.5^\circ$) and Fig.6 ($Q = 1nC$, $\phi = -45^\circ$)

Even after compensation, the energy spread has still linear dependence, at least for 60% of the particles.




Figure 3: Relative energy spread.




Figure 4: Average energy gain.




Figure 1: Relative energy spread.




Figure 2: Average energy gain.




Figure 5: Energy gain distribution for $Q = 8nC$.




Figure 6: Energy gain distribution for $Q = 1nC$.

Table 2: Maximum energy gain and minimum energy spread of a $\sigma = 250\mu m$ bunch in a TESLA cryomodule. Charge $Q = 1nC$

Voltage MV	Phase	$\langle U \rangle$ MeV,	$\Delta U / \langle U \rangle \cdot 1000$
100	$\phi = 0$	99.872	0.6032
	$\phi = -4.9$	99.506	0.1655
120	$\phi = 0$	119.871	0.5017
	$\phi = -4.1$	119.564	0.1347
140	$\phi = 0$	139.871	0.4293
	$\phi = -3.5$	139.61	0.1128
160	$\phi = 0$	159.87	0.3751
	$\phi = -3$	159.651	0.0968
180	$\phi = 0$	179.87	0.3293
	$\phi = -2.7$	179.67	0.0841
200	$\phi = 0$	199.87	0.2993
	$\phi = -2.4$	199.694	0.0744
320	$\phi = 0$	319.867	0.1861
	$\phi = -1.5$	319.757	0.0429

Table 3: Maximum energy gain and minimum energy spread of a $\sigma = 250\mu m$ bunch in a TESLA cryomodule. Charge $Q = 8nC$.

Voltage MV	Phase	$\langle U \rangle$ MeV,	$\Delta U / \langle U \rangle \cdot 1000$
100	$\phi = 0$	98.991	4.9097
	$\phi = -39$	76.706	1.964
120	$\phi = 0$	118.99	4.083
	$\phi = -32.8$	99.859	1.477
140	$\phi = 0$	138.99	3.4949
	$\phi = -28.2$	122.373	1.1937
160	$\phi = 0$	158.989	3.0544
	$\phi = -24.6$	144.467	1.006
180	$\phi = 0$	178.989	2.712
	$\phi = -21.8$	166.117	0.8715
200	$\phi = 0$	198.988	2.4391
	$\phi = -19.6$	187.4	0.7696
320	$\phi = 0$	318.986	1.5192
	$\phi = -12.2$	311.759	0.4537




Application of Iris Model to different Tubes

TUD


● Circular Aperture

$$k^2 = \frac{\varepsilon}{\varepsilon - 1} \frac{2}{a\delta} \quad k_{loss} = \frac{Z_0 c}{2\pi a^2} H(k\sigma_z)$$




● Elliptical Aperture

$$k^2 = \frac{\varepsilon}{\varepsilon - 1} \cdot \frac{a+b}{ab} \cdot \frac{1}{\delta} \quad k_{loss} = \frac{Z_0 c}{2\pi ab} H(k\sigma_z)$$




● Rectangular Aperture

$$k^2 = \frac{\varepsilon}{\varepsilon - 1} \cdot \frac{a+b}{ab} \cdot \frac{1}{\delta} \quad k_{loss} = \frac{Z_0 c}{8ab} H(k\sigma_z)$$



Martin Timm

Darmstadt University of Technology




NOVO Thu Nov 5 18:39:10 1998 Bunch 0.250mm RxZ = 5.50x 7.51 Length= 890.01mm

113



Energyspread of 3D-Structures

TUD




Martin Timm

Darmstadt University of Technology



Lossfactor of 3D-Structures

TUD





114

rsity of Technology

Kundename: LIBA
 Abteilung: Service
 Bearbeiter: Dilger

20.03.98
 Meßobjekt: Stufe500
 Auftragsnummer:





Talstelle



TUD


Shifted Rectangle and 2 Periods Structure




115

Bunch center position and Energy loss


$K_{\phi 0}=12.5, I=290$



High Q. One frequency. Surface roughness wake.



116



TESLA Damping Ring

Parameters of the ring:

$$\sigma_{DR} = 9.5 \text{ mm}, Q = 5.8 nC$$

$$V_{RF} = 25 \text{ MV}, f_{RF} = 433 \text{ MHz}, k_{RF} \sigma_{DR} = 0.086$$

Parameters of the vacuum chamber:

$$L = 17 \text{ km}, 52 \times 28 \text{ mm}^2, \text{ roughness } \delta = 0.5 \mu$$

Roughness wake frequency parameter

$$k_0 \sigma_{DR} = 190$$

Intensity parameter


$$I_0 = \frac{Q W_0 L}{V_{RF} k_{RF} \sigma_{DR}} = \frac{Q Z_0 c L}{\pi a^2 V_{RF} k_{RF} \sigma_{DR}} = 4 \times 10^3$$

Estimation for threshold

$$I_0^{\text{th}} = 1.5 (k_0 \sigma_{DR})^2 = 54 \times 10^3 \quad (13.5 \text{ times larger})$$


Philomen
NEN Legnaro

			- Spinning from Planar disks - Spinning from deep drawn tubes - Spinning from flowturned tubes
DESY	1.3 GHz		
		- Spinning from planar disk { 250 RRR Nb reactor grade Nb - Spinning from deep drawn tubes (monocell after mechanical grinding; 5 cell in preparation)	
Jefferson lab	1.5 GHz		
		{ Nb clad Cu from disks (Plan to reduce internal cracks)	
KEK	1.3 GHz		
		{ 500 mm thick wall Nb cavities in program.	
Orsay	3 GHz		
	1.5 GHz		
		- Spinning onto an Al mandrel - Spinning onto a collapsible mandrel	
Genoa Univ.	3 GHz		
		Spinning of OFHC Cu monocells for Nb sputtering	
Saclay	1.5 GHz		



Test #1: after manufacturing tumbling for ≈ 90 hrs, $\approx 90 \mu\text{m}$ bcp, heat treatment at 800°C for 2 hrs, $70 \mu\text{m}$ bcp

Test #2: Heat treatment at 1200°C for ≈ 30 min, tumbling for ≈ 95 hrs, grinding of cracks at beam pipe, $\approx 80 \mu\text{m}$ bcp



Test #3: $\approx 234 \mu\text{m}$ bcp

Test # 6b: tumbling for ≈ 100 hrs, $80 \mu\text{m}$ bcp, heat treatment at 900°C for 1 1/2 hrs, $60 \mu\text{m}$ bcp, grinding of cracks at beam pipe, $50 \mu\text{m}$ bcp

Test #7c: $20 \mu\text{m}$ bcp, baking at 115°C for ≈ 40 hrs "in situ"

Undulator Status Report

1-3-88

J. Meigs, HASYLAB

Overview

Vacuum System - 2.4 hrs

Undulator - Mechanical

Magnetic Measurements 1. Undulator Power


Hot. Field tuning $\rightarrow$ skimming $\checkmark$




Vert. Field tuning $\rightarrow$ pole adjustment $\checkmark$

Quad tuning $\rightarrow$ Rectangular coil Helicity $\checkmark$

Identification of Quad Axis $\checkmark$

Time schedule 2. & 3. Hours





Four Magnet Focusing Undulator
(4MFU)





Fig 4

For constant field $\bar{B}$:

$$I_2 = \bar{B} \cdot \frac{x^2}{2} ; \text{ If } I_2 \approx 10 \text{ T mm}^2$$

$$x \approx 5 \text{ m}$$

$$\bar{B} \approx 0.8 \mu \text{ T}$$



S_j : Field on j th Pole [T]

p_i : Shift of i th Pole [mm]

a_{ij} : Norm. Field change on Pole j due to shift of pole i

$$\begin{aligned}
 S_1 &= a_0 \cdot p_1 + a_1 \cdot p_2 + a_2 \cdot p_3 + \dots + a_{i-1} \cdot p_i + \dots + a_{N-1} \cdot p_N \\
 S_2 &= a_{-1} \cdot p_1 + a_0 \cdot p_2 + a_1 \cdot p_3 + \dots + a_{i-2} \cdot p_i + \dots + a_{N-2} \cdot p_N \\
 S_3 &= a_{-2} \cdot p_1 + a_{-1} \cdot p_2 + a_0 \cdot p_3 + \dots + a_{i-3} \cdot p_i + \dots + a_{N-3} \cdot p_N \\
 &\vdots \\
 S_j &= a_{i-j} \cdot p_1 + a_{2-j} \cdot p_2 + a_{3-j} \cdot p_3 + \dots + a_{i-j} \cdot p_i + \dots + a_{N-j} \cdot p_N \\
 &\vdots \\
 S_N &= a_{1-N} \cdot p_1 + a_{2-N} \cdot p_2 + a_{3-N} \cdot p_3 + \dots + a_{i-N} \cdot p_i + \dots + a_0 \cdot p_N
 \end{aligned}$$









Fig 2


$$\frac{1}{2} \cdot \left(\frac{\lambda}{2\pi} \right) \cdot B_0 = 4.7 T_{mm}^2$$



40.4.05



The Rectangular Coil Method (RCM)



Flux through rectangular coil moving along y :

$$\Delta\Phi(y) = N \cdot L \cdot \int_{y_0}^y B_z(y') \cdot dy' = N \cdot L \cdot g \cdot \frac{1}{2} ((y - y_0)^2 - (y_a - y_0)^2)$$

$$B_z(y) = -g \cdot (y - y_0)$$


same coil moving along z :

$$\Delta\Phi(z) = N \cdot L \cdot \int_{z_0}^z B_y(z') \cdot dz' = N \cdot L \cdot g \cdot \frac{1}{2} ((z - z_0)^2 - (z_a - z_0)^2)$$

$$B_y(z) = g \cdot (z - z_0)$$

Polynomial Fit: $\Phi_{fit} = a \cdot (y, z)^2 + b \cdot (y, z) + c \Rightarrow (y_0, z_0) = -b/2 \cdot a ; g = 2 \cdot a / L \cdot N$

g	field gradient
L	effective quad length
y_a, z_a	Start point
y_0, z_0	quad center
N	Number of turns (49)
L_{Coil}	Coil length (327.6)
w_{Coil}	width of coil (330mm)



Time Schedule

1-3-88

1. Oscillator Module finished (good News)
2. & 3. Modules to be finished (bad News)

Estimated time for one Module :

5-6 weeks, now that all problems are solved

→ End of May 88 for all three
Modules to be finished

Collimator Section


Holger Schlarb

March 1, 1999

- Overview
- Status of the components
- Beam loss detection
- Installation schedule

Main Features of the Collimator System

Scheme collimator section





- Type: Two stage spoiler/absorber system
 - primary particles are intercepted by spoilers (Al)
 - secondary particles are absorbed by absorber system (Cu)
- Possible variation of beam energy $E_0 = 200\text{-}500 \text{ MeV}$
- Full performance of the collimator within an energy width of $\Delta E_0/E_0 = 3 \%$
- Diameter of spoilers $g = 6 \text{ mm}$
- $\leftrightarrow 8.3 \sigma_1$ at 200 MeV TTF-beam parameters
- Optic
 - design $\beta_{xy}^* = 1.25 \text{ m}$ at OTR-screen
 - $\rightarrow$ maximum transition
 - functionality of collimator independent of the beam optic
 - maximum variation of beam cross-section at the OTR-screen $\sigma_1^{max}/\sigma_1^{min} \geq 5$ for all energies
 - $\rightarrow$ accurate measurement of β -function

127



Collimator System



01.11.98





— Undulator — Dipole — Quadrupole — Sextupole




Schnitt B-B. (M 1:20)









Spoiler 1




Spoiler 2












Absorber 1



133

Absorbe α



134

Alle Kanten gebrochen


☒ 10 ☒ 15

Original


[illegible]

Absorberteilstück 2

$z=0$
 $z=560$





Absorber 3



Photomultiplier signal versus current

Photomultiplier Voltage $U = 1.1 \text{ kV}$
 Number of bunches $N = 10$
 Number of lead bricks $M = 1 \text{ (5 cm)}$
 Screen 1EXPI





Electron Diagnostics for FEL

Physics requirements and expected performance

Pedro Castro / MPY

1. Beam current monitors
2. Beam position monitors
3. Transverse emittance monitors
4. Bunch length monitors

Beam transmission

Danger:


- high peak energy losses in collimators
 —→ cracks in material
 (collimator chamber with a minimum of $d=6$ mm)
- irradiation of permanent magnets
 —→ loss of magnetization
 (undulator chamber: $d=9.5$ mm and 15 m long)

Requirements:

- meas. of transmission loss up to 1%
- fast inhibit signal if transmission losses

Saclay current monitors


J. Fuselliu, J.M. Joly, M. Jablonka/Saclay



- were designed for injector 1, adapted to 1 MHz
- lab. test resolution 0.1 nC, with beam >0.1 nC
- 9 MHz: it would require change toroids

Fast differential security system

- works at 100 kHz (every 10 bunches)
- between pairs of toroids, for example: T3-T7, T4-T6
- if diff. > 0.15 nC during 30 bunches. stop laser in 5 μ s
- first test in July



Beam trajectory

Needed:

- for collimation of beam halo: centering of beam at spoilers ~ 0.2 - 0.5 mm
- for amplification of photon beam (SASE): beam alignment along undulator ~ 10 - 20 μ m

Requirements:


- high accuracy on absolute beam position
- high resolution + beam based alignment

Scheme:

- BPMs in undulator

- diagnostic blocks $\rightarrow$ absolute reference

- other BPMs




BPMs IN UNDULATOR


Requirement: 1-2 μm resolution (averaged over one pulse)

Vacuum chamber

U. Hahn/Argonne



Undulator vacuum chamber




141

Argonne/HahnLab

TTFL-FEL: Electrostatic BPM Pickup

Cross-section of a couple of opposite electrodes



Coaxial line monitor

M. Wendt/DESY

- number: 20 at undulator mod. 1 and 2
- expected resolution: 20 μm per single bunch
- 1-8 nC ok, amplifier included for < 1 nC
- 2 signals to ADC: need digital conversion to x,y
- installation in Argonne: ready
- electronics: in summer

Wave guide monitor

T. Kamps, R. Lorenz et al./DESY-Zeuthen

- number: 10 at undulator mod. 3
- expected resolution: few μm
- ok for 9 MHz
- 4 signals to ADC: current measurement possible

New design:

- mechanics: new wave guide-coax. adapter
→ robust mechanical pieces

Measurements of prototype in S-band (1 nC, for single bunches):

- linear range ± 1 mm
- ~ 50 μm resolution limited by 8-bit ADC of scope

Measurement of coupling between slots:


- coupling similar as in prototype
- slots in two BPMs have mechanical defects, coupling a factor 100 larger:
→ large error on absolute position
→ however, resolution should be ~ 10 μm

Installation:

- vacuum chamber Argonne → DESY, March
- vacuum preparation, 1-2 weeks
- electronics

Beam Trajectory monitor


J.S.T. Ng, S. Roth/DESY



- experimental device
- number: 1 at undulator mod. 3
- range ± 500 μm
- position resolution ~ 10 μm
- absolute pos. depends on alignment hole-detector

Diagnostic Block

U. Hahn/Argonne, H. Rüter, G. Schmidt/DESY



Function: High accuracy absolute beam position and absolute beam profile

- number: 4 diagnostic blocks
- length = 300 mm
- has hor. and ver. wire scanners and a cavity BPM
- installation: mid-April

Wire scanner

G. Schmidt, H. Schultz, M. Werner, K. Wittenburg et al./DESY


- relative position 1 μm with optical ruler
- absolute position $\sim 15 \mu\text{m}$ against undulator reference


Detection:

- (1) lead glass detector with photo-multiplier at the end of the linac
- (1) plastic scintillator with photo-multiplier at each monitor block
- (2) current on the conducting wire (due to secondary electron emission)


G. Schmidt

Cross section of the Diagnostic Block





• Principles



- (3) Future option: photo diode to measure reflected photons from the FEL radiation on the wire (only vertical direction through the window below)

Problem: Heat load on the wire

- with 8 nC : wire survives only few hundreds μ s
- solution: operate with short pulses or low bunch current

- full FEL power: at the last block: sublimation of wire material (operation limited to 0.1 nC)

Solution: 3 wires per frame (spares)

Cavity BPM


R. Lorenz/DESY-Zeuthen, S. Sabah/TU-Berlin

- expected resolution 1 μ m (for single bunches)
- current measurements
- electronics installation: ready for March

OTHER BPMs

Cold cavity monitor

R. Lorenz/DESY-Zeuthen




- number: 2 in acc. module 2 and 3
- expected: 10-20 μ m resolution (averaged over one pulse)

Problem:

- no self-calibration on beam current (work in progress with tests in BPM "3BC2")

Reentrant cavity monitor


M. Lalot, C. Magne, J. Novo, B. Phung/Saclay



- number: 2 at spoiler locations
- resol. $\sim 10 \mu$ m (meas. with beam at 3 nC)
- bunch charge range 1-8 nC
- up to 3 MHz (for 9 MHz needs change of electronics)
- installation: electronics: July and August

Strip-line monitor

F. Tazzioli et al./INFN



- number: 3 behind undulator
- resol. $\sim 20 \mu\text{m}$
- bunch charge range 1-8 nC


Beam transverse emittance - Optics

Needed:

- for collimation of beam halo: 90° phase advance between spoilers
- β matching linac - undulator

Instrumentation:

- OTR and view screen
- resolution of camera: pixel $20 \times 20 \mu\text{m}$ (387x256 pixels)
- resolution of very small spots limited by diffraction
- Wire-scanners in diagnostic blocks




747

TECHNIQUES


Quadrupole scan

M. Castellano et al./INFN



Phase-space tomography

M. Geitz/DESY



- to get good resolution: 18 rotations in steps of 10°
- intrinsic errors of tomography: 10%(symmetric) to 30%(non-sym.)

- measurement time: ~ 20 min.
- systematic errors: beam jitter, quad. field errors, screen calibration $\rightarrow 50\%$
- problem: beam dispersion
 - measure dispersion
 - correct with dispersion bumps

Bunch length

Needed

- large charge density for SASE

Interferometry with OTR light

M. Geitz et al./DESY

Coherent light emitted by the beam when crossing the OTR screen.

Detectors:

- Pyro-electro det.: interferogram in ~ 30 min.
- Josephson junction det. : voltage scan in few min.


Freq. range 100-1500 GHz, i.e. 3 to 0.2 nm

Long. phase-space tomography

M. Geitz et al./DESY

Rotation of long. phase-space


- at IBC2 screen: changing phase cav. 8 in module 1
- at IEXP3 screen: changing phase of module 2 or 3
- first tests: this week #8



Intensity interferometry of spontaneous synchrotron light

J. Fink-Finowicki, J. Krzywinski, L. Plucinski, R. Sobierajski/

IP PAS-Warsaw



Synchrotron light emitted at spectrometer

- experimental technique
- no cut-off freq. effects
- no systematic errors
- for FEL-parameters and over 1000 bunches: 10% resolution

Photon diagnostics

J. Feldhaus, HASYLAB at DESY

Photon beam characterization

- Overview
- Status
- Schedule

1. Total flux of each photon pulse

spontaneous radiation: 0.2 μJ - P-Si Schottky diodes
FEL at saturation (70 nm): 0.4 mJ - thermo-electric detector

2. Beam size and angular distribution

~5 mm diameter at ~1 mm resolution - pinholes
- fast thermopile matrix
- PbWO_4 crystal + CCD

3. Spectral distribution of individual pulses

spont. radiation at low resolution 1 m NIM, 1200 l/mm, b.i. CCD
FEL fine structure at high resolution 3600 l/mm, ICCD

4. Time structure

bunch length: T ~ 1 ps - autocorrelation exp. (Jülich)
fine structure: $\Delta t \sim 10$ fs - crosscorrelation exp. (Jena)



5. Radiation damage of optical components


peak power density $10^9 - 10^{16} \text{ W/cm}^2$ special experiment using
focusing mirror and various
detectors (Warszawa)

69


HASYLAB
Univ. HH
LEPAM, Warsaw
Bablin City Univ.
FZ Jülich
Univ. Jena

Photon beam diagnostics






Saturation of the Pt-Si photodiode



Approximated micropulse energies at
 $527\mu\text{m}$ wavelength
 (2. Harmonics of a Nd:YLF laser)
 $U_{\text{rev}}=12\text{ V}$

Thermopile detector



YBa₂Cu₃O_{7-δ} film (35... 500 nm)
on a SrTiO₃ substrate



$$\lambda = 0.5 \cdot 10^{-6} \cdot \frac{1}{\sin(\theta)} \Rightarrow \frac{1}{\lambda} = \frac{1}{0.5 \cdot 10^{-6} \cdot \sin(\theta)}$$

Wavelength



$\lambda = 0.5 \cdot 10^{-6} \cdot \sin(\theta)$

S. Zeuner et al., Appl. Phys. Lett. 66, 1833 (1995)


Fast thermopile matrix detector




4*4 matrix detector (prototype)




Piezo-actuator



TEMPORAL STRUCTURE



Cross correlation experiment (Unijena)



delay $\tau = t_2 - t_1 = \frac{2x}{c} \sin \alpha$

(1) total delay across w : $T = \frac{2w}{c} \tan \alpha = 2 \text{ ps}$

$w = 2 \text{ mm} \Rightarrow \alpha \approx 8.5^\circ$


detector resolution: $20 \mu\text{m} \rightarrow$ time resolution: 20 fs

(2) high resolution: e.g. $1 \text{ fs} / 20 \mu\text{m} \rightarrow \alpha \approx 0.43^\circ$

$\rightarrow$ total range cross beam: 100 fs

- very long mirrors

- large distance (78 m lid!)



Schedule for photon diagnostics

Vacuum

pre-assembly, test	4 weeks in March
cleaning, final assembly in cleanroom	4 weeks in May
installation	2 weeks in June

Detectors

delivery, tests	March / April
assembly, tests	April

Monochromator

dismounting from HASYLAB beamline	1st week in April
re-configuration, tests, calibration	April / May
installation	June

Cabling for motors and signals

March / April

Computer control

hardware configuration	May
software	May / June
installation, tests	June

WORKING GROUP CAVITIES

I - Superstructure

- Parameters, general
 - W-G. Coupler
 - W-G. Coupler
- M. Sekulovics
 H. Dulius
 A. Zavadsev

II - Trapped modes

- Simulation + tests in 3-cell
 - Measurements on modules
 - Measurements in 4 cavities
 - Beam experiments
- F. Harbauer
 H. Glöckle
 N. Balcer
 N. Balcer

III - Cavity fabrication techniques

- Activities at Legnano
 - " at IPN Orsay
 - " at LAL Orsay
- E. Pelucien
 M. Foucaud
 L. Grandjean

IV - R/D

- E.P. CERN/DESY/SLAC
 - Measurements at Wuppertal
- L. Lefe
 G. Hüter

TRAPPED MODES

- Experiments with beam July 98 for 404: Unexpected mode at 2.585 GHz in one cavity of module 1
- Calculations, Measurements on modules 1 and 2 - Measurements on cavities
- Experiments with beam (August II) in cavity #3 of module 1 and #5 of mod. 2

Some facts:

- in cavity 3 (1) and 5 (2) there were shifts at a frequency ~ 2.58 GHz and are poorly damped.
- Comparison with other cavities in the same pair band $\rightarrow$ look as additional modes
- Transmission thru a chain of 3 cavities similar in mod 1 and mod 2 - Difficult to understand.
- Varying the length of the beam tube has large influence on field pattern (calculated and measurement)

SUPERSTRUCTURES

Build and test with beam a superstructure: 4×7 -cell.

Best estimate = 1st quarter 2001.

Need:

- New tuners
- New HOM coupler
 - = will use Plunger b/w cavities
 - = Test with existing Power Coupler
- Individual cavities, held in V cryostat
- Installation in a module similar to present design.

* Test with beam necessary:

- Correct acceleration
 - (LLRF - Energy dispersion)
 - HOM, trapped modes
- Need moderate Eacc (~10 MV/u)

W-G. Input Couplers

Discussion on some parameters:

- 1 coupler / 4 cavities
- Fixed coupling (adjusted for wup. beam power: $\approx 210^6$)
- Designed for the 700 cell parameters
 - $\Rightarrow P \approx 1.3 \text{ MW}$

• 2 designs of WG Coupler presented (see 11 to work on coax coupler)

1. Elliptical WG -

- window method from beam by 'wall' or 'diverge'
- calculation of RF risk
 - heat load

2. Rectangular WG

- window in pill box configuration

{ The better design the WG goes straight to the outside

CAVITY FABRICATION TECHNIQUES

I. Spinning - E. Pelletier

- Several cavities for different labs.
- Importance of grinding of cracks
- Spinning better than hydrof. for Cu cavities (Nb/Cu)

II. Cu deposition of Nb cavities - R. Fouaidy

- Several cavities under preparation
- Systematic studies on sample
- Role of bonding alloy.

III. Hydroforming - L. Grandjean

- 2-cell, 8-Band, RRR 40, $\frac{P_{eq}}{P_{ir}} = 1,3$
- Hot hydroforming: test of deformation
- Equipment for diagnostic.

Conclusion - Questions

- We need more calculations (3D?) and measurements (on several cavities)
- Influence of beam tube? acts as a resonator?
- Model of 'superstructure' for dipole modes?
- Are there other modes?
- Comparison for TESLA and FEL of the distance of real modes.

- Beam experiment are important
 - Easy with module I, good location for further tests
 - Exper. easier with 54 MHz beam and charge modulation
- $\Rightarrow$ work on lasers.

TESLA Waveguide Coupler


J.Boster, J.Dicke, M.Dohlius, A.Gamp, H. Hartwig, K.Jin, A.Jöstingmeier,
C.Martens, V.Kaljuzhny, S.Yargin, A.Zavadsev

1. Versions
2. Elliptical Waveguide
3. Windows
4. Integrated Waveguide-Coupler / Window
5. *Tuning*

Martin Dohlus Deutsches Elektronen Synchrotron Mar.99


1. Versions

version 0: coupler for 2*28 cells



Report: TESLA 99-01

2. Elliptical Waveguide



$$f_{\text{cutoff}} = 1.051 \text{ GHz}$$

$$f_0 = 1.3 \text{ GHz}$$


$$\max \{ \bar{E} \}_{P=1 \text{ MW}} = 449 \text{ kV/m}$$

$$\alpha = 8.71 \cdot 10^{-4} \text{ N/m for } \kappa = 58 \cdot 10^6 \text{ 1/}(\Omega\text{m})$$


$$\alpha = 2.10 \cdot 10^{-4} \text{ N/m for } \kappa = 10^9 \text{ 1/}(\Omega\text{m})$$

e.g. $P = 1 \text{ MW}$, $t = 1.4 \text{ ms}$, $f_{\text{rep}} = 5 \text{ Hz}$, copper(40 K) $\Rightarrow 2.5 \text{ W/m}$

version 1: coupler with wall and straight waveguide




version 2: coupler with “chicane” and straight waveguide



Martin Dohlus Deutsches Elektronen Synchrotron Mar.99



4. Integrated Waveguide-Coupler / Window

4.1 Version 1: coupler with wall and straight waveguide + integrated window




$Q_{\text{ext}} = 3.1 \cdot 10^6$
ceramic in SW minimum
for $l \ll l_{\text{fill}}$

Problems:
“resonator” losses
kick: $\vec{K} = 16.0 \text{ kV } \vec{e}_x + 11 \text{ kV } \vec{e}_y$




Martin Dohlus Deutsches Elektronen Synchrotron Mar.99

163



4.2 Version 2: coupler with "chicane" and straight waveguide + integrated window




$Q_{\text{ext}} \approx 3.1 \cdot 10^6$
ceramic in SW minimum
for $t \ll t_{\text{fil}}$

a) Fields


$E_{\text{max}} = 0.75 \cdot 10^6 \text{ V/m} \approx 3.5 E_0$

214 kW $\leftarrow E_{\text{re}}$








$B_{\text{max}} = 1.6 \cdot 10^{-3} \text{ T}$

B_{im}



$|B| < 0.38 \cdot 10^{-3} \text{ T}$





kick

$$\int F_y dz = (0.7 - j 7.7) kV$$



c) Losses

setup 1:





2 K losses: 0.061 W, 0.093 W, 0.162 W
4 K losses (6.5 K): 1.74 W, 1.96 W, 2.43 W

setup 2:



2 K losses: 0.094 W, 0.101 W, 0.124 W
4 K losses (6.5 K): 1.98 W, 2.16 W, 2.54 W

setup 3:






2 K losses: (1.091 W, 0.101 W, 0.124 W
4 K losses (6.5 K): (1.77 W, 0.99 W, 1.46 W



3.6 Double Window

Normalized Transverse
E-Field in Waveguide ($r = -1 .. 0$)

$E_0(P = 1 MW) = 0.449 MV/m$



setup 4: (double window, estimated)



2 K losses: 0.091 W, 0.101 W, 0.122 W
4 K losses (6.5 K): 0.77 W, 0.87 W, 1.09 W

5. Tuning

5.1 Coupler with adjustable coupling: ???

5.2 External Tuning

design: $Q_{\text{ext}} = 3.10 \cdot 10^6$


e.g. wrong coupling: beam pipe 5 mm too long $\rightarrow Q_{\text{ext}} = 5.44 \cdot 10^6$

beam pipe 5 mm too short $\rightarrow Q_{\text{ext}} = 1.80 \cdot 10^6$

reflection by external tuner: $|r| = \left| \frac{Q_{\text{ext}}^{\text{design}} - Q_{\text{ext}}}{Q_{\text{ext}}^{\text{design}} + Q_{\text{ext}}} \right|$ example $|r| = 0.27$

field distribution in window

$r = -0.27, 0, +0.27$ $P_{\text{forward}} = \text{const}$



Martin Dohlus Deutsches Elektronen Synchrotron Mar.99


DOHLUS/MARTINDOHLUS, MAR99/98/18

Measure of the superheating magnetic field

C.Thomas (PhD), G.Bienvenu, M.Fouaidy*, H.Sun**

- Direct measuring H_{sh} in High Power RF Short Pulsed mode
- $H_{sh} = f(\lambda/\xi) H_c$
 - Measuring λ on cavity

*IPNO **Visitor



3 GHz Nb CAVITIES
λ EXPERIMENTAL DETERMINATION

Theory :

London ->

$$\lambda_L = \frac{\lambda_{L0}}{\sqrt{1-t^4}}$$

GL -> for clean supra

$$\lambda = \frac{\lambda_{L0}}{\sqrt{2(1-t)}}$$

for dirty supra

$$\lambda = \frac{\lambda_{L0}}{\sqrt{2(1-t)}} \sqrt{\frac{\xi_0}{1.33l}}$$


Method :

Variation of the reactance



$$\Delta\lambda = \frac{2G}{\mu_0} \left(\frac{\omega_0 - \omega}{\omega_0^2} \right)$$



Evolution of experimental frequency as a function of temperature



Preliminary Results



Fit of the experimental $\Delta\lambda$ by Ginzburg-Landau model

Dirty case : $31 < l(\text{nm}) < 119$

$12 < RRR < 44$



Characteristic of the direct
measurement of H_{sh}

$$P_I < 5 \text{ MW}$$

$$T_{RF} = 4.5 \mu s$$

$$f = 3 \text{ GHz}$$

$$Q_{ext} \in [30000 ; 10^7]$$



IPN Orsay - SEA Collaboration

**SURFACE RESISTANCE MEASUREMENT OF SUPERCONDUCTING SAMPLES
WITH VACUUM INSULATED THERMOMETERS**

M. Ribeau, S. Chel, J.P. Charrier, M. Juillard SEA/DAPNIA/DSM CEA
M. Fouaidy IPN Orsay (CNRS/IN2P3-Univ. Paris XI)

Abstract

A cylindrical niobium TE011 cavity is used at Saclay for measuring, with a differential method, the overall surface resistance R_s of superconducting thin films (Nb or NbTiN) sputtered on removable copper disks (Nb/Cu samples). An alternative device, for Nb/Cu samples RF properties characterization purpose was developed. The main feature of this technique, which is based on thermometry, is an improved accuracy and sensitivity as compared to the usual method. The thermometric method, conjointly with a thermal model, is used for the measurement of the absolute R_s distribution on superconducting thin film samples. Precise calibration of test-samples RF losses is performed by means of a removable DC heater and temperature sensors pressed on the back of the disk and placed in a vacuum chamber. This new facility allows in-situ determination of all the thermal parameters involved in the model (substrate thermal conductivity and heat transfer coefficient at the solid-LHe interface). The thermometric technique was first successfully validated and RF properties of several Nb/Cu sample was studied with this new device. Interesting data was obtained and analyzed. In particular, the effect of the copper substrate surface conditions on the Nb/Cu sample RF properties was investigated and the corresponding results discussed.

Motivations for developing such an instrument

● Why did we need to develop a new instrument for measuring the RF surface resistance (R_s) of sputtered superconducting films with such SRF cavity ?

1) In order to improve the accuracy and the sensitivity of R_s measurement, because the lack of accuracy and sensitivity at 4.2 K in the case of measurements performed by the usual so-called end plate replacement method !

2) Measure exclusively the test-sample RF losses by excluding any extra RF losses :

→ Some of these extra RF losses are inherent to the 'classical' method namely : rest of the cavity, indium gasket, RF coupling loops.

→ Potentially, anomalous RF losses induced by Field Emitted electron impacting area other than the sample .

● Purpose :

⊗ improve the accuracy, reliability and sensitivity of R_s measurement .

⊗ Thorough and precise RF characterization of sputtered Nb and NbTiN films onto Copper substrate :

➤ Study the effect of sputtering process parameters and substrate surface preparation on the films RF properties in order to improve the superconducting sample performance and master the technology.

➤ Investigate $R_s(T)$ in the temperature range : 1.6K - 4.5 K

➤ Study R_s spatial distribution on the sample .

⊗ Progress in the understanding of SRF properties and get more insight into superconducting film physics and develop new superconducting material interesting for accelerators applications.

● Main advantages of this method


➔ Absolute, direct and local method as compared to the usual RF technique.

➔ no reference disk needed (save time, no assumption concerning the rest of the Niobium cavity RF surface).


➔ Vacuum insulation and hence a precise temperature measurement (the thermometers are in contact with a non-wetted solid wall) .

➔ in-situ measurement of substrate thermal parameters.

Shéma de principe




Profil radial de température (T-T_{bain}) sur le disque (P_{STAT}=P_{Rf}=242mW)



$V_r > 40 \text{ mm}$ $P_{\text{STAT}} = P_{\text{Rf}} \Rightarrow \Delta T_{\text{STAT}} = \Delta T_{\text{Rf}}$
 $\Rightarrow$ détermination via la relation (1) des coefficients (R_0, R_1, R_2)


COLLABORATION IPN Orsay - SEA/DAPNIA/DSM/CEA
M. FOUAIDY, M. RIBEAUDEAU




EXPERIMENTAL SET-UP

<http://ipweb.in2p3.fr/~yaniche/>

571





Rs vs B measurement of Nb Films on Cu substrate (T=1.7K, f=4GHz)



→ The Nb film RF surface resistance increases with the substrate roughness.

① →

20 μm 50 μm 


SAMPLE# D62
(electropolishing)

D57
(SN2 bath)

D58
(SSCR2 bath)

D60
(SN6 bath)


② →

5 μm 

1 Copper substrate before coating with the Nb film - 2 Nb film (1.5 μm) coating on copper substrate (magnetron sputtering)


Résultats HF à $T_b=4,2\text{K}$

1/Validation de la méthode de mesure : comparaison à bas champ de R_s (Nb massif) par méthode HF et thermométrie



⇒ Valeurs comparables entre les deux méthodes de mesures

Rs vs B measurement of Nb Films on Cu substrate (T=1.7K , f=5.6GHz)



M.FOUAIDY for IPN Orsay, LAL, SEA/CE Saclay collaboration

SRF NIOBIUM CAVITIES STIFFENING BY THERMAL SPRAYED COATING

S.Bousson, A.Carnette, M.Durante, M.Fouaidy, H.Gassot, N.Hammoudi, T.Junquera, J.C.Lescornet, J.Lestrel, IPN Orsay - France

J.L.Borne, J.C.Bourdon, L.Grandshire, A.Thibault, LAL Orsay - France

C.Antoine, SEA CE Saclay - France

MAIN OBJECTIVES

- ⊗ Cavity stiffening in order to reduce frequency shift Δf induced by Lorentz forces
- ⊗ Develop an alternate scheme to the actual Nb stiffening rings which are no more efficient for $E_{acc} \geq 28$ MV/m (i.e $\Delta f > 434$ Hz = TESLA cavity BW @ $Q_{ext} = 3.10^9$)
- ⊗ Possible gain in cavity thermal performance ?
- ⊗ Reliability and cost reduction ?

MAJOR ISSUES OF THE R&D PROGRAM

① Compare different thermal spraying techniques.

→ Focus on 4 thermal spraying methods in collaboration with 2 French Laboratories .

- 1) Vacuum Plasma Spraying (VPS),
- 2) Atmospheric Plasma Spraying (APS) ,
- 3) Controlled Atmosphere Plasma Spraying (CAPS) ,
- 4) High Velocity Oxy-Fuel Spraying (HVOF)

② Material characterization on ^{samples} specimens

- Metallurgy, microstructure, porosity
- Mechanical properties and thermal properties,

③ Numerical simulation of cavity mechanical and thermal behaviour.

④ Fabrication and test of monocell and multicell cavities

- 354 Hz monocell cavities
- 5 1.36 GHz monocell cavities
- Nb : Heraeus : thickness : 4 mm RRR ≈ 130

¹ M.FOUAIDY TESLA Meeting, Desy Hamburg March 1999

Fabrication and test of monocell and multicell cavities



- 3GHz cavities (number: 7)
- Five 1.3GHz monocelle cavities
- Two 1.3GHz TriCell cavities
- Nb sheets supplied by Heraeus RRR = 140
Thickness : 4mm
- Coat cavities with thermally sprayed deposit
- coating thickness : 2-3mm
- Material : to be decided After Mechanical and thermal tests on samples
- coating technique : APS or VPS or HVOF
To be chosen according to several criteria:
 - High Bonding strength
 - High Young modulus
 - Good thermal performance
 - Best mechanical properties (low Temp.)

S. Bousson
IPN Orsay (France)
13/1/99


Test of copper coated 3 GHz monocell cavities


Cavity # Nb RRR 40 e=0.5 mm	1			2			3			4			5		
	E _{max}	Q ₀	Rem.	E _{max}	Q ₀	Rem.	E _{max}	Q ₀	Rem.	E _{max}	Q ₀	Rem.	E _{max}	Q ₀	Rem.
First Test	4	$5 \cdot 10^3$ à $3 \cdot 10^3$	Quench	12	$2 \cdot 10^3$ à $2 \cdot 10^3$	Quench	*	*	not tested	*	*	not tested	*	*	not tested
Heat treated 800°C	11	$5 \cdot 10^3$ à $3 \cdot 10^3$	Quench	16	$4 \cdot 10^3$ à $3 \cdot 10^3$	Quench	yes	yes	not tested	no	no	not tested	no	no	not tested
Heat treated 1200°C	12.5	$3 \cdot 10^3$ à $2 \cdot 10^3$	X-rays Quench	<u>24.5</u>	$4 \cdot 10^3$ à $1 \cdot 10^3$	X-rays Quench	no	no	not tested	16.5	$2 \cdot 10^3$ à $1 \cdot 10^3$	X-rays Quench	14.6	$4 \cdot 10^3$ à $2 \cdot 10^3$	Q-Switch Quench
Copper Coating (2 mm)		01/99			01/99		10	$4 \cdot 10^3$ à $3 \cdot 10^3$	Quench	16.5	$3 \cdot 10^3$ à $2 \cdot 10^3$	Quench	13.5	$2 \cdot 10^3$ à $2 \cdot 10^3$	Quench

FREQUENCY SHIFT



COPPER COATING by PLASMA SPRAY:
A New Method to Improve the Stiffening of TESLA Cavities




MATERIALS	IPN Diff. Thermal contraction	Residual Stresses (ENSAM)	Cracks prep. Thermal shock Microscope (ENSAM)	Young Modulus at 300K (E)	Simulate Cavity Tuning	Porosity
	CuAgZr } L ALTi... } P Tubes } S	CuAgZr } L ALTi... } P Tubes } S	CuAgZr } L ALTi... } P Tubes } S	Measure Hardness Estimate E	Two half cell (Diabolo)	CuAgZr LPPS Cu HVOF ALTi LPPS
STRUCTURES	Cu : HVOF Tube	Cu HVOF Tube	Cu : HVOF Tube	• LAL ? • LEREHPS (Belfort)		Ti LPPS, APS Cu APS Tubes
			FLAT SAMPLES	ALTi... LPPS Cu: HVOF Cu: APS (?) Ti (LPS, APS) Traction exp. Flexion ≠ Lab.	FLAT SAMPLES	Cu APS Ti LPPS, APS
THERMAL PROPERTIES	OVERALL Ther. Resist.	THERMAL CONDUCTIVITY		Permeability		
	ALTi... LPPS → ? Cu : HVOF → ? Cu : APS → ? Ti LPPS, APS → ?	Depend on the previous tests ?		OK OK OK OK		

M.FOUAIDY

COMPARISON OF DIFFERENT SPRAYING TECHNIQUES

Technique	Particles velocity, Temperature and spraying distance	Atmosphere	Porosity (%)	Bond strength for metals (MPa)	Coating thickness (μ m)	Powder particle size (μ m)	Remarks
Flame Spraying (F.S)	80-100 m/s 3000-3500 K d : 120-250 mm	air	10-20 0 for self- fluxing coating	30 (Typical) 60-70 (Max.)	100-2500	5-100	Inflight Particle Oxidation (IPO), trapped air...
Atmospheric Plasma Spraying (APS)	120-350 m/s (400-550 m/s) 2000-3500 K d : 50-150 mm	air	1-7 could be greater	>70 bonding alloys	50-500 2500 obtained	5-100	IPO, Oxygen content up to 2% density $\approx$ 80% Bulk inhomogeneous
Vacuum Plasma Spraying (VPS or LPPS)	Up to Mach 3 2000-3500 K d : 300-400 mm	Inert gas Ar at $\sim$ 50 mBar	1-2	>80	150-500	5-20	Oxygen content less than 500 ppm density $\approx$ 95% Bulk homogeneous high bonding strength
Controlled Atmosphere Plasma Spraying (CAPS)	80-100 m/s 2000-3000 K d : 100-250 mm	Ar, He, N ₂ 1-5 Bar	1-7	20-45	50-500	5-100	low bonding strength
D-Gun Spraying	750-900 m/s 3500-4500K d $\approx$ 100 mm	Air	0.5-1	>70-80	300	5-60	high bonding strength
High Velocity Oxy-Fuel Spraying (HVOF)	< 1500 m/s 1500-2500 K d : 150-300 mm	Air	<1	up to 90	100-300	5-45	high bonding strength




Atmospheric Plasma Sprayed Coating Build-up

CHARACTERIZATION OF PLASMA SPRAYED COPPER COATINGS

○ microstructure analysis by SEM and image processing :

- get data on the structure morphology, pores dimension distribution, microchannels geometry and flow pattern, interface region analysis (inter-splat area and Nb/Cu interface), coating porosity....
- optimize the spraying parameters which have an influence on the coating properties



Micrograph of Cu coating deposited onto a Nb substrate
(Atmospheric Plasma Sprayed Copper Coating)

→ Main features of this APS Cu coating :


- big number of unmelted particles,
- low cohesion between particles,
- high porosity,
- some discontinuities observed at the Nb/ bonding layer interface (MEB)

Mechanical properties of coatings

Sample type	Young's modulus (elastic constants) @ room temperature	Porosity	Residual stress	Thermal Stress @ 4 K	Thermal shocks @ 70 K...4K (fatigue, crack growth)	Bond Strength
Tube Ø 40...50	Estimated from hardness meas.	OK (Archimede, Image analysis)	OK X-diffraction	OK (strain gauges)	OK Optical Microscopy SEM Microscopy	---
Plate 100...150 (width : 10...30)	Strain-stress meas. a) tensile b) compressive c) cantilever beam or 3 -points bending meas.	OK (Archimede, Image analysis)	OK X-diffraction	OK (deflection, strain gauges)	OK Optical Microscopy SEM Microscopy	---


- Thick deposits (two welded half-cells) : coating growth, thermal shocks, plastic deformation,...
- Bonding Homogeneity : ultrasonic tests

Residual Stress Measurement by X diffraction H. GASSOT / IPN / FRANCE V. JI / ENSAM / FRANCE



Tensile properties of V.P.S. Copper Deposits

G. Montavon et al. LERMPS (Belfort, France) 1996




M. FOUAIDY

T. Junquera
12/1/99


Porosity and Elastic Properties Model

Kuroda (NRIM, Japan) 1991

Homogeneous inclusion model → predict Young's Modulus (E)
porosity ≡ randomly distributed ellipsoids




⑤ pore aspect ratio
→ $S = \frac{a}{b}$




Molybdenum:
Experimental data

• APS alumina deposits
 $\frac{E_{APS \text{ coating}}}{E_{Bulk}} = 0.3$



The cavity is subjected to an axial deformation and we measure ΔL vs Force

Experimental set-up



LOW TEMPERATURE (4.2 K - 300 K) DIFFERENTIAL THERMAL CONTRACTION EXPERIMENT

IPN Orsay - IAT Collaboration

- Goal : measure the thermal stresses associated to the differential contraction between bulk niobium and plasma sprayed copper coating.



Low Temperature Strain Gauge Calibration Set-up

- ➔ 3 samples : Bulk Nb, Bulk Cu, APS Cu coating.


Each sample is equipped with strain-gauges and 2 calibrated thermometers (Carbon & Platinum resistors).

Rosette $\approx$ 3 superposed strain-Gauge (resistive sensors made of Nickel-Chrome Alloy)


- ➔ The strain-Gauge are calibrated by the supplier : but the calibration curve (Temperature effect correction) depends on the material to be tested and the mounting conditions (bonding agent.....).

- ➔ One need calibration to get the temperature-induced apparent strain for the test-specimens (Bulk Niobium, Bulk Copper and APS Cu coating).

Low Temperature Strain-Gauges Calibration results




Apparent Thermal Contraction of Bulk Niobium, Bulk Copper and APS Copper during Samples Warm-up from 4.2 K to Room Temperature.



Bulk Copper and APS Copper Apparent Thermal Contraction : Samples Cool-down versus Warm-up between 300 K and 4.2 K.

T (K)	[L(293)-L(T)]/L(293)	
	Copper	Niobium
293	0	0
273	-330	-140
260	-540	-230
240	-860	-370
220	-1170	-500
200	-1480	-630
180	-1780	-760
160	-2070	-880
140	-2340	-990
120	-2590	-1110
100	-2820	-1210
80	-3000	-1290
60	-3140	-1370
40	-3220	-1410
20	-3240	-1430
4	-3240	-1430




TESLA Meeting,

Desy, Hamburg


March 1999

Orsay
M.FOUAIDY

LOW TEMPERATURE (4.2 K - 300 K) DIFFERENTIAL THERMAL
CONTRACTION EXPERIMENT



Test-samples : Bulk Nb tube (left) , Nb tube with LPPS CuAgZr (Ag:3%,Zr:0.5%)
coating, APS Cu coating disk (left) Bulk Cu and Bulk Nb plates.




Close view to the two tubes

(All the samples are equipped with Strain-gauges and temperature sensors)

☺ The experiment will be performed during TESLA Meeting (March 1999) !!!

Close view to the flat samples already used for calibration experiment



IP Orsay

M.FOUAIDY

EFFECT OF PLASMA-SPRAYED COATING ON THE CAVITY OVERALL THERMAL RESISTANCE

● We performed up to now 10 experiments with different Test-cells

→ Purpose : measure the effective thermal resistance of the plasma sprayed copper

→ Differential method : measure and compare heat transfer between Niobium and superfluid helium (naked Nb specimen (pure Nb) versus copper coated Nb specimen).

⇒ Kapitza resistance R_K at Nb-He II interface is reproducible :

× Assumption : R_K have the same value for two similar samples

• machined from the same Niobium sheet

• prepared at the same time and

• according to exactly the same procedure (Mechanical polishing, degreasing, heat treatment, chemical etching,...etc).

● For comparing all the experimental data obtained up to now (different test-cells used) the analysis is restricted to the overall thermal resistance R_O data @ 1.8 K.

➤ The measured overall thermal resistance R_O is given by :

$$R_O = R_K + \frac{e_{Nb}}{k_{Nb}} + R_K$$

k_{Nb} : Niobium thermal conductivity,

e_{Nb} : Niobium thickness.

2


$$R_O = \frac{e_{Nb}}{k_{Nb}} + R_K$$

LEWIS Orsay

Hell filing port



Comparaison de la résistance thermique globale Nb vs Nb/Cu
Nb Wah -Chang RRR= 30-40 ($\epsilon=0.5$ mm), dépôt Cu à P_{am}



Echantillon Nb Wah Chang avec chimie 40 μm (RRR ≈ 40) et échantillon Nb/Cu (dépôt Cu avec sous-couche d'accrochage sous air à la pression atmosphérique)


O Mesure du RRR (Residual Resistivity Ratio)

> Banc de mesure opérationnel à l'IPN. Test de 10 échantillons simultanément.

Echantillon	Traitement	RRR mesuré	RRR (Specifications)	Fournisseur
010	Brut	136	160-200	Heareus
011	Brut	132	160-200	Heareus
013	Soudure B.E	112	160-200	Heareus
014	Soudure B.E	111	160-200	Heareus

Exemples de résultats

> Très bon accord entre les valeurs mesurées directement (méthode électrique), les valeurs calculées (teneurs en impuretés O, N ...) et celles déduites des valeurs expérimentales de conductivité thermique à 4.2 K ($RRR \approx a.k_{0.2}$, $a = 4-5 m.K/W$).



Test	Test-cell Samples	Nb RRR * and Cu & Nb thickness	$R_0(K.m^2/W)$ @ 1.8 K	$\Delta R_0(K.m^2/W)$ @ 1.8 K	Remarks
1	4 rods ($\Phi 8$)	100 *	$5.6 \cdot 10^{-4}$		OK
1	4 rods ($\Phi 8$)	e_{Cu} : 1-1.5 mm or 2-2.5 mm	$6.5 - 7.5 \cdot 10^{-4}$	$0.9 \pm 1.9 \cdot 10^{-4}$	OK
2	2 Nb Cabot disks, BCP 50 μ m	30-40 * $e_{Nb} = 1.96$ mm	$1.46 \cdot 10^{-3}$		OK
2	2 Nb cabot disks, BCP 50 μ m with APS bonding alloy and APS Cu coating (Mallard)	$e_{Nb} = 1.96$ mm $e_{Cu} = 2.5$ mm	$2.07 \cdot 10^{-3}$	$6.2 \cdot 10^{-4}$	permeability test to be performed on the APS Cu coating disk
3	2 Nb Plansee disks, BCP 40 μ m	30-40 * $e_{Nb} = 2$ mm	$6.32 \cdot 10^{-4}$		OK
3	2 Nb Plansee disks BCP 40 μ m with APS bonding alloy	$e_{Nb} = 2$ mm $e_{Al} = 0.2$ mm	$1.27 \cdot 10^{-3}$	$6.4 \cdot 10^{-4}$	OK
4	2 Nb Wah-Chang disks BCP 50 μ m	30-40 * $e_{Nb} = 0.5$ mm	$3.84 \cdot 10^{-4}$		Nb k(T) not yet measured (without HT: Ti @ 1200 °C).
4	2 Nb Wah-CHang disks, BCP 50 μ m with APS bonding alloy and APS Cu coating (Mallard)	$e_{Nb} = 0.5$ mm $e_{Cu} = 2.2$ mm	$7.48 \cdot 10^{-4}$	$3.6 \cdot 10^{-4}$	permeability test to be performed on the APS Cu coating disk
5	2 Nb disks Wah-Chang machined on the lathe	200 * $e_{Nb} = 2.02$ mm	$5.6 \cdot 10^{-4}$		Nb k(T) not yet measured
5	2 Nb disks Wah-Chang machined on the lathe with CAPS (Argon) Cu coating (CEA/DAM)	$e_{Nb} = 1.85$ mm $e_{Cu} = 2.0$ mm	$5.6 \cdot 10^{-4}$	≈ 0	Nb/Cu interface analyzed by US, Micrograph to be done (after second test ?).

TABLE I: OVERALL THERMAL RESISTANCE R_0 OF ALL Nb and Nb/Cu SAMPLES TESTED UP TO NOW

• Theoretical estimation of the interfacial thermal resistance between Nb and Cu
 (see theory (1879))
 Based on Acoustic Mismatch Between the two media:

$$R_{I,th}^{(1)} (K.m^2.W^{-1}) \approx 2.1 \cdot 10^{-4} T^{-3}$$

$T(K)$	1.5	1.7	1.8	1.9
$R_{I,th}^{(1)} (K.m^2.W^{-1})$	6.10^{-5}	$4.2 \cdot 10^{-5}$	$3.6 \cdot 10^{-5}$	3.10^{-5}

R_g : Total thermal resistance

$R_{g1} \rightarrow Nb$; $R_{g2} \rightarrow Nb/Cu$

$$\Delta R = R_{g2} - R_{g1}$$

1. (1879) : (1879) for T : 1.8 K $\rightarrow$ 1.5 K:

thickness of the bonding layer (Cu-Al alloy) 10% of Al) . $e_b \approx 0.2$ mm

Bad thermal conductivity $\rightarrow k \approx 1$ W/m.K at 2.0 K

$$R_{Alloy} = \frac{e_b}{k} \approx 2 \cdot 10^{-4} \frac{K.m^2}{W}$$

$$R_{Alloy} \approx 2 \cdot 10^{-4} K$$

low porosity of the plasma sprayed copper = "dirty material"

Something else ???

○ Darcy permeability κ

① → Room temperature tests (300 K) using a gaseous helium permeameter : measurement of the pressure ΔP across the porous medium (thickness : l) versus the gas mean gas velocity v (flowrate).

$$\kappa = \frac{\eta l v}{\Delta P}$$


η : helium dynamic viscosity = 20.10^{-6} Pa.s.

➤ First result obtained with a copper coating (APS) : we measured $\kappa = 2.4 \cdot 10^{-15} \text{ m}^2$. This figure is within the range of Darcy permeability of porous plug devices operated in He II in space applications.

② → Thermal method in superfluid helium (under development)

➤ Goal : Characterization and modelling of the heat transfer in the porous medium cooled by He II.

➤ Principle : Based on the outstanding thermohydrodynamics and thermal properties of superfluid helium. (Two-fluid model)



Darcy permeability experimental method in He II

According to the phenomenological two-fluid model (Tisza, Landau & Lifschitz) of superfluid helium, the heat flow is controlled by He II thermohydrodynamics (counterflow of the two components).

● We distinguish two main heat flow regimes :

➤ Low heat flux linear Landau regime, where the dissipation is dominated by the normal fluid viscosity according to the relationship :

$$\dot{Q} = A \frac{\rho^2 S^2 T}{\eta_n} \frac{\Delta T}{l} \kappa_n \quad (1)$$

A : porous medium cross section ,

$\dot{Q}$: heat flux (W),

ΔT : temperature difference between the heated He II inside the test-cell and the thermostat (He II bath),

η_n : dynamic viscosity of the normal fluid ,

κ_n : Darcy permeability relative to the normal fluid,

S, ρ : specific entropy and He II density .

From equation (1) , we could define an effective thermal conductivity K_{eff} in the Landau regime :

$$K_{eff} = \frac{\rho^2 S^2 T}{\eta_n} \kappa_n \quad (2)$$

By comparing the relation (2) with the similar expression of K_{eff} for the case of He II counterflowing in a cylindrical duct (diameter D), the physical meaning of the Darcy permeability is quite obvious :

$$\kappa_n = \frac{D^2}{32} \quad (3)$$

→ For this simple model , The porous medium equivalent hydraulic diameter is $D_h = 4(2\kappa_n)^{1/2}$.

THERMAL CONDUCTIVITY (KT) TEST-CELL



→ Steady-state axial heat flow method


- Four specimens tested simultaneously (temperature range : 1.54 K - 9.0 K)
 - Each specimens is equipped with a heater and 3 calibrated thermometers
- Test-samples description:

→ Samples dimensions in mm : 55x10xthickness (th.)

- Sample #1 : Niobium Heraeus RRR (Spec.) = 160-200 -As received (th. = 0.92mm)
- Sample #2 : Niobium Wab-Chang Teledyne RRR (Initial Spec.) = 30-40 , measured after Heat Treatment with titanisation @ 1200 °C (th. = 0.36 mm)
- Sample #3 : Niobium (abot RRR (Spec.) = 30-40 -As received (th. = 2.05 mm)
- Sample #4 : Niobium Plansee RRR (Spec.) = 30-40 -As received (th. = 1.94 mm).


→ Good agreement between the RRR values as deduced from k_{23} ($k_{23} \propto RRR$) those measured directly (electrical resistivities ratio) and calculated (impurities content O_p , N_{pp}).

→ <http://ipnweb.in2p3.fr/~yaniche>



THERMAL CONDUCTIVITY TEST-CELL
(TEMPERATURE RANGE : 1.5K - 60K)


Thermal conductivity of 4 Niobium samples tested at IPN Orsay Lab. (Nov. 1998)



M.FOUAIDY-TESLA meeting, Desy (Hamburg) March 1999

Graph2

Valeurs expérimentales (Novembre 98)
des échantillons de Niobium PLANSEE, CABOT, WAH-CHANG et HERAEUS
 k (W/m.K) = $f(T)$



LOW TEMPERATURE THERMAL CONDUCTIVITY MEASUREMENT AT IPN Orsay
Tests of November 1999 4 specimens tested simultaneously

Test-samples description

SAMPLE #	1	2	3	4
Material	Niobium	Niobium	Niobium	Niobium
Length (mm)	55	55	55	55
Width (mm)	10	10	10	10
Thickness (mm)	0.36	1.94	0.92	2.05
Supplier	Wah-Chang Teledyne	Plansee	Heraeus	Cabot
Initial RRR (Spec.)	30-40	30-40	160-200	30-40
Initial RRR (Calc.)	36-46	56	166	41
RRR (Measured)	not Meas.	not Meas.	126-147	not Meas.
RRR (a. $k_{4.2}$)	122-153	45-56	164-205	50-63
$k_{4.2}$ (W/m.K)	30.5	11.2	41	12.5
Treatment	HT@ 1200 °C withTi	as received	as received	as received

26/02/1999

STATUS OF CAVITIES R&D AT LAL ORSAY

- Laurent Grandsire
- Jean Claude Bourdon
- Jean Luc Borne
- Jean Marini
- Bernard Jacquemard
- Joel Leduff
- Emmanuelle Vernay
- Alice Thiébault
- Patrick Lecoeur

grandsir@lal.in2p3.fr

1

PLAN

- Hydroforming
- hot forming
- plasma spraying of copper
- E.B. welding
- non destructive controls
- mechanical tests

grandsir@lal.in2p3.fr

2

197

HYDROFORMING (SIBB)

- Principle
 - process in 2 steps
 - 40 % of deformation in first step,
 - annealing (900 °C, 2 hours),
 - 90 % in second step
- Operative conditions
 - bi-cells 3 GHz cavities
 - Dirts ext = 51.7 mm,
 - Deg ext = 94.6 mm ($r = 1.89$)
 - Th init = 2 mm
- Results
 - 21 tested tubes
 - 5 tubes to 40 %
 - 4 bicell-cavities
- Conclusions
 - Perfecting period (buckling)
 - correlation success / textures of tubes ?
- To come:
 - chemical etching (Saclay) and test (IPN Orsay)
 - chemical polishing (saclay) and test (IPN)

grandtir@lal.in2p3.fr

3

Hydroflambage
Tube Niobium épaisseur 2 mm - diamètre 52 mm



3

HOT FORMING (I)



Two parallel methodologies in order to conciliate scientific, technological and practical

knowledge:

- **empiric studies**
- **scientific studies**

HOT FORMING (II) EMPIRIC STUDIES


- **Principle**
 - Axial load + internal pressure
 - No dies
 - Induction heating (800 °C)
 - VERMETAL
- **Operative conditions**
 - Dext = 38 mm, Th = 0.5 mm
 - 50 % of deformation (limited by induction turn)
 - Dext = 51.7 mm, Th = 2 mm
 - tubes too rigid for the device (axial load and pressure limitations)
 - Dext = 49.7 mm, Th = 1 mm
 - to be continued....
- **Knowledge of the ratio Pressure/axial load (tear / buckling)**



HOT FORMING (III)

SCIENTIFIC STUDIES

- 2 successive steps
 - mechanical characterization of niobium
 - HERAUS RRR 120
 - 700-900 & 1300-1500 °C
 - SEP Bordeaux
 - determination of
 - optimal temperature (900 & 1400 °C)
 - optimal speed of deformation (10^{-3} s^{-1})
 - mechanical law (tensile test)
 - simulation of hot forming
 - risks of breaking
 - Initial and final thickness
 - cycle of temperature / pressure
 - die geometry
 - ENSAM Angers (ABAQUS EXPLICIT)



PLASMA SPRAYING OF COPPER

- Goals:

- Removal of iris rings
 - easiness of manufacturing
- Thinner thickness of Nb
 - cost
- first studies about the process (Malard)
- in collaboration with IPN Orsay
 - study of induced stress by differential dilatations between copper and niobium
 - stress and deformation gauges
 - US NDT (unsticking ?)

grandsir@lal.in2p3.fr

2



⑤

E.B. WELDING

- Stamping and E.B. Welding devices at LAL
- bench mark programme with CERCA
 - monocell 3 GHz 1 mm RRR 120 HERAEUS
 - 3 CERCA cavities (CERCA etching) + 4 LAL cavities (Saclay etching)
 - IPN testing
 - quality of weldings, vacuum, proceedings
- Realizations and work program:
 - thickness (0.5; 1; 2 mm)
 - RRR 40; 120; 200
 - 1.3 & 3 GHz
 - parameters

grandsir@lal.in2p3.fr

8

NON DESTRUCTIVE CONTROLS


- Ultrasonic and eddy currents devices
- control of sheets and tubes after delivery and before deformation
- ultrasonic (immersion) device:
 - 0.4 mm of resolution for cracks
 - 0.5 mm of resolution for Ta inclusions
- Eddy current device:
 - $50 \text{ KHz} \leq f \leq 400 \text{ KHz}$
 - $0.1 \text{ mm} \leq \delta \leq 1 \text{ mm}$

grandsir@lal.in2p3.fr


9

2023

MECHANICAL TESTINGS



- Mechanical device
 - MTS Systems 150 KN
 - tensile test
 - compression
 - tear /peel
 - flexion
 - cryogenic test in the future ?
- Program:
 - Data base
 - Optimisation of annealings
 - Material characteristics (copper)



HOM Measurements at TTF

- February 1999 -

O. Napoly, N. Baboi, H.-W. Glock, F. Marhauser,
C. Magne, H. Schlarb, S. Simrock, G. Kreps,
G. von Walter, M. Hüning, T. Garvey and others

(DESY, CEA - Saclay, University of Rostock,
Inst. of Applied Physics - Frankfurt)

TTF Collaboration Meeting, 2.03.99

Nicoleta Baboi

HOM Experiments at TTF

- FEBRUARY '99 -

SCOPE : MEASURE BEAM DEFLECTION
INDUCED BY TRANSVERSE HOM
IN THE TTF CRYOMODULES.

METHOD : DETUNE 1 CAVITY SUCH
THAT THE STUDIED MODE
FREQUENCY BECOMES A MULTIPLE
OF THE BUNCH FREQUENCY

$$f_{\text{HOM}} = n \cdot f_b \left(1 \pm \frac{1}{2Q} \right)$$

LOCK AT BCTH BPM 2
SPECTRA

SCALING MONITORING OF TRANSMISSION

206

1st module / cavity 3

30 bunches

3 nC / bunch

GRADIENT: ~ 6 MV/m.

MODE AT 2.584970 GHz

$$Q \approx 10^6$$

DETUNING -20 kHz for HOM
+12.6 kHz for FM



STEER THE BEAM WITH THE

DOG LEG → HEAD-TAIL RESONANCE


2nd module / cavity 5

MODE AT 2.584494 GHz
 $Q \approx 400000$


DETUNING -544 kHz for HOM
+340 kHz for FM




7200



dogleg
3A



dogleg
3A



Run at 12 o'clock.

We reproduce exactly the head-tail resonance


fin time monitoring with neutron BPM

beam current is monitored on the same oscilloscope screen


channel 2: I beam
34 400 mV/nC (74) beam
channel 3: ΔX
700 mV/mm @ 3.4 nC

SET BOTH CHANNELS OF THE OSCILLOSCOPE TO:
1 MΩ load
AC ~


dog leg - 3A 4A ↔ 5mm




dogleg = 0



dogleg + 3A




Mod 2
CSK2
108m
C8m
Shift
+500
6Hz




SP: 2.5840042 GHz

4:14
Mod 2
CSK
208m





SP: 2.5840042 GHz

Mod
CSk
2064



PEAK POWER OF THE MODE FROM DIFFERENT HOM COUPLERS



26.7.9

[illegible]

C. 0.0000000000000000

SPIN 200.0KHZ

2000 21 4

3. 0-100

ASHP 200sec

104 25 11 11 01 37

4. *Journal of the American Medical Association*, 1997; 277: 1033-1038.

0113

1. 8. 19. 130 : 1

26.7.9%

CAVITY 3 / MODULE 1

NO DETUNING

1998, 1999, 2000, 2001, 2002, 2003, 2004, 2005, 2006, 2007, 2008, 2009, 2010, 2011, 2012, 2013, 2014, 2015, 2016, 2017, 2018, 2019, 2020, 2021, 2022, 2023, 2024, 2025, 2026, 2027, 2028, 2029, 2030, 2031, 2032, 2033, 2034, 2035, 2036, 2037, 2038, 2039, 2040, 2041, 2042, 2043, 2044, 2045, 2046, 2047, 2048, 2049, 2050, 2051, 2052, 2053, 2054, 2055, 2056, 2057, 2058, 2059, 2060, 2061, 2062, 2063, 2064, 2065, 2066, 2067, 2068, 2069, 2070, 2071, 2072, 2073, 2074, 2075, 2076, 2077, 2078, 2079, 2080, 2081, 2082, 2083, 2084, 2085, 2086, 2087, 2088, 2089, 2090, 2091, 2092, 2093, 2094, 2095, 2096, 2097, 2098, 2099, 2100, 2101, 2102, 2103, 2104, 2105, 2106, 2107, 2108, 2109, 2110, 2111, 2112, 2113, 2114, 2115, 2116, 2117, 2118, 2119, 2120, 2121, 2122, 2123, 2124, 2125, 2126, 2127, 2128, 2129, 2130, 2131, 2132, 2133, 2134, 2135, 2136, 2137, 2138, 2139, 2140, 2141, 2142, 2143, 2144, 2145, 2146, 2147, 2148, 2149, 2150, 2151, 2152, 2153, 2154, 2155, 2156, 2157, 2158, 2159, 2160, 2161, 2162, 2163, 2164, 2165, 2166, 2167, 2168, 2169, 2170, 2171, 2172, 2173, 2174, 2175, 2176, 2177, 2178, 2179, 2180, 2181, 2182, 2183, 2184, 2185, 2186, 2187, 2188, 2189, 2190, 2191, 2192, 2193, 2194, 2195, 2196, 2197, 2198, 2199, 2200, 2201, 2202, 2203, 2204, 2205, 2206, 2207, 2208, 2209, 2210, 2211, 2212, 2213, 2214, 2215, 2216, 2217, 2218, 2219, 2220, 2221, 2222, 2223, 2224, 2225, 2226, 2227, 2228, 2229, 2230, 2231, 2232, 2233, 2234, 2235, 2236, 2237, 2238, 2239, 2240, 2241, 2242, 2243, 2244, 2245, 2246, 2247, 2248, 2249, 2250, 2251, 2252, 2253, 2254, 2255, 2256, 2257, 2258, 2259, 2260, 2261, 2262, 2263, 2264, 2265, 2266, 2267, 2268, 2269, 2270, 2271, 2272, 2273, 2274, 2275, 2276, 2277, 2278, 2279, 2280, 2281, 2282, 2283, 2284, 2285, 2286, 2287, 2288, 2289, 2290, 2291, 2292, 2293, 2294, 2295, 2296, 2297, 2298, 2299, 2300, 2301, 2302, 2303, 2304, 2305, 2306, 2307, 2308, 2309, 2310, 2311, 2312, 2313, 2314, 2315, 2316, 2317, 2318, 2319, 2320, 2321, 2322, 2323, 2324, 2325, 2326, 2327, 2328, 2329, 2330, 2331, 2332, 2333, 2334, 2335, 2336, 2337, 2338, 2339, 2340, 2341, 2342, 2343, 2344, 2345, 2346, 2347, 2348, 2349, 2350, 2351, 2352, 2353, 2354, 2355, 2356, 2357, 2358, 2359, 2360, 2361, 2362, 2363, 2364, 2365, 2366, 2367, 2368, 2369, 2370, 2371, 2372, 2373, 2374, 2375, 2376, 2377, 2378, 2379, 2380, 2381, 2382, 2383, 2384, 2385, 2386, 2387, 2388, 2389, 2390, 2391, 2392, 2393, 2394, 2395, 2396, 2397, 2398, 2399, 2400, 2401, 2402, 2403, 2404, 2405, 2406, 2407, 2408, 2409, 2410, 2411, 2412, 2413, 2414, 2415, 2416, 2417, 2418, 2419, 2420, 2421, 2422, 2423, 2424, 2425, 2426, 2427, 2428, 2429, 2430, 2431, 2432, 2433, 2434, 2435, 2436, 2437, 2438, 2439, 2440, 2441, 2442, 2443, 2444, 2445, 2446, 2447, 2448, 2449, 2450, 2451, 2452, 2453, 2454, 2455, 2456, 2457, 2458, 2459, 2460, 2461, 2462, 2463, 2464, 2465, 2466, 2467, 2468, 2469, 2470, 2471, 2472, 2473, 2474, 2475, 2476, 2477, 2478, 2479, 2480, 2481, 2482, 2483, 2484, 2485, 2486, 2487, 2488, 2489, 2490, 2491, 2492, 2493, 2494, 2495, 2496, 2497, 2498, 2499, 2500, 2501, 2502, 2503, 2504, 2505, 2506, 2507, 2508, 2509, 2510, 2511, 2512, 2513, 2514, 2515, 2516, 2517, 2518, 2519, 2520, 2521, 2522, 2523, 2524, 2525, 2526, 2527, 2528, 2529, 2530, 2531, 2532, 2533, 2534, 2535, 2536, 2537, 2538, 2539, 2540, 2541, 2542, 2543, 2544, 2545, 2546, 2547, 2548, 2549, 2550, 2551, 2552, 2553, 2554, 2555, 2556, 2557, 2558, 2559, 2560, 2561, 2562, 2563, 2564, 2565, 2566, 2567, 2568, 2569, 2570, 2571, 2572, 2573, 2574, 2575, 2576, 2577, 2578, 2579, 2580, 2581, 2582, 2583, 2584, 2585, 2586, 2587, 2588, 2589, 2590, 2591, 2592, 2593, 2594, 2595, 2596, 2597, 2598, 2599, 2600, 2601, 2602, 2603, 2604, 2605, 2606, 2607, 2608, 2609, 2610, 2611, 2612, 2613, 2614, 2615, 2616, 2617, 2618, 2619, 2620, 2621, 2622, 2623, 2624, 2625, 2626, 2627, 2628, 2629, 2630, 2631, 2632, 2633, 2634, 2635, 2636, 2637, 2638, 2639, 2640, 2641, 2642, 2643, 2644, 2645, 2646, 2647, 2648, 2649, 2650, 2651, 2652, 2653, 2654, 2655, 2656, 2657, 2658, 2659, 2660, 2661, 2662, 2663, 2664, 2665, 2666, 2667, 2668, 2669, 2670, 2671, 2672, 2673, 2674, 2675, 2676, 2677, 2678, 2679, 26

1. 8759713 C 11

-51.17 0139


27 BUNCHES

27 Lu

1, 7mC

dog

04





6. *Chlorophyll a* and *Chlorophyll b* were determined by the method of Arar and Collins (1971).

5-11. 200.0417


43

3 29 00 12

ASAP POSSIBLE



212



$R/Q = 1.5 \cdot 10^5 \Omega/m^2$ (VERY PRELIMINARY!)

$Q = 10^6$

ARE OTHER MODES CONTRIBUTING
SIMULTANEOUSLY TO THE BEV?

PRELIMINARY CONCLUSIONS

WE SAW THE HEAD-TAIL RESONANCE
AND THE CORRESPONDING SPECTRUM
ANALYSER SIGNAL ($P \sim x^2$)

NEED MORE CALCULATIONS / TIME
TO UNDERSTAND:

- WHY BUNCH TRAIN SIGNAL
 $\neq n \cdot 1 \text{ MHz}$?
- WHY MODE PRESENCE DEPENDS ON
NUMBER OF BUNCHES AND HOW ?
- WHERE IS THE MAXIMUM SIGNAL
TO BE EXPECTED ?
- CONTRIBUTION OF MORE MODES ?
- LIMITED NUMBER OF BUNCHES /


Y. Skutovica
MHF-SH

List of tasks to build and to test with the beam the
first Nb prototype of the 4x7-cell superstructure

TTF meeting, DESY, March 2, 1999 ²

To minimize the cost and the effort we like to perform all treatments and tests for each sub-unit (7-cell) individually and then make assembly of 4 sub-units in the superstructure.

This allows to use with some changes the existing "9-cell" infrastructure for the cleaning procedures and test.




It seems to us that for the first prototype it will be easier to use the flange connection between 7-cell structures.



The welding procedure, cheaper for the mass production, is not require to test the first prototype and is not very well established at the moment.

Tasks can be splitted into groups :



I. Changes in the design and in the fabrication of:

- **Cavities** : tooling to form new end-cells, superconducting flange connection of sub-units as proposed by A. Matheisen.
- **FM coupler** : increase outer diameter to $\varnothing$ 60-80 mm and make FM shorter by 18 mm (important for position of standing wave under full-reflection)
D. Proch, B. Dwersteg, W-D. Möller, A. Zavadsev
- **HOM couplers** : new requirements on HOM damping (H. Chen , V. Puntus, JS)





05,02



II. Changes in the design of :

- Tuners and LHe vessels : there is not enough space between cavities for the present version of the tuner (new solution proposed by H. Kaiser)
- Cryomodule : new position the sliding supports

III Treatments and preparation : generally no problem since sub-units are shorter than the TTF cavities

IV Cold test of sub-units:


7-cell cavities are terminated with two type of beam tubes:
 the short one 21 mm and/or
 the long one 91 mm.



TTF meeting, DESY, March 2, 1999 5

This asymmetry reduces number of the flange connections to 3. But to test 7 cells with the reasonable field profile one has to use two superconducting end-cups:



- end-cup with the variable input coupler
- end-cup with the pickup antenna

which provide electric short at the distance of $\lambda/4$.





V Assembly in the cryomodule and final test with the beam. (J. Waisend, C. Pagani).



Waveguide Input Coupler for Accelerating System

(one of possible constructions)

A.Zavadtsev
DESY

1. APPOINTMENT

The power input coupler may be used for RF feeding of:

- one N-cells cavity ($N=9$ or more) or
- two N-cells cavities ($N=9$ or more) or
- one Superstructure [1] ($4*7=28$ cells) or
- two Superstructures ($2*4*7=56$ cells).

2. COUPLER STRUCTURE

The power input coupler is destined for power transition from gas-filled rectangular waveguide at the room temperature to the high clean vacuum filled accelerating structure at 2K.

The final variant of the input coupler (coaxial or rectangular waveguide) may be chosen after carrying out the following main works:

- calculation of the form and sizes of the coupler;
- calculation of the field in the coupler;
- calculation of the kick for the beam;
- investigation of the multipacting ;
- design of the coupler construction (in the cryomodule);
- design of the cooler circuits (70 and 2 K), calculation of the heat regime and the temperature distribution;
- design of the HOM couplers;
- design of the processes of manufacture, chemistry development, heating, tuning, assembling and high power tests of the input coupler and the accelerating system.

The waveguide input coupler consists of

- warm ceramic window,
- cool ceramic window (at 70K),
- coupling element,
- connecting lines.

Each commercial waveguide window with satisfactory parameters may be used as the warm ceramic window.

The coupling element may be used as in [2].

The parameters of the waveguides and the coaxial line in travelling wave regime are represented in Table 1. All parameters in this report correspond to P=1.3 MW (two Superstructures - 56 cells).

Table 1: Feeding lines parameters.

Feeding line	Maximal electric field, kV/cm	Maximal voltage, kV	Decrement relative values
Waveguide 165x82 mm	4.48	37.0	1
Waveguide 165x50 mm	5.76	28.8	1.44
Waveguide 165x30 mm	7.44	22.3	2.18
80 mm 80 Ohm coaxial line	10.3	14.4	1.78
- inner conductor			1.41
- outer conductor			0.37

The multipacting chart in the rectangular waveguide in travelling wave regime is available [3].

3. CERAMIC WINDOW

3.1. Common ideas

The main requirements for the ceramic window are:

- the window should have minimal sizes because it will be install into the cryomodule;
- the ceramic should not be seen from the beam axis;
- the electric field in the window should be minimized.

The power transmission through the window is

$$K = \frac{4\beta_1\beta_2}{(1 + \beta_1 + \beta_2)^2} \cdot \frac{1}{1 + \left(\frac{2Q_0\Delta f}{(1 + \beta_1 + \beta_2)f} \right)^2}$$

β_1 and β_2 are the coupling coefficients of the cavity with input and output waveguides,

Q_0 is own Q-factor of the cavity,

Δf is frequency shift.

Analysing this equation one can say that

- the power transmission is equal to 1 at resonance frequency if $\beta_1 = 1 + \beta_2$;
- the window has more broad frequency band for higher β_1 and β_2 .

Therefore it is better to make $\beta_1 \gg 1$ and $\beta_2 \gg 1$. The good matching may be got for $\beta_1 = \beta_2$ in this case. It means that the window may be symmetrical about the window centre.

3.2. Calculated parameters.

The configuration of the window is the development of the idea proposed in [4]. The waveguide cross-section is 165.1x30 mm. The coupling slots sizes are $h \times 30$ mm.

Table 2: Parameters of the window variants in the frequency range 1.0-1.6 GHz.

Variant	Mode	f_0 , MHz	Δf , MHz ($S_{11}=0.1$)	E_{cer} kV/cm
One-mode variant with $h=90$ mm.	TM ₀₁₀	1155	10	12.3
	TE ₁₁₁	1225	<10	11.0
	TE ₂₁₁	1400	10	11.0
Tree-modes variant with $h=114$ mm.	TM ₀₁₀ +TE ₁₁₁ +TE ₂₁₁	1300	170	5.0

4. CONNECTING LINES

Table 3: Connecting lines parameters.

Connecting line	f_0 , MHz	Δf , MHz ($S_{11}=0.1$)	E_{max} , kV/cm
82-30 mm tran- sition	1300	160	7.5
30-30 mm S-bend	1300	540	7.5

HP 85180A High-Frequency Structure Simulator was used for all calculations.

5. CONCLUSION

Proposed construction of input coupler has following properties:

- minimal sizes; the ceramic window is disposed inside the waveguide volume practically;
- low electric field; the optimization of the window sizes provides the travelling wave in the window cavity practically like in the transmission line rather than the standing wave like in the resonator;
- admissible frequency band - 160 MHz at $S_{11}=0.1$ level (cool window and connecting lines).

7. REFERENCES

1. J.Sekutowicz. Status of Superstructure Studies. The TTF Coupler Meeting, Saclay, October 19-20, 1998. November 1998, TESLA 98-28.
2. M.Dohlus, A.Gamp, H.Hartwig, N.Holkamp, A.Jostingmeier, C.Martens, M.Marx, C.Pagani, J.Weisend, V.Kaljuzhny, K.Jin, A.Zavadtsev, S.Yarigin. Status of Waveguide Coupler Activity at DESY. The TTF Coupler Meeting, Saclay, October 19-20, 1998. November 1998, TESLA 98-28.
3. D.Proch. Multipactor Simulations. The TTF Coupler Meeting, Saclay, October 19-20, 1998. November 1998, TESLA 98-28.
4. A.Zavadtsev. New Idea for Waveguide Coupler Window. The TTF Coupler Meeting, Saclay, October 19-20, 1998. November 1998, TESLA 98-28.




Fig.1. Maximal electric field E in the waveguide with the cross-section 162xb at power $P=1.3$ MW.




Fig.2. The voltage U in the waveguide with the cross-section 165xb at power $P=1.3$ MW.




Fig. 3. The decrement α depending on b .




Fig. 4. View of the window.




Fig.5. $S_{11}(f)$ dependence for window with $h=90$ mm.




Fig.6. $S_{11}(f)$ dependence in Smith chart for window with $h=90$ mm.




Fig.7. $S_{11}(f)$ dependence for window with $h=114$ mm.




Fig.8. $S_{11}(f)$ dependence in Smith chart for window with $h=114$ mm.




Fig.9. The field distribution in the window at phase 0^0 .




Fig.10. The field distribution in the window at phase 30^0 .




Fig.11. The field distribution in the window at phase 90° .




Fig.12. 82-30 mm transition.




Fig.13. $S_{11}(f)$ dependence for 82-30 mm transition.




Fig.14. 30-30 mm S-bend.




Fig.15. $S_{11}(f)$ dependence for 30-30 mm S-bend.




Fig.16. Common view of the coupler.

FIELD MEASUREMENTS FOR A 4-CAVITIES CHAIN


	PASSBAND LIMITS	(BY INDIVIDUAL MEASUREMENTS)	
		MONOPOLE	DIPOLE
1.	A17	2.460425	2.5803
2.	A18	2.469575	2.5815
3.	S9	2.461375	2.5748
4.	A19	2.467140	2.5790

TRANSMISSION CURVES → VERY DIFFERENT THAN AT TTF.

STRENGTHENING BELOW ⇒ HIGHER PASSBAND LIMIT.

NEXT : COPPER CAVITY IN CHAIN

9.2.99





WE USED INPUT COUPLERS AND PICK-UP ANTENNAS.
(IN TTF - HOM COUPLER)

Tube 1-2 : $3\frac{1}{4}, 5 \text{ mm}$

Cav, $2i - 2r$

$T_{12} = 460 \text{ mm}$ } relative lengths
 $T_{23} = 445, 5 \text{ mm}$ } of tubes




-Amp

TUBE 4-2 : 334.5 mm

Car. 2i-2r



TA2 = 450 mm
T25 = 495.5 mm



TUBE 4-2 : 324.5 mm

~~Tube~~ Car. 2i-2r

TA2 = 440 mm
T25 = 495.5 mm



234

Amp

- Amp

(NO) CONCLUSIONS

- TRANSMISSION CURVES - DIFFERENT THAN IN TTF
- BUT: IN TTF → HOM COUPLERS
HIER → INPUT COUPLERS + PICK-UP ANTENNAS
- SHORTENING BEAM TUBE → MODE
FREQUENCY INCREASES
- BELLOWS → NO EFFECT
(H.W. GLOCK → CALCULATIONS)
- NEXT: COFFER CAVITY IN THE CHAIN
→ STUDY POLARIZATION EFFECTS


MODULE 1

	8	7	6	5	4	3	2	1
CAVITY	S7	D4	(S11)	D2	D1	(S10)	S8	D3
INPUT COUPLER	FNAL	FNAL	DESY	FNAL	FNAL	DESY	DESY	FNAL
HOM COUPLER	SACLAY	DESY	Saclay	DESY	DESY	Saclay	Saclay	DESY


MODULE 2

	1	2	3	4	5	6	7	8
CAVITY	(C22)	C21	C25	C23	(A15)	C26	C27	C24
INPUT COUPLER	FNAL	FNAL	FNAL	FNAL	FNAL	FNAL	FNAL	FNAL
HOM COUPLER	Saclay	Saclay	Saclay	Saclay	DESY	Saclay	Saclay	Saclay


Monopole and dipole band limits (Module 2)



Module 1 Cav.3, Module 1 Cav.6, ...



Low or no
transmission
(< -80 dB)




Outline

- DC field emission measurements with a new planar I-U measurement technique configuration with a luminescent ITO screen (IMLS)
 - Measurement configuration
 - First results on niobium samples
 - Comparison of FESM and IMLS
- Investigation of enhanced field emission due to etching defects
 - Etching of niobium cavities
 - FESM scans of differently etched niobium samples

Samples prepared at TTF by D. Reschke

Experimental




UHV-Analysis- and Preparation Chamber of the Field Emission Scanning Microscope (FESM)

IMLS

Planar diode configuration

Camera (film or CCD)




- Pressure 10^{-7} mbar
- Spacer thickness $10 - 100 \mu\text{m}$ (Teflon foil)
- Maximal anode Voltage $2 \text{ kV} \Rightarrow E_p \leq 200 \text{ MV/m}$
- I-U measurement with PC

Comparison of IMLS and FESM


IMLS	FESM (field emission scanning microscope)
Advantages - simple and cheap apparatus - fast sample investigations (2h): - onset of FE : $E_{on}(I=0,5nA)$ - integral I-U measurements - imaging of strongest emitters - long term current- and gasprocessing possible	Advantages - very high spatial resolution (100nm) - in situ SEM for emitter analysis - single emitter investigations (E_{on}, Fowler-Nordheim : β, S) - reliable non-destructive Fe measurements - UHV 10^{-10} mbar - in situ AES, Ion gun
Disadvantages - limited spatial resolution ($\approx 100 \mu m$) - reidentification of emitters impossible - no single emitter investigations - danger of (multi-) discharges due to switch on effects	Disadvantages - slow Fe investigations (1 day/sample) - complex and expensive measurement system

Emitter activation due to discharges on Nb sample



Sample area $1 \times 1 cm^2$

First tests of IMLS on a niobium sample




sample area of $1 \times 1 \text{ cm}^2$

$U = 880 \text{ V}$; $I = 50 \text{ } \mu\text{A}$; $d = 50 \text{ } \mu\text{m}$

7 light spots visible at 17.6 MV/m

(mechanically bad prepared sample)

Field Emission Scans of a Graphite Film:
Comparison between IMLS and FERMI



IMLS: constant U
 $U = 1200 \text{ V}$
 $d = 200 \text{ } \mu\text{m}$
 $I_{\text{int}} = 65 \text{ } \mu\text{A}$



FERMI: constant $I(x,y)$
 $I(x,y) = 10 \text{ nA (local)}$
 $d = 50 \text{ } \mu\text{m}$
 $U = 250 - 2500 \text{ V}$


Etching of cavities

Problem : Enhanced surface etching by residual acid during filling/emptying period

Question : Enhanced field emission due to etching defects ?


Three samples were prepared at DESY :

Etching for 15 min
removal of acid



Sample D6

Direct water rinsing after etching




Field emission scans in FESM : Ø 13,5 mm

=> *Only 1 weak emitter at 80 MV/m ($E_{on} \approx 70$ MV/m)*

Sample D13

Water rinsing 1 min after removal of acid




Fieldemission scans in FESM : Ø 13,5 mm

=> four strong emitters at 50 MV/m and 80 MV/m with $E_{on} = 25-40$ MV/m
=> switch on effects

Sample D10

Water rinsing 10 min after removal of acid



50 MV/m

- => *three strong emitters at 50 MV/m ($E_{on} = 30-40$ MV/m)*
- => *switch on effects*
- => *dark currents at 80 MV/m*

Conclusions

- IMLS measurements provide a fast and simple FE-characterisation
=> similar apparatus planned at DESY (D. Reschke)
- FESM measurements necessary for microscopic emitter analysis
- FESM advantageous in case of heavy or unstable emitters (switch on effects)
- Etching from residual acid seems to enhance the FE
=> further FE-investigations with FESM in situ SEM planned
- Statistics on etching experiments not sufficient
=> additional measurements on other samples

Electropolishing of cavities

CEA-CERN-DESY

Lutz Lilje -FDET-

1

Electropolishing and welding status at CERN

Why?

- try to reduce field emission
- easier EB welding?
- less diffusion into grain boundaries?

1. Collaboration

Thanks to:

D. Bloess
L. Ferreira
S. Forel
J. Guerin
B. Thony
E. Chiaveri
...

Introduction

- 1 BCP cavity and 4 EP cavities have been manufactured by CERN
- EP has been done by polishing the half cells, then welding

Lutz Lilje -FDET-

2

Aim

- Has polishing of half-cells a benefit?
- What is the procedure for the preparation of a electropolished cavity?
- Can one do a pre-polishing on half cells?

Lutz Lilje -FDET-

3

Polishing Curve




Fig. 11 Relationship between material removal and surface roughness with CP.
The error bar means the variation in three points measurements.








Fig. 12 Relationship between material removal and surface roughness with EP.

121



Reverse process of electroplating in a chemical reaction



insoluble

2


1

1



Copper

248




WORKING PAIR

- large plateau

- Reasonable removal rate of min. 1-2 $\mu\text{m}/\text{min}$

HALF CELL POLISHING



FERREIRA et al.

Echantillon n°27.

Etat de surface de l'échantillon.

Détail de la photo précédente.

Niobium — surface etching

Origin: Yuh Chang

File: wl.tex

Preparation status:

- sample dimensions 1cm^2 , manufactured by electroerosion
- scratch made with the edge of a niobium sheet
- chemical etching $20\mu\text{m}$, mixture from hydrofluoric acid - nitric acid - phosphoric acid (1-1-2)




Figure 1: magnification 120, right upper corner




Figure 2: magnification 482






Figure 3: magnification 965

Echantillon n° 60:



Observation générale de la surface de l'échantillon.



Détail de la photo précédente.

Procedures on all electropolished cavities



www.samson-tahak.de

- EP 100 um on the half cells
- Welding preparation with HF
- Welding
- HF+ Rinsing
- Delivery to CEA

Lutz Lilje -FDET-



First measurements at CEA Saclay

- Thanks
 - H. Safa
 - B. Aune
 - and many more

Lutz Lilje -FDET-

5


1B5 Handling

- HPR only
- Idea: Minimum impact on the surface.
Try to avoid BCP.

Lutz Lilje -FDET-

6

1B5 Tests




Lutz Lilje -FDET-

7

252

1B5 T-Map



Lutz Lilje -FDET-

8

1B3 Handling


- US ->copper!
- Nitric acid -> no copper traces anymore
- BCP 2 um -> brilliance got lost

Lutz Lilje -FDET-

9

253


1B3 Tests



Lutz Lilje -FDET-

10

1B3 T-Map




254

Lutz Lilje -FDET-

11

Cavity 1B3 (EP on halfcells)



255

L. LIGNE
J.P. CHARRIER
H. SATTA
et al.


Outlook

- How much chemical treatment ? (20 μm)
- Build one-cell apparatus

Lutz Lilje -FDET-

14

1B3 Tests



2.3.94:

$$Q_0 = 3 \cdot 10^{10} @ 20 \frac{\text{mK}}{\text{m}}$$

$$Q_0 = 3 \cdot 10^5 @ 27,5 \frac{\text{mK}}{\text{m}}$$

- electrons

- quench @ equator!

⇒ copper in cold?

J.P. GARRE

CEA

Lutz Lilje -FDET-

10

256

Problems

- Copper
 - Comes from the electrode or the cooling pipes
- Electrons
 - Niobium weld beads

Conclusions

- Copper-free electrode
- What material ? (Gold-plated copper ?)
- Half-cell-polishing ?
 - Difficult (Impossible?) to avoid a chemical treatment after welding
 - BCP ?
 - One-cell polishing!

LINAC OPERATION

- N. Baboi (H.O.M. Experiments)
- M. Castellano (Emitance measurements)
- S. Schreiber (Laser performance)
- M. Timm (Surface Roughness linkfields)
- M. Hanning (Exptl proposal for above)
- H. Edwards (Machine improvements!)

Charging?

Doesn't survive? dietetic / we feed.
Wade Fields?

gam steadily, and forward on flat top

feed forward?
Q, Any change
pulse.

gun sparts -
wds sparts -

Need gun used (recs from Owen)

tech interlocks

- move from approach
- fast interlocks and response.

1- few less not we fear
- what we can will not work for 100%
must still supply.

BPM electronics

sets / screen

Must get
ICT line drivers

but F17-14; P.S.
one converts regulation
some P.S. broken.

Controls (Comments only)

Timing of timing lined up.

- at least ADC's
- make use of Everts.

Displays

- Censor.
- Screen clearance.
- Plots scaling.
- up/down control (open windows don't count)
- Display - tree.

too many windows.

too many ways to see same.

Information

on the set point on/off.

Start out under page with #1's to

call forward page.

Summary Spread- ΔE - ΔT A?

Camera technical?

FEL - Commissioning

P. Castro : Beam - Based Alignment

H. Schlarb : Collimator

FEL - Performance:

Design - Parameters

$$E_u = 2 \text{ } \mu\text{m} \cdot \text{mrad}$$

$$Q_E = 0.8 \text{ } \mu\text{s}$$

52

$$\text{Power Gain @ } 15 \text{ m} : \approx 5 \cdot 10^4 \text{ (Saturation)}$$

Worst Case

$$E_u = 20 \text{ } \mu\text{m} \cdot \text{mrad}$$

$$Q_E = 1.6 \text{ } \mu\text{s}$$

$$\text{Power Gain @ } 15 \text{ m} : < 100$$

New + Modified Components

- Timing (3 MHz $\rightarrow$ effect on most diagnostic)
- Magnets (polarization, limitation on the collimator steer)
- Module #3 (conditioning, Phase + Gradient optimization)
- Undulator (Alignment)
- Collimator (Single bunch operation - Photomultiplier
- reduced use of view screen)
- Toroids (Timing, beam for new toroids)
- BPM - strip-line (operational, check with beam)
 - recouant cavity (collimator: July + August, Injector: exist
collimation with beam)
 - cavity (incl. coll. before, etc. coll. with single bunch)
- Wamguide monitor + Wire Scanner (collimation with single bunch)
- peripheral Area (reconnect + timing)

FEL - Commissioning (Run: July '99)

- ① Module #3 - conditioning etc
- ② Single Bunch Operation
 - I) high transmission (view screens)
 - II) diagnostic collimation
- ③ Calibration of Photon Diagnostic using
Spontaneous undulator radiation
- ④ Stable optics @ 230 MeV
- ⑤ Improvement of beam quality for
SASE-FEL operation
- ⑥ SASE-FEL

Summary on Schedule for installation and Commissioning 99

- 1) Undulator & experimental area
- 2) Module
- 3) Injector
- 4) Schedule
- 5) Discussion


1) Undulator & experimental area

Consists of Collimator, Undulator & Undulator vacuum chamber, Diagnostic blocks, experimental area.

⇒ ~ 30 m beamline are exchanged

Important milestones:

- 15.3.99 Start to disassemble EXP
- 22.3.99 Start to disassemble ACC4
- 19.4.99 Collimator components ready
- 19.4.99 Start collimator assembly
- 26.4.99 EXP area installed
- 26.4.99 Undulator ready
- 26.4.99 Diagnostic block ready
- 14.6.99 Final vacuum connection to exp and collimator
- 28.6.99 Ready for beam



G. Schmidt, -MPY-, 1.3.99

2) Module

Module 3 replaces module 1.

Important dates: 19.4.99 Module into Linac tunnel

14.6.99 Module ready to be cooled down

3) Injector

Work needed for installation of:

Balakin BPM

Balakin Kicker

Optimization of the gun elements (i.e. laser mirror)

Best time is at the end of the shut down in parallel to the alignment of the undulator


4) Schedule

Start of shutdown 15.3.99


Ready for commissioning 28.6.99

Ready for beam: Week 28 / 12.7.99

→ detailed information in the afternoon talks




G. Schütz



Undulator

203

As a result



HALUSCHKE/NTKAISER, MAR01/02:11

G. Schmidt

G. Schmidt, MPY, 1.3.99

5) Discussion:

room: 4b building: 1b
after the two other working groups.
Everybody interested is invited to participate.

BC area no changes needed up to now.

Discussion on: - Shut down planning.
- Commissioning.

Changes and correction to the Schedule for installation and Commissioning 99

-Time schedule seemed to be reasonable. ^{start: 15.3.99}
_{ready: 12.7.99}

-Main problem will be the work load and space in the clean room.

-No further components have been asked to be installed except one OTR foil for the EXP area

1) Module

Important milestones: 15.03.99 start of string assembly

until mid April module 1 must be taken out (2 weeks of work)

04.05.99 module ready to go into the tunnel

23.06.99 module ready for cool down

01.07.99 module cold

Agreed on:

Clean room is needed for cavity installation until 15.03.99.

After that date the clean room is used with highest priority for beamline components

2) Collimator

-All parts at Desy end of March.

-Built collimator up for checking if everything fits (2 weeks)

-2 weeks for cleaning

-then start of installation beginning of May.

3) Photon diagnostic

installed beginning of June inside the tunnel.

2 weeks for commissioning with permanent access to the tunnel needed, which can be done in parallel to the undulator alignment.

Commissioning was discussed in the working group

→ first tentative schedules proposed in the next weeks.

**Preliminary Agenda
for the TTF Collaboration Meeting
DESY, 1st - 3rd March 1999**

March 1st, Seminarroom 4a+b, Building 1b

9:00	Introduction and Future Planning	D. Trines	Chair:
9:30	Summary of Cavity Tests	M. Pekeler	S. Tazzari
10:00	FNAL Gun Status	H. Edwards	
10:20	Coffee Break		
10:50	Linac Operation Experience	M. Geitz	
11:10	RF Operation of two Cryomodules	G. v. Walter	
11:20	Modulators and Klystrons	J. Kahl/A. Gamp	
11:40	Status of Cryogenics	B. Petersen	
12:00	Lunch		
13:30	News from Collaborating Institutions		Chair:
	Saclay/Orsay		B. Aune
	INFN		
	FNAL		
	CERN		
	Univ. Wuppertal		
	INP Protvino		
	FZ Karlsruhe		
	Univ. Rostock		
	Argonne		
	TU Darmstadt		
	Others as requested		
15:30	Coffee Break		
16:00	Undulator Status	J. Pflueger	
16:30	Collimator Section	H. Schlarb	
16:50	Electron Diagnostics	P. Castro-Garcia	
17:10	Photon Diagnostics	J. Feldhaus	
17:30	Organisation of Working Groups		
19:30	Social Event (DESY Canteen, Annex)		

March 2nd

- 9:00 Working Groups
1) Cavities and Auxiliaries Seminarroom 4a, Building 1b
Conveners: B. Aune, D. Proch
2) Linac Operation and FEL Commissioning Seminarroom 4b, Building 1b
Conveners: T. Garvey, S. Reiche
Meeting on General Schedule (Time and Room to be announced)
G. Schmidt
17:00 Technical Board Room 292, Building 1d
C. Pagani

March 3rd, Seminarroom 4a+b, Building 1b

- 9:00 Summaries of Working Groups Chair:
Group 1: B. Aune H. Edwards
Group 2: S. Reiche
10:30 Coffee Break
11:00 Summary on Schedule for Installation and Commissioning - G. Schmidt
11:25 Next TTF-Meeting
11:30 AOB
12:00 End of Meeting

On Wednesday afternoon (starting at approximately 13:30) a Coupler Workshop is scheduled (organized by D. Proch).