

TESLA - COLLABORATION

Transparencies from the
TESLA Meeting, July 7-9, 1999 at DESY

DESY



July 1999, TESLA 99-13

TESLA Meeting at DESY, July 7 - 9, 1999

Contents of TESLA Report 99-13.....	I
Agenda	II
Welcome and Introduction, <i>D. Trines</i>	1
Linac Operation Results Until 15 March 99, <i>G. Schmidt</i>	8
Run 1/99 - Results, <i>S. Schreiber</i>	26
Status of Cavities and Auxiliaries, <i>D. Proch</i>	50
Nb Prototype of the Superstructure, <i>J. Sekutowicz</i>	64
Shutdown Activities, <i>H. Schlarb</i>	73
Progress on Controls, <i>K. Rehlich</i>	85
Undulator Status, <i>U. Hahn</i>	93
Photon Beam Diagnostics for the SASE-FEL at TTF Phase I, <i>R. Treusch</i>	114
Laboratory Talks	
Orsay/Saclay Activities, <i>T. Garvey</i>	123
News on TTF Activities at INFN, <i>C. Pagani, P. Michelato</i>	128
CERN Activities, <i>L. Lilje</i>	133
FZ Karlsruhe Activities, presented by <i>S. Wolff</i>	136
BINP Activities, <i>V. Balakin</i>	138
Progress on the FEL (DESY) Gun, <i>F. Stephan</i>	140
Mode Measurements at the Warm TTF Module 1 and Influence of Input Couplers (DESY, Rostock, Frankfurt), presented by <i>N. Baboi</i>	142
Working Group Summaries	
WG Cavities I, <i>B. Aune</i>	148
WG Cavities II, <i>P. Schmüser</i>	150
WG Commissioning and Experimental Program for the TTF Linac, <i>M. Castellano, T. Garvey, G. Schmidt</i>	159
TESLA-500 WG:.....	163
Positron Injector Linac, <i>V. Paramonov</i>	164
Spent Beam Line Collimation, <i>E. Merker, I. Yazynin</i>	169
Positron Source Before the IP, <i>R. Brinkmann</i>	177
Damping Ring Design Update, <i>W. Decking</i>	179
Multi-bunch Instabilities in the Damping Ring, <i>C. Burton</i>	184
Multi-bunch Beam Dynamics in Main Linac, <i>N. Baboi</i>	186
Beams with Different Energies (FEL Collider), <i>V. Tsakanov</i>	190
Estimate of Beam Halo, <i>R. Brinkmann</i>	196
Beam Position Measurement at the IP, <i>T. Scholz</i>	199

**Preliminary Agenda
for the TTF Collaboration Meeting
DESY, 7th - 9th July, 1999**

July 7th, Seminarroom 2, Building 2a (Please notice different room)

9:00 Welcome and Introduction
 9:15 Summary of Linac Operation
 10:00 Status of Cavities and Auxiliaries
 10:20 Superstructure Concept
 10:40 Coffee Break
 11:10 Shutdown Activities
 11:30 Progress on Controls
 12:00 Undulator Status
 12:20 Photon Diagnostics
 12:40 Organisation of Working Groups

- Cavities and Auxiliaries
 B. Aune/D. Bloess/P. Schmäser
- Commissioning and Experimental Program for TTF Linac
 M. Castellano/T. Garvey/G. Schmidt

14:00 Main Auditorium
 Colloquium in Memory of Björn H. Wiik

July 8th, (Rooms to be announced)

9:00 Working Groups
 17:00 Meeting of Technical Board
 19:00 Social Event (Annex of DESY canteen)

July 9th, Seminarroom 4a+b, Building 1b

9:00 News from Collaborating Institutions
 Saclay / Orsay
 INFN
 FNAL
 CERN
 FZ Karlsruhe
 Others as requested
 10:40 Coffee Break
 11:10 Summary of Working Groups
 12:40 Next Meeting
 AOB

July 8th, Seminarroom 5, Bld. 1b

9:00 TESLA-500 Working Group

Conveners: R. Brinkmann, O. Napoly

Preliminary programme: (final programme will be announced at the meeting)

Spent beam line and collimation; E. Merker
 Positron injector linac; V. Paramonov
 Damping ring design update; W. Decking
 Positron Source before the IP; R. Brinkmann
 Multi-bunch beam dynamics in main linac; N. Baboi
 Beams with different energies (FEL/collider); V. Tsakanov
 Estimate of beam halo; R. Brinkmann
 Non-linear Energy Collimation; N. Walker
 Beam Position Measurement at the IP; T. Scholz

Discussion on work to be done for TDR; all participants

**Scientific Colloquium
in Memory of
Prof. Dr. Bjørn H. Wiik**

Wednesday, July 7, 1999
at 2:00 pm

Am Mittwoch, dem 7. Juli 1999, findet um 14:00 Uhr das wissenschaftliche Kolloquium zum Gedenken an Bjørn H. Wiik statt. Dazu werden etwa 300 auswärtige Gäste aus dem In- und Ausland kommen.

Da im DESY-Hörsaal nur etwa 350 Personen Platz finden, wird das Kolloquium in den Seminarraum 4 und auch nach Zeuthen in Wort und Bild übertragen.

Ferner wird in das Foyer des DESY-Hörsaals und auch in den Vorraum vor dem Seminarraum 4 eine Tonübertragung geschaltet, um allen Besuchern die Möglichkeit zu geben, das Kolloquium zu verfolgen.

Wegen des so geringen Platzangebotes im DESY-Hörsaal werden die DESY-Mitarbeiter gebeten, insbesondere den Seminarraum 4 bzw. in Zeuthen das Foyer zu besuchen, um so in Gastfreundschaft den auswärtigen Gästen den DESY-Hörsaal zu überlassen.

Das Programm des Kolloquiums sieht folgende Beiträge vor:

Streichquartett Op. 27, 1. Satz von E. Grieg

Eröffnung des Kolloquiums - Prof. Dr. Albrecht Wagner

Worte des Erinnerns • Reminiscence and Recollection

Erster Bürgermeister Otwin Runde
MDG, Dr. Hermann Schunck, BMBF
Prof. Dr. Jürgen Lüthje, Universität Hamburg
Prof. Dr. Ditlev Ganten, HGF
Prof. Dr. Luciano Malani, CERN
Prof. Dr. Ralph Eichler, Wissenschaftlicher Rat

Maury Tigner Impact of Superconductivity on Particle Physics
Burton Richter The Role of Electron-Positron Colliders for Particle Physics
Coffee/Tea Break
Chris Llewellyn-Smith Deep Inelastic Scattering
Jochen Schneider Synchrotron Radiation Research at Particle Physics Laboratories
Volker Soergel Bjørn H. Wiik and DESY

Deutsches Elektronen-Synchrotron
Hamburg, Germany

TESLA

March 25th Oberbergamt Clausthal-Zellerfeld
had invited administrative bodies from communities and county and also environmental interest groups to set the scope for the Environmental Impact Study for TESLA

"Scoping Termin"

Project was presented by DESY
Civil engineering by engineering bureau
Positive atmosphere; mainly constructive criticism

Part of the procedure to secure the legal framework for the construction of TESLA

April 19 th Ministry of Education and Research
Frau Bulmahn
intends to recommend to the German Science Council
to evaluate TESLA in 2001




Hochfrequenz-Photoinjektoren als Quellen für Elektronenpakete extrem kleiner Länge und Emittanz

Zusammenfassung

DESY plant in Zusammenarbeit mit anderen HGF Zentren und einer grossen Zahl internationaler Partner ein internationales Institut für Angewandte- und Grundlagenforschung in Deutschland. Diese Anlage wird weltweit einmalige Forschungsmöglichkeiten in Bereichen von der Elementarteilchenphysik über die Festkörperforschung, Chemie und Materialwissenschaften bis hin zur medizinischen Diagnostik und Molekularbiologie anbieten. Die laufenden Forschungs- und Entwicklungsarbeiten für TESLA werden zu einem integrierten System erst für einen supraleitenden Linac und einem SASE FEL im VUV und weichen Röntgenbereich führen (TESLA Test Facility, TTF).

Für den FEL und den Linac-Betrieb werden Elektronenstrahlen mit höchster Strahlqualität benötigt. Deshalb wird bei DESY ein Entwicklungsprogramm im Bereich der Hochfrequenzelektronenquellen mit dem Ziel einer Optimierung der Strahlqualität erreicht werden, wie z. B. der Betriebsparameter, verfolgt. Um diese Ziele zu erreichen sind neben einer Weiterentwicklung im Bereich der Simulationsrechnungen und theoretischer Ansätze insbesondere qualitativ hochwertige Messungen der Strahlmittanz unabdingbar. Nach bisherigen Erfahrungen ist ohne ein Experimentierprogramm, also nur aufgrund von Rechnungen, kein nennenswerter Fortschritt zu erwarten.

Beteiligte Institute:



Superconducting RF Cavities of Ultimate Performance

Abstract

DESY plans, together with other HGF centers and a large number of international partners, to build the Tera Electronvolt Superconducting Linear Accelerator TESLA as an international institute for pure and applied science in Germany. This facility, comprising an electron-positron collider with a center-of-mass energy of at least 500 GeV and a Free Electron Laser in the X-ray regime, will offer world-wide unique possibilities for pure and applied research in areas ranging from elementary particle physics via solid state physics, chemistry and materials science to medical diagnostics and molecular biology.

The Forschungszentrum Jülich in collaboration with a large number of international partners is pursuing the design of the European Spallation Source ESS as the next generation neutron source to secure Europe's leading role in applying neutron beams to basic and applied research in physics, chemistry, materials science, life sciences, engineering sciences and Earth sciences.

Both facilities rely heavily on superconducting radio-frequency cavities to accelerate high currents of electrons or positrons in TESLA and of negative hydrogen ions in the ESS to high energies. Their main advantages in comparison with normal-conducting accelerating structures are the much reduced operational costs and the improved beam quality.

In order to fully exploit the capabilities of superconducting cavities fabricated from solid niobium, an extensive R&D program is proposed concentrating on the following four topics:

- Development of production methods for niobium of higher purity,
- Improved chemical treatment methods of the inner (radio frequency) surface of the cavities,
- Reinforcement of the mechanical stability of the cavities,
- Development of seamless cavities.

It is intended to collaborate in the R&D program with other HGF institutions (GKSS, HMI), with institutes and universities (Bundesanstalt für Materialforschung, CERN, RWTH Aachen, IN2P3 Orsay, CE-Saclay, Universität der Bundeswehr) and with industry (ACCEL, F.I.T. Messtechnik, Heraeus).

Want to have first cost evaluation of the whole project beginning of next year.

Also required manpower for the construction, installation and commissioning period.

INFN will design and evaluate
damping rings
cryostats
cavity production


INR Troitsk will design and evaluate
positron linacs

IHEP Protvino will design and evaluate
beam dumps
collimation system

Orsay/Saclay will design and evaluate
injectors
beam delivery system
cavity production

Have established a planning group

BESSY
+ HMI
JOINED
WORK ON TTF
+ FEL BEAMLINES



Obtained results from two independent studies on cavity preparation to module assembly

Positiv: no problem to process 20000 cavities within three years

Surprise: fraction of personnel to total cost is dominant main part therein module assembly differences between two studies have to be evaluated

Studies underway or in preparation:



cavity production with present technology


parallel studies by INFN and Saclay are envisaged

klystron production


modulator fabrication

wave guide production





IRAF'S COMPYNT THIN52, MAY24/142P




1999

2000

2001

2002



Linac operation results until 15. March 99

Introduction

Diagnostic changes due to 1 MHz bunch repetition rate

- BPM developments
- Toroids for beam current measurement

Results of emittance measurements:

Comparison between pepper pot and phase space tomography measurements

Summary module operation

Summary of achieved beam parameters

Conclusion



Goal of the run

Preparation of the linac for the installation of the FEL

Commissioning of new beamline elements

- 1) New injector: FNAL Gun and new diagnostics
- 2) Bunch compressor π
- 3) Cryo Module 2



New diagnostics had to be made operational and beam parameters for the FEL had to be established.

->First results have been presented during the TESLA Meeting, March 1-3, 1999 at DESY

For High Energy collider: HOM and RF steering experiments (presented TESLA Meeting, March 1-3, 1999 at DESY)

Performance of the TTF-FEL Phase I

G. Schmidt, -MPY-, 6.07.99



Diagnostic changes due to 1 MHz bunch repetition rate

BPM developments

The 1 MHz bunch repetition rate was new. Change in electronics and special delays for the signals to the ADC's were needed.

At the end of the run all BPM's were working. Calibration with steerer changes were done.

Resolution around 10 micro m can be expected for warm cavity BPM's

All BPM's show modulation of the offset along the macro pulse

Toroids for beam current measurement


Toroid system was adapted to 1 MHz

All Toroids were working at the end of the run and calibration of current was done to 20 %. Problem occurred with saturation effects at higher beam currents.

Bunch Position Measurements (March 99)

For each steerer setting
measure 10 pulses and
calculate average bunch position

Have Steerer stepsize




Goal:
Calibration of Reentrant BPM in straight section of BC2
⇒ 1 V @ 8 nC, @ 1 mm

Beam Energy after Module 1	84.4 MeV
# Bunches	5 - 30
Bunch Spacing	1 μs
Bunch Charge	1 - 8 nC

mostly beam compensation off

- used for position measurements: design resolution
- 2 Cavity Monitors (No. 1,3): 10 μm
 - 1 Reentrant BPM (No.2): 1 μm
 - 1 Strip Line (No. 4): 20 μm
 - X/Y steerer (No. 5)




$$\Delta I = 0.2A \hat{=} \Delta X, Y = 400\mu m$$


Variation over 30 bunches: Max-Min ~ 0.3mm (X/Y)

- X: S-Shape
- Y: Peak @ 4. Bunch
- MORE DATA NEEDED TO IDENTIFY ERROR SOURCES:
 - DISPERSIVE EFFECTS
 - TEAR OFFSET IN MODULE
 - ...
- X: PULSE-TO-PULSE VARIATION ⇒ TOS. SHIFT BY STEERER



Strip Line ACC2.ADC4: RUN CAL 8nC 110399 11-Mar-1999 13:55:58




Cavity ACC2.ADC2: RUN CAL 8nC 110399 11-Mar-1999 13:55:58




Different shape of the offset along the run & have
 -> depends on steering-inte-modality



BPM 1BC2, steerer ACC1




Signals 1BC2/y, position and jitter




Signals 1BC/x, position and jitter

BPM 1BC2, x, steerer ACC1




Signals 1BC2/x, position vs. steerer




Signals 1BC2/x, position for st-value

BPM 1BC2, x, steerer ACC1




Signals 1BC2/x, steerer ACC1




Signals 1BC2/x2, steerer ACC1, fine

BPM 1BC2, y, steerer ACC1



Signals 1BC2/y, steerer ACC1



Signals 1BC2/y, steerer ACC1, fine

No real understanding of emittance growth to up to 80 mm mrad in the exp area.

Emittance measurement in BC2 and EXP

- ⇒ show good agreement in between error bars
- ⇒ emittance growth with number of bunches
- ⇒ multi bunch emittance was measured

Comparison of pepper pot and phase space tomography measurements at the injector (ALDs)

Emittance measurement along the linac

Improved analysis of

pepperpot (slit mask) data

taken on 5.3.'99

Frank Stephan
FDET

• Introduction + Definitions

• Procedure

• Results

• Errors

• Conclusions

• Outlook

Injector settings

• magnets: trim = 0.0

Sol. 1 = 158, 165, 176

Sol. 2 = 86, 90, 96

← scan

gun steerer: hor. = -0.3, vert. = +0.8

CC steerer: hor. = 0.0, vert. = +0.3

S.HS INJ1 = 0.0, S.V6 INJ1 = 0.0

PP → doublet Q.1 INJ1 = 0.0 = Q.2 INJ1 !

screen →

• gun: SP voltage = 35 MV

power reading at gun ≈ 2.27 MW

SP phase = -1150 (ok!)

• laser: $U_{ctrl} = 1.5 V$ ⇒ Pk-Pk (ICT_{gun}) ≈ 20 mV

$\phi_{iris} \approx 3 mm$




d.h. ≈ 1 nC

• cap. cav.: phase = 141.29° (ok!)

gradient = 11.3 MV/m

• data taken on Fr. 5. March 1999 8:00 → 14:00

by D. Sertore + F. St.



$$\epsilon_1 = \epsilon_2$$

$$\epsilon_2 = \sqrt{\langle X^2 \rangle \langle X'^2 \rangle}$$

$$\langle X^2 \rangle = \frac{\sum_{i=1}^M (x_i - \bar{x})^2}{M} \quad \frac{3 \text{ spots}}{M = N_1 + N_2 + N_3} \quad \frac{N_1(0 \text{mm} - \bar{x})^2 + N_2(1 \text{mm} - \bar{x})^2 + N_3(2 \text{mm} - \bar{x})^2}{N_1 + N_2 + N_3}$$

$$X' = \frac{X - \bar{x}}{385 \text{ mm}} \quad \left(\Rightarrow \overline{X'} = 0 = \overline{X'}_{N_1} = \overline{X'}_{N_2} = \overline{X'}_{N_3} \right)$$


distance between slit mask and screen

$$\langle X'^2 \rangle = \frac{1}{M} \sum_{i=1}^M X_i'^2 \quad \frac{3 \text{ spots}}{N_1 + N_2 + N_3} \quad \frac{N_1 \langle X'^2 \rangle_1 + N_2 \langle X'^2 \rangle_2 + N_3 \langle X'^2 \rangle_3}{N_1 + N_2 + N_3}$$

7.2 in last digit

ION PUMPS
Toroids Lmac

165-90-pp2.his




fit:

$$f = c + g_1 + g_2 + g_3$$


$$g = P_1 \cdot \exp\left\{-\frac{1}{2} \left(\frac{x - P_2}{P_3}\right)^2\right\}$$

projection on y axis

165-90-pp2.his



picture 165-90-pp2




picture without clear x-rays

20b

176-96-pp2.his

ID	30
Entries	39277
Mean	25.78
RMS	12.86
UDFLW	.0000E+00
OVFLW	.0000E+00
ALLCHAN	.39277E+05
χ^2/n	.8527E+05 / 27
P1	512.7 ± .2857
P2	964.0 ± .7322
P3	15.89 ± .1410E-02
P4	1.556 ± .1454E-02
P5	754.9 ± .7498
P6	24.42 ± .1751E-02
P7	1.591 ± .1715E-02
P8	224. ± .6944
P9	32.66 ± .1201E-02
P10	1.920 ± .1270E-02




projection on y axis

20a

158-86-pp2.his

ID	30
Entries	43009
Mean	24.06
RMS	12.47
UDFLW	.0000E+00
OVFLW	.0000E+00
ALLCHAN	.4301E+05
χ^2/n	.8256E+05 / 27
P1	535.5 ± .3135
P2	710.8 ± .7337
P3	13.04 ± .3370E-02
P4	2.200 ± .3067E-02
P5	1078. ± .6187
P6	22.68 ± .6189E-02
P7	3.648 ± .7816E-02
P8	387.7 ± 1.944
P9	29.41 ± .3325E-02
P10	2.010 ± .5298E-02




projection on y axis

RESULTS

olenoids	name	# bunches	ϵ (in π mm mrad)	
58-86	pp1	20	0,329	
	pp2		0,295	
	pp3		0,300	
	pp4		0,300	
				0,31
				$\pm 0,02$
	55-90	pp5	10	0,285
		pp6		0,254
			0,27	
			$\pm 0,02$	
176-96	pp1	20	0,232	
	pp2		0,240	
	pp3		0,211	
	pp4		0,250	
				0,23
				$\pm 0,02$
	pp5	10	0,129	
			0,107	
				0,12
				$\pm 0,02$
	pp1	30	0,264	
				$\rightarrow 0,26$
pp2	20	0,237		
		0,208		
		0,245		
		0,232		
			0,23	
			$\pm 0,02$	
pp6	10	0,147		
		0,175		
			0,16	
			$\pm 0,02$	




norm. stat. emittance
 \uparrow in π mm mrad
 $(\gamma = 32)$



Summary of systematic errors:

norm. error in γ -plane
measured by tomography

(directly after
pp measurements)



$$\epsilon \rightarrow \epsilon + 6\% + 5\% \pm (4\% \oplus 2.6\% \oplus 5\% \oplus 1\%)$$

\uparrow #splits \uparrow ϵ \uparrow w \uparrow Digits

$$\Rightarrow \underline{\underline{\epsilon \rightarrow \epsilon + 11\% \pm 7\%}}$$

CONCLUSIONS

smallest measured emittance at $I_1 = 165 \text{ A}$
 $I_2 = 90 \text{ A}$
($\gamma = 32$)

with 10 bunches:

$$\epsilon_N = [4,2 \pm 0,6 (\text{stat.}) \pm 0,3 (\text{sys.})] \pi \text{ mm mrad}$$

with 20 bunches:

$$\epsilon_N = [8,3 \pm 0,6 (\text{stat.}) \pm 0,6 (\text{sys.})] \pi \text{ mm mrad}$$

(comparison with tomography in γ -plane:
 $\epsilon_N = (9,5 \pm 3) \pi \text{ mm mrad}$)

⇒ higher precision, even higher precision for parameter scans
(but no information about beam dynamics)

⇒ clear increase of emittance with # of bunches
(e.g. slope on rd probe signal)

(single bunch emittance may be not measurable with existing hardware)

⇒ emittance minimum at $I_1 = 165 \text{ A}$, $I_2 = 90 \text{ A}$ may be because
2 spot shape of electron beam

→ probably not optimal setting (→ higher)
for uniform transverse e-beam profile

UNLOCK



• install slits with 0.5mm distance correctly
and use these slits!
→ smaller uncertainties!

• to analyse data in ttf environment
CERNLIB (maglib, prolib, packlib, PAW) must be installed

• helpful: look at OTR using a mirror
→ exclude X-rays

• redo parameter scans with homogeneous transverse
e⁻ beam profile

QUADRUPOLE SCAN



Location of the emittance measurement


Phase Space Tomography

reconstructed normalized emittance



$$\epsilon_x = (5.5 \pm 2.5) \text{ mm mrad}$$

$$\epsilon_y = (9.5 \pm 3.1) \text{ mm mrad}$$



at TTF photo-injector, $E = 16 \text{ MeV}$, $Q = 1 \text{ nC}$.





Backprojected phase space



Backprojected phase space





Beam Parameters:
 $\epsilon_x = 80 \text{ mm mrad}$
 $\alpha_x = 1.6$
 $\beta_x = 3.1 \text{ m}$



Linac Emittance Measurement:
 BC2, $Q = 1 \text{ nC}$, $E = 80 \text{ MeV}$, 15 bunches, horizontal plane,
 standard injector settings

Linac Emittance Measurement:

BC2, Q = 1nC, E = 80 MeV, 15 bunches, vertical plane, standard injector settings



Beam Parameters:

$$\epsilon_x = 45 \text{ mm mrad}$$

$$\alpha_x = 1.0$$

$$\beta_x = 1.5 \text{ m}$$

Results of the emittance measurement

- 1) We measured not a single bunch emittance. What was measured was the multi-bunch phase space volume. Beam jitter causes an emittance growth. A minimum number of bunches is needed to get the signal above the dark current illumination of the OTR foils. The single bunch emittance is therefore smaller
 - 2) The multi-bunch emittance at the injector is between 7 and 10 mm mrad (measured by pepper pot and phase space tomography depending on the number of bunches).
 - 3) A growth of the normalized emittance was observed nearly in all measurements in the bunch compressor and experimental area. (Quad scan and phase space tomography)
 - 4) The reason of the emittance growth is not identified. Possible explanations are:
 - growth of the multi bunch emittance by offsets in the modules and HOM effects
 - ⇒ find a way to measure single bunch emittance, measure the emittance as a function of the offset in the module or use a BPM reading to see drift of beam center and correct the emittance
 - A part of the growth can be explained by errors of the optical system used (depth of field, diffraction, bad optical elements used)
 - ⇒ Improvements of system will be installed for next run
- ⇒ Nevertheless need deeper understanding of space charge effects and compensation between capture cavity and module 1.

Summary of module operation

Max gradient in module 2 with beam (1nC at 10 to 30 micro seconds pulse length: 18.6 MV/m (Shown with 2 Klystrons for module 1 and 2. On module 2 no regulation was used)


Max gradient without beam 20.5 MV/m (500 to 800 micro seconds flat top)

But: Long term operation with gradients larger than 18 MV/m not possible due to e- and vacuum events in the main couplers further processing needed

Dark current from module 2 at high gradient was significantly reduced due to processing.

Standard gradient: ~10 MV/m

The beam energy was limited between 160 and 180 MeV during stable operation with 1 Klystron by cavities in module 1 and the equal power distribution between modules



Summary of achieved beam parameters

For 1 nC case:

Energy spread $\leq 0.3\%$ at injector and linac
EXP3 _(achieved with STK) => sufficient for FEL

Standard beam energy between 160 and 180 MeV
limited by cavities in module 1
=> new module 1 should allow to go to 230 MeV

Emittance at injector = 5 mm mrad for 10
bunches _{- 9 mm mrad in second plane}
Emittance growth observed along the linac but
not understood => Space charge effect?
=> enough for undulator installation but not
good enough to reach saturation.

For 8 nC:

Energy spread $\leq 1\%$ at the injector
And the possibility of beam transport along the
linac was shown.
=> needed for RF calibration

28

Conclusion

Diagnostic improved during last run. Nearly all
BPM's and toroids were working at the end of
the run.

Bunch compressor works predictable and
compression shown.

The Phasing between module 1 and 2 for the
Bunch compressor operation was difficult and
reproducibility was not always possible.

Understanding of different methods to measure
the bunch length is improving

Ready for lasing?


Yes and no. Main problem seems to be the
understanding of optics and beam emittance
along the machine. *(real or by measurement method) 22*
A method to measure the twiss parameters at
different points along the machine exists.
-> FEL will show if emittance growth exists.



RF, bunch compressor and in principle the
injector have proven the ability to deliver a
sufficient beam quality for the startup of the
FEL experiment.

Run 1199
 RESULTS Part I
 S. SCHREIBER
 DEST.
 TTF matching
 7.9.89
 Gun
 Cathode
 Laser
 Bunch length

TTF Injector II

Train of 800 electron bunches, train length = 0.8 ms
 Repetition rate 10 Hz
 Bunch charge = 8 nC
 Bunch length = 1 mm
 Energy = 20 MeV
 Emittance (x,y) = 20π mm mrad





General running experience

1. The last run started mid Dec 38

until mid Mars 93 ≈ 2000 h

2. the conditioning of the rf gun + window

went smooth, we reached nominal gradient (35 MV/m or 2.2 MW), short pulse (50 ps) at 1 Hz before Xmas

3. the availability of the rf gun + laser was close to 100%, except one modulator repair + one laser repair

4. the injector delivered beam to test the two installed TESLA modules, to test

the new bunch compressor and for various experiments (short, bunch length, emittance etc.)

the overall performance of the new injector is satisfactory

5. further improvements (\rightarrow emittance for FEL operation) and more detailed studies on beam parameters and beam diagnostics are scheduled for the next run in Summer '93




RF Gun Low Level RF System


Digital control system

- 2 TMS C40 DSPs
- table driven feedforward
- control by adjusting feedforward table between pulses ("adaptive feedforward")


28



Pulse train (SHG) measured at the output of the laser system



- Energy per micropulse at 1.06 μm : $E = 200 \text{ uJ}$
- Accuracy of synchronization: $dt = 1 \text{ ps}$
- Pulse width (FWHM) at 1.06 μm : $t = 25 \text{ ps}$
at 0.26 μm : $t = 12 \text{ ps}$
- Energy stability from shot to shot at 1.05 μm : $\pm 1 \%$
at 0.53 μm : $\pm 2 \%$



The Lasersystem

3

Performance

- Energy:
 - up to 100 μJ per micropulse, largely sufficient for 8 nC
 - stability (shot to shot/within train) better than 5% rms
- Phase:
 - stability better than 1 ps
 - drift seen with short pulses, fixed by forcing laser phase to 0 using the phase feedback system
 - occasional drift of resonator length
- Transverse profile:
 - flat top, uniformity not satisfactory yet
 - spatial filter in UV to be included, conversion green to UV to be optimized
- μ Pulse length:
 - phase scans suggested a long pulse, confirmed by streak camera and autocorrelation measurements ($\sigma = 15$ ps in UV)
 - fixed by replacing the oscillator laser head
 - now: $\sigma = 10$ ps in IR, 7.1 ± 0.6 ps in UV


The Lasersystem II: Reliability

- Uptime:
 - is running since mid December (except Xmas)
 - in total 2000 hours with 1 Hz or $8 \cdot 10^6$ shots
 - uptime 99 %, available for beam 97 %
- Failures:
 - flashlamps of pulse train oscillator (PTO) exchanged after $8 \cdot 10^6$ shots
 - lost 4 hours + 2 shifts with very unstable conditions
 - complete PTO laser head exchanged to cure pulse length
 - Sparc cpu in laser VME had to be replaced
- Server:
 - laser server and control program is running smoothly and stable
- Interlocks
 - no failure of personal laser safety interlock
 - access to tunnel with laser beam on was not established in a way, that operators could make use of it.
 - no failure of technical laser safety this time (we had one failure in May 1998), SPS is working fine



Cathode System

INFN Milano LASA
DESY (Vacuum equ.)


- Cs₂Te cathode: high QE (>1 % over months)
- The cathode system allows to change the cathode without breaking the vacuum
This is essential to maintain the high quantum efficiency of the Cs₂Te cathode



- The cathodes are prepared off side




February 1999



Quantum efficiency of cathode #2

Quantum efficiency: $QE = (5.9 \pm 0.6)\%$
 over the test period of one week



Cathode #2



MIDFIELD
 SCIENTIFIC
 SERVING

→ This cathode has a
 → No. mirror surface finish
 → than Cs₂Te
 Cathode #1 QE ~ 0.5%

Charge transmission of the gun



MICHELATO/SCHREIBER/SERTOLE


\rightarrow 8 nC } nominal
 \leftarrow 1 nC }

\Rightarrow linear up to ~ 16 nC Laser spot ϕ 40 mm

Observation of space charge



Effects:

energy laser good for 2.4 nC: constant
 \rightarrow charge extraction reduced
 for lower fields





SERTOLE/SCHREIBER/MICHELATO

ϕ laser on cathode = 3 mm
 — from Gauss' law




example for two different laser energies
 but same charge density (by use of an
 attenuator)



Ac. 2 current e Br2

36

Cathode #1



Dark Current


Cathode #1 ~ mA

Cathode #2 50 pA @ 42 MV/m


< 20 pA @ 35 MV/m

37

Dark Current Cathode #2



Gun Power: Power 2.5 MW (37 MV/m)



Beam ON

Beam OFF

Gun RF OFF

Dark Current = \rightarrow **0.6 V = 100 pA** (not linear)


Dark current measured with

Wentz cavity BPT $\approx 0.3 V \approx 30 \mu A$


Cathode #2, 37 MV/m $0.2 V \approx 20 \mu A$

\rightarrow consistent with ICT measurement
20-25 μA


Cathode #2



Cathode #2, rfon, beam off




Example of beam current




39

measured with ICT's & towards

transmission in the injector ~ 100%




Towards MNC



example for MNC
T2, T3, T4, T7

Bunch length measurements Run 1/99

ICT B2
example for current monitoring with
ICT B2 (downstream CC)




stability $\pm 0.1 \text{ nC}$ of $0.7 \text{ nC}/\text{min}$
rms $\sigma \approx 0.03 \text{ nC} \pm 5\%$

measurements were done with the following methods:

- ∴ Streak camera - synchrotron radiation
@ Dipol (HE) - laser pulses
- ∴ Martin-Publett - Interferometer - HE Section (Exp)
- ∴ Josephson Junction \rightarrow no results yet
- ∴ others !

Auto correlation method for laser pulse length measurements




measure green signal @ PD (photo diode)
as a function of delay


⇒ direct measure of pulse length
(1/2 - 300 ps delay ~ 1 ps)

but: we cannot measure 100 ps pulse length
as simple as this


laser
auto correlation - before repair
@ 1047 nm



Laser
 autocorrelation - after repair
 @ 1047 nm



Principle layout of a Streak Camera




- ARP Streak Camera from LAL/Orsay
- Resolution of the photo tube 2 ps
- Measurement performed with
 - Synchrotron Radiation at the HE Dipole
 - Laser

Laser

43

before repair of Osc.




$\sigma_{UV} = 16 \text{ ps}$ for nominal flashlamps current

$\sigma_{green} = 20 \text{ ps}$



Laser

after repair of osc.




$\sigma_{UV} = 7 \pm 1 \text{ ps}$

Bunch length measured
 Dipol in EXP3 with Synchrotron
 radiation




44


An example of beam diagnostics: Bunch length measurements using coherent transition radiation



- Martin-Puplett Interferometer
- Transition radiation is produced at an aluminum foil hit by the beam
- The coherent part of the transition radiation is split in a Michelson-type interferometer. After recombination, the interference pattern is measured with pyro-electric detectors.
- From this, the bunch length is determined to be 1.5 ± 0.5 ps (0.45 ± 0.15 mm) rms.




The Difference Interferogram




- ⇒ 2 Detectors measure "anticorrelated" signal
- ⇒ Correlated fluctuations due to instabilities of the electron beam
- ⇒ Normalized Difference Interferogram (NDI)

$$NDI = \frac{\text{Detector 1} - \text{Detector 2}}{\text{Detector 1} + \text{Detector 2}}$$



- ⇒ The NDI is a smooth function, statistical fluctuations within the size of the data points
- ⇒ Time of measurement: ca. 15 minutes

Kramers-Kronig Reconstruction



Normalized difference interferogram:

↕ Fourier Transformation

Form factor:

Extrapolation to:

$f \rightarrow 0$: 2nd order polynomial function

$f \rightarrow \infty$: exponential function

Minimal phase (Kramers-Kronig)

Assumptions:

Causality

Extension of form factor into complex plane



$$\psi_m(\omega) = \frac{2\omega}{\pi} \int_0^\infty \frac{\ln|f(\omega_0)|/|f(\omega)|}{\omega^2 - \omega_0^2} d\omega_0$$

↔ $5.2 \text{ ps} \approx 0.6 \text{ nm}$

Fourier Transformation:


$$\rho(t) = \int_0^\infty |f(\omega)| \cos(\psi_m(\omega) + \omega t) d\omega$$

Magnetic bunch compression



Measurement of the longitudinal charge distribution

(GEITZ)



R_{56} transforms initial energy spread into final bunch length

+ off-crest acceleration:

$$R_{65} \text{ transforms initial bunch length into final energy spread}$$

$$R_{66} = \frac{\text{initial beam energy}}{\text{final beam energy}}$$

48

Matrix multiplication

$$\begin{pmatrix} L \\ \frac{\Delta E}{E} \end{pmatrix}_{\text{final}} = \begin{pmatrix} 1 & R_{56} \\ R_{65} & \rho \end{pmatrix} \begin{pmatrix} L \\ \frac{\Delta E}{E} \end{pmatrix}_{\text{initial}}$$

where $\rho = R_{56} R_{65} + R_{66}$


Let $\rho \rightarrow 0$:

$$\frac{\Delta E}{E}_f = R_{65} L_i \quad \text{at} \quad R_{56} = -\frac{R_{66}}{R_{65}}$$



Limits: \Rightarrow Resolution of the spectrometer dipole magnet

\Rightarrow Assumption on beam transfer, impact of non-linear wake-fields, transverse-longitudinal coupling


TTF measurements:



$\Rightarrow L_i = 1.9 \text{ mm}$



$\Rightarrow L_i = 215 \mu\text{m}$



Summary

- ∴ We had a successful run with the new injector (mid. Dec 88 - mid March 89)
- ∴ Smooth conditioning of the gun + rf window design of pulse length reached (800 fs)
- ∴ at design gradient (35 MV/m)
- ∴ availability of gun + cathode + laser 98%
- ∴ the injector delivered routinely beam for TESLA experiments (modules, HOM, bunch compressor studies etc.)

⇒ next run in summer will concentrate on beam for TTF/FEL experiments with an undulator installed
emittance!

Status of Cavities and Auxiliaries

D.Proch

- I Cavity measurements since last TTF meeting
- II Remaining cavities of second production
- III Third cavity production
 - order of Nb material
 - order for cavity production
 - time schedule
 - improved eddy current scanner for Nb sheets
- IV Status of input couplers, tuners

D.Proch, TTF meeting july 99

1

Cavities for module 3

4 cavities from ACCEL (S28, S29, S30, S32) and 4 cavities from Dornier (D39, D40, D41, D42) selected for module 3.

Average gradient in the vertical test was:
25.4 MV/m

All cavities are equipped with He vessel

4 cavities are equipped with processed cold part of main coupler

3 (+1) cavities have been tested in
CHECHIA

2 additional main coupler are processed
and 2 more additional main coupler are
under processing -> all cavities will be
equipped with a processed cold window

29

I Cavity measurements since last TTF meeting

5 cavities for Rossendorf (R1, R2, R4, R5, R6)


same design, material, manufacturer, treatment as TTF cavities

but: changed LHe vessel connection, cannot be exchanged with TTF cavities


8 cavities for TTF (A16, A17, A18; S33, S35; C46, C47; Z49)

1 single cell cavity (1S4) of the electro-polishing program


D.Proch, TTF meeting july 99
2



With another calibration, fields above $30 \frac{MV}{m}$ reached, but this calibration was done with unstable bath-temperature conditions!!



$\Rightarrow 29 \text{ MV/m}$ are more (between) than $> 30 \frac{MV}{m}$
 (remains lower in (S.E. = ...))




27

Quench limits

first production - S7, S8, S9, S10, S11, S12
A13, A14

$\Sigma N = 7$


Σ cavities = 17




second production - S34, S36, C43, C45
C48, C50 - 2 cavities

$\Sigma N = 9$

Σ cavities = 27



power/quench limit of cavities
vert. tests, march-june 99



gradient [MV/m] $\Sigma \Sigma_{acc} = 24$


Remaining cavities after modules 1, 2, 3

cavity	E _{acc} ≥ 25	E _{acc} ≤ 25	n _o E _{acc}	comments
d1		23.1		module 1, new flange
d2	25.6			module 1, new flange
d3		20 (25)		module 1, new flange
a16		22.9		new flange
a17	25.5			new flange
a18	27.8			new flange
s31		14(28)		
s33		20.4		
s35		21.2		
s36			x	
d37		20.3		
d38		19		
c44	25.2			
c45			x	
c46	28.9			
c47		22		
c48			x	
z49		19.4		
z50			x	delivery Sept 99
z51			x	delivery Sept 99
z52			x	delivery Sept 99
z53			x	delivery Sept 99
z54			x	delivery Sept 99
Σ 23	5	10	8	

S34 E1 NFF: R09UE

S34

$$S_{1/5} = \frac{S_{1/5}}{0.7} = 2.8.4$$



FS

II Remaining cavities of second production

5 cavities with $E_{acc} \geq 25$ MV/m

7 cavities with $25 \text{ MV/m} \geq E_{acc} \geq 20 \text{ MV/m}$

3 cavities with $E_{acc} \leq 20$ MV/m

8 cavities not yet measured

Σ 23

Cavities needed:

8 cavities for module 1*

8 cavities for module 4

==> one module will operate at $E_{acc} \geq 25$ MV/m
second module will operate at $E_{acc} \geq 20$ MV/m

D.Proch, TTF meeting july 99

3

III Third cavity production

- Nb is ordered for another 30 cavities, delivery already started
- bids for 24 9-cell cavities and 6 modified superstructure cavities are received from ACCEL, CERCA and ZANON
- only one company meets required delivery schedule of
-first delivery end of January 00
-delivery rate of 5 cavities per month
- contract will be signed this week, Pönale for late delivery is agreed on by the contractor

D.Proch, TTF meeting july 99

4


55



Improved eddy current scanner for Nb sheets

- First eddy current scanner operated by scanning the Nb sheet line by line
===> start and stop of the scanning head excited mechanical vibrations. This noise limits the ultimate sensitivity.
- New system rotates the Nb sheet continuously (100 rpm), scanning head is placed like the tangential arm of a record player
- first laboratory set up was used to scan the first 160 new Nb sheets:
===> higher sensitivity is demonstrated
faster measuring time (10 instead of 25 minutes)


D.Proch, TTF meeting july 99

5





Heraeus Sheet Nr. 28



Heraeus Sheet Nr. 28



*crossed section of superstructure - Corrosion
in central region No. 28,
with corrosion in the
area*

x200

IV Status of input coupler, tuner

Input coupler:

TTF2 10 new couplers are fabricated, processing just started, they need wave guide windows

TTF3 20 new couplers are under fabrication, delivery at end of 99, no wave guide windows needed

Short comment about the input coupler workshop, April 26-27,1999:

-RF power of superstructure coupler fixed to 1 MW (2MW, including TESLA upgrade), fixed coupling

-understanding of RF processing: desorption of gases by low energy electron impact

-lambda/2 coax window operated up to 1 MW

- input coupler workshop November 99

D.Proch, TTF meeting july 99

Summary

- $\langle E_{acc} \rangle$ of vertical cavity tests approaches the TESLA demand of 25 MV/m
- Quenching of some cavities around $E_{acc} = 20$ MV/m needs further investigation
- There are enough cavities available for completion of the next two module 1* and module 4. Average accelerating gradient is expected to be 25 MV/m for one module, slightly below for the other one
- 24 new 9-cells cavities will be fabricated until summer 2000
- Amongst the auxiliary components, the wave guide windows are critical in respect to the time schedule

D.Proch, TTF meeting july 99

Nb PROTOTYPE OF THE SUPERSTRUCTURE

N. Baboi, R. Bandelmann, H. Chen, B. Dwersteg, M. Ferrario,
 H. Kaiser, G. Kreps, M. Liepe, C. Martens, A. Matheisen,
 W.-D. Möller, C. Pagani, H.-B. Peters, E. Plawski, D. Proch,
 V. Puntus, P. Schmüser, J. Sekutowicz, W. Singer, G. Weichert,
 A. Zavadsev

64

I Introduction

Why?

The hope is that the proposed superstructure will increase:

- number of cells fed by one input coupler (impact on costs),
- the effective gradient in both linacs (impact on performance).

What?


The aim is to build Nb prototype of the superstructure made of four 7-cell cavities and to test it with the beam in January-February 2001.

How?

To minimize the effort we would like :

- to use many of the existing components,
- to make only minor changes in the infrastructure and in the cryostat.

II Components





-in this prototype all sub-units (7-cell cavities) are connected by a superconducting junctions (proposed by A. Matheisen) .

- Cavities

- mid cells and stiffening rings are of the same shape as for TTF cavities,
- end cells have modified shape to compensate for the bigger diameter of the beam tube.


There will be two types of cavities :



We will order: 2 cavities with the port for input coupler (type I) and 4 of type II.


- Input coupler

- the superstructure will be fed by coaxial coupler of the DESY TTF III type,
- the coupler will be placed 45 mm apart from the end cell (axial position),
the radial position is changed because new beam tube has bigger radius by 18 mm.
- penetration depth of the antenna tip for $Q_{\text{ext}}=2 \cdot 10^6$ is 6 mm as it is for 9-cell TTF cavities.
- the only modification is new shape of the flange used for assembly in the cryostat (C. Martens)



In general the input coupler stays unchanged !!!

C. Martens



- HOM couplers

First computation of the emittance growth showed that high impedance transversal modes should be damped to the level of $Q_{ext} \leq 10^5$. The resulting impedance limit for transversal modes is:

$$Z = (r/q)_{max} \cdot Q_{ext} = 17.5 \Omega/cm^2 \cdot 10^5 \leq 1750 \text{ k}\Omega/cm^2$$

The peak power limit for the monopole modes is:


$$Z = (R/Q)_{max} \cdot Q_{ext} = 300 \Omega \cdot 3 \cdot 10^4 \leq 9000 \text{ k}\Omega$$

We are still working on the HOM coupler (delay of about 4 weeks). The reason is that part of the space between the cavities is occupied by flanges. This causes that



- HOM couplers must be based on smaller, 40 mm, coaxial line (less coupling requires deeper penetration of the antenna and of the loop)
- HOM couplers must be moved from the mid plane of the interconnection towards end-cell (antenna tip is exposed to more FM field).

The coupler we have at the moment fulfils requirements on damping, but:


- the antenna penetrates 20 mm in the beam tube,
- it may quench below 25 MV/m since RF losses on the antenna tip for this coupler are 8 times bigger than for 9-cell TTF cavities.




Limit:
 $\uparrow 1750 \text{ k}\Omega/cm^2 \uparrow$



Limit:
 $\leftarrow 9000 \text{ k}\Omega$







- tuner (critical component of the superstructure, new design H. Kaiser)

- new design of the tuner is unavoidable,
- the space needed for the TTF tuner is $\lambda/2=115$ mm. It is the whole space available between two cavities in the superstructure.


III High Q test of 7-cell sub-units

- cavities will be tested in the vertical cryostat used for the standard 9-cell cavities,
- for the Q vs. E measurements field profile must be balanced as for the operation. Two special end-cups have been constructed to keep field equal in all cells (R. Bandelmann).



IV Cryomodule


The prototype will be assembled in the spare "old type" cryomodule which should be ready in November 2000 (C. Pagani). The modification of the cryomodule and how the superstructure will be installed (support system) are under discussion (C. Pagani, H.-B. Peters).





V Summary

- RF measurements on the copper model

- field flatness: all cavities have been tuned for almost 98% field flatness. After assembly and small frequency corrections the achieved field flatness was about 93%. It can be better.




- transients: example cell #28, computation (HOMDYN M. Ferrario) and measurements.



- field profile for HPP

Example: processing of the cavity #2 (detuned by -200 kHz, C#1 by 6 kHz)



- FM coupler position has been fixed.
- HOM couplers optimization in progress.

- Time Schedule

By the end of 2000 we should install the superstructure in the TTF linac.

- 1 month for the assembly of cryomodule,
- 3 months to test 6 sub-units,
- 8 months to produce 6 sub-units, end-cups for the test,

Conclusion is that by mid/end of July we need:


- new design of HOM coupler,
- new design of the tuner and new helium vessel including conical head plates,
- technical drawings for the cavity production,
- to place order for the cavity production.

Shutdown Activities

Holger Schlarb
July 7, 1999



- Injector
- Acc-Module 1
- Collimator Section
- Undulator
- Experimental Area 1
- Air-conditioned chamber
- Infrastructure



TESLA TEST FACILITY (HALL 3)




- Cavity Treatment and Assembly
- == Cavity Testing (RF System / He Plant)
- TTF Linac


73















Vorläufige Version, 18.03.99
 PRELIMINARY












1:30



Time schedule for July/August 99
for the TTF Shut Down
(Mar.-July 1999)

Goal: First lasing or electron beam through the undulator before the FEL Conference 99 (23 -28 August).

Status:

- Undulator:
 - 1st Section in
 - 2nd Section in
 - 3rd Section ready for installation inside tunnel

Diagnostic Block: All assembled, 2 diagnostic block fiducialized,
4 blocks leak checked after assembly
1 block installed inside tunnel

Collimator: Vacuum components completely installed. Section is leak tight and prealigned

Tentative Schedule for July 99

- Installation work on the injector: 1st and 2nd week of July (28.6-9.7)
- collimator: Concrete shielding inside tunnel 5.7.99
- Undulator: 9.7.99 Vacuum chamber installed and undulator inside the tunnel
- Prealignment of undulator: 12-16.7.99

- Diagnostics blocks installation and vacuum connection: from 16.7.99 to 23.7.99
- collimator: Alignment and last concrete shielding inside tunnel 16.7.99 so that tunnel roof can be closed
- Tunnel roof can be closed now (19.7.99)
- 26 -28.7.99 Alignment of diagnostic blocks
- 26.7-6.8.99 alignment of undulator and diagnostic blocks (laser interferometrie)

Mile stones:

- Tuesday 20.7.99 Interlock ready and tunnel closed. Start to cool down modules. Work on the injector, linac (magnet power supplies diagnostic etc.) and modules can start during shifts.
- Monday, 26.7.99 Module cold.
- The undulator would be completely aligned on the 6.8.99
- 2 weeks are then available for tests with the undulator before the FEL 99 conference.



Progress on Controls

Kay Rehlich
DESY MVP2

RF

New Components and Modifications in

Hardware

New Features and Improvements in

Software

Laser



Interlock (PLC)

DOOCS Server

Modifications, bug fixes



Scope server

New TTF beam line components/positions

...

RF

DSP (digital signal processor)

5 Systems: linac, Chechia, RF gun, FNAL, lab

RF procedures/operations

Preparation for TESLA requirements (new DSP, in tunnel..)

Modulator controls discussions



Finite State Machine (FSM)



Tool to create finite state server programs

to automate linac operation

DOOCS display



Multi data in a plot



Correlation plots

Drag and drop

DESY

Interlock

Beam Inhibit System (BIS)

"Fast OFF" box for the collimator

ProfiBus

Design of a new VME board to control 2 ProfiBus lines including a UNIX driver

is used to control BIS, Pumpstations and other PLCs

Undulator

Temperature Controller

Temperature measurement

Integrators for photo multipliers

Fast ADC (Hamburg & Zeuthen)

8 channel VME ADC board

for undulator BPMs, RF and ..

14 bit resolution, up to 10 MHz

5 boards ready: 20. July

12 more boards: mid August

(old board: 12bit, 2MHz, price factor 3 higher)

Network Infrastructure

Network in Hall 3

faster: 10/100 MBit backbone

better maintainable: star topology

Packet switching

100 IP nodes connected

Computer Infrastructure

4 VME crates (undulator)

2 consoles in the new control room

Orbit correction (FSM)

Timing

Modification from 10MHz to 9MHz

86

TTF Laser

Sequence Status

- Laser Main Switch
- Laser Power Supplies (please wait 1 min, than proceed)
- Pulse Train Oscillator
- Check 1.3 GHz Phase
- Laser Amplifiers
- Laser Shutter

1.900 Flashlamp current (U_ctrl [V] > + 1.000 (usefull range: 0 ... 4 V))

0.007000 Number of Pulses (last two digits of 2200) note: at least 2202

Errors: Error Show Interlock

Show ADC: Output Fundam. Output SHG Phase 54 MHz Xpert

Help

TTFUTIL/LASER/INTER/LASERINTERLOCK

Inputs:		
OK	temperature amplifier cooler	E32.1
OK	flow amplifier cooler	E32.2
OK	flow cavity #1	E32.5
OK	flow cavity #2	E32.6
OK	flow cavity #3	E32.7
OK	no alarm oscillator cooler	E33.0
OK	flow oscillator cooler	E33.2
OPEN/CLOSED	safety shutter	E64.3/4
toggle	VME alive	E64.2

outputs:		
ON	mains switch	A32.1
OPEN	safety shutter	A32.2

show details M. Szlach 08.01.2009

TTFDIAG/SCOPE/T_OSCIL/CH4

Channel coupling: DC AC DC GND

Channel impedance: HFC

Channel position: 2

Channel scales: 10.0

Recall: Save and recall scope settings to/from locations (1-5):

Save: [1] [2] [3] [4] [5]

Hardcopy file path: /usr/ttfsrv3/ttfinac/tp/scope.ps

Change file path: [Browse]

Trigger commands: Coupling: DC Slope: R1S Source: AUX Level (V): +1.37

Vertical commands: CH1 CH2 CH3 CH4

Horizontal scale(sec/div): 5.0 ns

Units: [5] [10] [20] [50] [100] [200] [500]

changing the scale first choose units if other than current

Show waveforms Autoset

TTFDIAG/SCOPE/T_OSCIL


File: gv:Postscript Monochrome Portrait Image

State: Page: Portrait 1.000 BBox: Postscript Monochrome Jun 8, 1998

Print All Print Page Save All Save As...

File: [Browse] [Open] [Print] [Save] [Save As] [Print Page] [Print All] [Save All] [Save As] [Print] [Print Page] [Print All] [Save All] [Save As]

87



6.4.99 Kay Rehlich

RF System Building Blocks

BPAL_FB

Active state:
 BP_FB.FB_ON : feedback 'on' state
 CALC_Y_POS : calculates the vertical beam position
 CALC_X_POS : calculates the horizontal beam position

status: feedback on

Expert

DMP X reading and averaging
 DX = 0.00146

DMP Y reading and averaging
 DY = -0.0017601

DOOCS Data/Display vitaly@vitali VI.2.0

List of Components:

- BPM_FB
- BP_FB
- FB_ON
- bpm_feedback_param
- hist_bmp

BP_FB

```

    graph TD
      FB_OFF --> FB_ON
      FB_ON --> FB_OFF
      fb_error --> FB_OFF
      fb_error --> FB_ON
    
```

FB_ON

```

    graph TD
      beam_up --> beam_down
      beam_down --> beam_up
      beam_left --> beam_right
      beam_right --> beam_left
      beam_up --> CALC_Y_POS
      beam_down --> CALC_Y_POS
      beam_left --> CALC_X_POS
      beam_right --> CALC_X_POS
    
```

Program attribute

Server name: bpm_t...

ENS Address: TEST.VFSM/VFSM/...

KEY_GEN: 8898... Oper_gid: 22...



Source dir: /usr/ttfsr2/vitaly/fsm/bpm.t

Object dir: /usr/ttfsr2/vitaly/doocs/solaris2/obj/BPM

Defined:


```

    set(Iact-dI) = -1.9878 tor = -0.0799999
    ##### BP_FB_beam_down <y> = -0.0809599 Iact = 0.0072
    set(Iact-dI) = -1.9928 tor = -0.0023998
    ##### BP_FB_beam_left <x> = -0.00341597 Iact = 0.0121999
    set(Iact-dI) = -1.9878 tor = -0.0799999
    ##### BP_FB_beam_down <y> = -0.0809599 Iact = 0.0072
    set(Iact-dI) = -1.9928 tor = -0.0809599 Iact = 0.0072
    ##### BP_FB_beam_left <x> = -0.00390396 Iact = 0.0146399
    set(Iact-dI) = -1.98536 tor = -0.0823998
    ##### BP_FB_beam_down <y> = -0.0802399 Iact = 0.0048
    set(Iact-dI) = -1.9952 tor = -0.0799999
    set(Iact-dI) = -1.9878 tor = -0.0799999
    ##### BP_FB_beam_left <x> = -0.00365396 Iact = 0.0121999
    set(Iact-dI) = -1.9878 tor = -0.0799999
    ##### BP_FB_beam_down <y> = -0.0799999 Iact = 0.0072
    set(Iact-dI) = -1.9928 tor = -0.0799999
  
```




Beam loss detection system at low β -function section


H. Schlarb




New Network Infrastructure in Hall 3

17.3.1999
Kay Rehlich






Kay Rehllich, 13.05.1996
 last update: 14.5.1999
 (1) ...



Kay Rehllich, 7.7.1999

Timing System in TTF



8 Channels of fast ADCs: up to 1 or 10 MHz sampling, 14 bit resolution, 128k word of memory
 1 DSP port: for a link to a standard Ti C60 processor

Kay Rehlich, 3.98

New ADC Board Design for Diagnostics and Feedback Systems

FILE EDIT OPERAND PROJECT WINDOWS HELP

READ REGISTERS

INIT ADC

FILL TEST

FILL&INC TEST

WRITE MEM

CLEAR ERROR

WRITE REGISTER

ADC Registers

BAR A0

ISR 0

CIR 0

CSR0 0

CSR1 1

RL 1E74

Reserved 1E74

Received 1E74

TR 0

SR A0

CMD 114

ADCCR1 0

TC 0

SC 0

AC 0

VALUE 114

Write Register

VALUE 0

OFFSET 0

A/D MODE

FELMEM_S32

DELAY 500

ERROR OUT

status code

source

QUIT

ADC MEMORY READ

1E75	1E09
1E73	1E0A
1E74	1E08
1E75	1E09
1E72	1E08
1E74	1E09
1E73	1E08
1E73	1E09
1E75	1E08
1E72	1E07
1E73	1E08

START ADDRESS 0

OF SAMPLES 20000

ADC MEMORY TEST

START ADDRESS 0

OF SAMPLES 100000

PATTERN 0

BUILD PATTERN

Location Value

Stop after 50 Errors

SPECTRUM PARAMETERS

Amplitude(Vrms)

None (Uniform)

Linear

Vrms

Sample Frequency 940000

92

Undulator Status

Ulrich Hahn, HASYLAB at DESY

7. 7. 1999

Outline

Introduction

Undulator Vacuumchamber

Monitorblocks

Status of the Magnet Structures

Final Assembly and Set up in the Linac

The Undulator Vacuum System

length: ~ 15m, \varnothing 9.5 mm

vacuum: outgassing rate $< 1 \cdot 10^{-11}$ mbar•l/sec•cm²

particle free: according TESLA specification


4 monitor blocks (185 mm long)

***monitoring of the particle beam position in front and at the end of
the 3 undulator modules***

3 FEL - vacuum chambers 4.5m long 128x11.5mm²

***monitoring of the particle beam position in the gap of the undulator
modules***

steering of the particle beam in the gap of the undulator modules



Three FEL - Vacuum Chambers

Material: extruded Aluminum with stainless steel flanges

Chamber crossection: 128x11.5mm², Ø 9.5 mm

Chamber length: 4492.2 mm

Microroughness of the hole: 0.47µm along the extrusion and 0.98µm perpendicular to the extrusion direction

relative beam position measurement

2 chambers with 10 **pick up monitors** (40 electrodes - vertical - horizontal)


1 chamber with 10 **waveguide monitors** (40 electrodes - vertical - horizontal)

beam steering


36 watercooled steering coils in each chamber

FEL vacuum chamber

designed and manufactured
by DESY-HASYLAB and APS-Aigoune Nat'l Lab
Chicago




SCALE: 1:1000, JAN 22/1994



pick up monitor

Pickup Monitor
(prototype)




M. Wendt et. al.


Waveguide Monitor
(Prototype 2)

coupling window (3.2 x 5.2 mm)







12/30/1999





Four Monitor Blocks

Main purpose: *absolute* beam position measurement
(goal ~ 15 μm)

1. horizontal and vertical wirescanners with mechanical calibrated reference plate
2. horizontal and vertical cavity monitors
(absolute after calibration)
3. the only position of pumping








Status of the Magnet Structures


SASE 100 completed and installed in Linac	26.5.
SASE 200 completed and installed in Linac	21.6.
SASE 300 completed and to be installed in Linac	9.7.

UNDULATOR Setup in the Linac

Vacuum connection	6. – 23.7
Prealignment	12. – 16. 7.
Set up of Laserinterferometer	12. – 23. 7.
Infrastructure: Connecting monitors, correctors Water, etc.	12. – 23. 7.








112

Conditions for laserinterferometric precision alignment of undulators and wire scanners

(~ two weeks)

Undulator installed & prealigned, Infrastructure connected
Vacuum system evacuated
Air conditon running at least two weeks
Tunnel closed
Concrete shielding and all heavy itoms in undulator region in
place
Lasersystem & software running



**Photon Beam Diagnostics
for the SASE-FEL at TTF Phase I**

Photon Beam Diagnostics Group

Rolf Treusch

HASYLAB @ DESY

114

Lutz Bittner
Josef Feldhaus
Ulrich Hahn
Fini Jastrow
Michael Meschkat
Rolf Treusch
Ernst Weiner
Wenxuan Xu

+ external groups from
Dublin City University
Universität Jena
Forschungszentrum Jülich
IFPAS Warszawa



R. Treusch



Contents

- Motivation
- Experimental setup and detection techniques
- Current status
- Summary

25

Motivation


Main goal:

Experimental verification of the SASE (self-amplification of spontaneous emission) theory for short wavelengths in the VUV

Details:

- measure photon beam profile and integral intensity
- prove predicted gain for given e-beam and undulator parameters
- comparison of “spiked” structure in the time and frequency domain with theory
- check statistical intensity fluctuations

**Experimental setup and
detection techniques**



1: bending magnet, 2: alignment laser, 3: aperture unit, 4: detector unit,
5: deflecting mirror, 6: TSP + ion pump, 7: 1 m NIM, 8: CCD-camera
9: 2nd detector/aperture unit and focusing mirror (optional), 10: beamline
for autocorrelation experiments / radiation damage investigations

Intensity measurements

Expected FEL parameters:

$$40 \text{ nm} < \lambda_{\text{phot}} < 120 \text{ nm}$$

$$1 \text{ nJ (spont. em.)} < E_{\text{pulse}} < 400 \mu\text{J (SASE)}$$

$$(P/A)_{\text{max}} > 1 \text{ GW/cm}^2$$


$$\text{bunch/pulse separation: } 1 \mu\text{s (111 ns)}$$

Detectors


- wires and plate (photocurrent)
- PtSi photodiodes in different sizes
- thermopiles: single one and 4x4 matrix
- fluorescent crystals viewed with CCD camera

Fast thermopile matrix detector

Fluorescence screens



4x4 matrix (prototype)




Readout

PbWO₄ and Ce:YAG crystals

- fast fluorescence channel of a few / several 10 ns
- emission in the visible range (matching camera sensitivity)
- very homogeneous
- radiation hard
- UHV compatible

Frequency spectrum



spike width \implies bunch length
envelope \implies electron energy bandwidth

Requirements for monochromator/detection:

- Resolution: $\frac{\omega}{\Delta\omega} \geq 1 \times 10^4$
- shutter faster than pulse separation

Monochromator



- 1 m normal incidence monochromator with spherical grating (up to 3600 l/mm)
- piezo controlled entrance slit (min. slit width $\approx 1 \mu\text{m}$)
- Cameras for spectrum detection:
 - thinned back-illuminated CCD, UV sensitive
 - fast shutter ($\geq 5 \text{ ns}$) ICCD + phosphor

Current status

- beamline front end installed
- chambers with detectors assembled
- monochromator/slit/cameras tested and ready for installation


120

Water cooled detector unit





Summary

- unique properties of the FEL
 - ⇒ new concepts for detectors
- variation of beam intensity over several orders of magnitude
 - ⇒ manifold of different detectors necessary
- lack of experience with extremely intense VUV light
 - ⇒ beside photon diagnostics also benchmark for detectors





FEL performance crucially depends on electron beam properties, i.e. all TTF-components. The characterization of the photon beam is also a good means of diagnostics for the e-beam and thus the performance of the machine.


Photon beam diagnostics and machine operation/commissioning will/have to be performed in a close, symbiotic collaboration.




STRUCTURE OF THE TRANSITION



COUPLEUR PROJET TTF



FENETRE TW





CAVITY STIFFENING BY THERMAL SPRAYING: Thermal considerations and tests on single-cell cavities

*Cavity
Stiffening by
Thermal
Spraying*



I.P.N. - ORSAY



S.Bousson, A. Caruette, M.Fouaidy, H.Gassot,
J.C. Lescornet, J. Lesrel, T. Junquera



L.A.L. - ORSAY




J.L. Borne, L. Grandsire, J. Marini




C.E.A. - SACLAY



H. Safa, J.P. Charrier, M. Boloré





News on TTF Activities at INFN

(LNF, LNL, Milano & Roma2)

Presented by **Carlo Pagani**

1) Cryostat Design & Cryomodule Assembly

- Cryostats # 2 & # 3 - including WPMS
 - # 2 successfully in operation
 - # 3 assembled and ready for cooldown
- Cryostat # 1 to # 1*
 - Delivery expected by September '99
- New Assembling Tools - in fabrication
 - Due by September '99
- Cryostats # 4 and # 5 in fabrication with WPMS
 - Expected delivery at DESY: November '99
 - Composite posts (FNAL design) in fabrication
- Cryostats # 6 in fabrication with WPMS
 - Expected delivery at DESY: April 2000

2) Photocathodes (P. Michelato)

- TTF Injector II Cathode System
- INFN Photocathodes in operation at DESY and FNAL
- New System for the DESY gun: ready by October '99
- R&D Activity
- "New" photoemissive materials: K-Te & K-Cs-Te
- Poisoning and life tests on new cathodes
- Thermal emittance measurements: ready to start

3) Beam Diagnostics (LNF & Roma 2 groups)

- Beam instrumentation
- OTR screens
- Pepper pot
- Fast electronics for the strip-lines
- Beam measurements (M. Castellano)
- New Diagnostics
- Diffraction radiation experiment installed

4) Cavity Fabrication


- Standard Cavities - A16 to A18 measured
- A18 : 27.8 MV/m @ Q=9.7 10⁹ - Average gradient > 25 MV/m
- New Fabrication Technologies -
 - Spinning at LNL
 - Plasma spray at Milano

5) Theoretical activity (M. Ferrario)


- Beam behavior in Superstructures

28


ELECTRON SPECTROMETER




127




WU METAL CHAMBER FOR THE TOP
SPECTROMETER / $1/8 \pm 20 \text{ mSec}$




TOF SPECTROMETER






MCP DETECTOR

Mo Φ : 4.2eV $h\nu = 4.7\text{eV}$
Time of flight of photoemitted electrons from Mo (different bias potentials)




Mo $\Phi: 4.2\text{eV}$ $h\nu = 4.7\text{eV}$

Energy spectrum of photoemitted electrons from Mo (different bias potentials)




Test without HPR at CERN




05.07.99


Lutz Lilje DESY -FDET-



133



Test with HPR at CERN



05.07.99

Lutz Lilje DESY -FDET-

134

Results at CERN

- 1,3 GHz test stand is operational
- Water rinsing system is operational, minor problems during first setup
- First one-cell EP possible next week
 - mechanics finished
 - leak check done

04.07.99


Lutz Lilje DESY -FDET-


OVERVIEW OF THE "SMES" MODULATOR DEVELOPMENT (Feb 26, 1999)

July 8, 1999
status/sched


	STATUS	SCHEDULE	
POWER SUPPLIES FOR SMES AND CAPACITOR	ORDERED	10/99 DELIVERY	10/99 first test in Eston
POWER PULSE FORMER UNIT	BEING ORDERED BY COMPONENTS	11/99 DELIVERY	ordered 11/99 start stage 03/00 test in Est
PULSE TRANSFORMER	DELIVERED	1/99 DELIVERY	delivered
SAFETY SYSTEM	SPECIFICATIONS READY	11/99 DELIVERY	12/99-01/00
CONTROL SYSTEM	UNDER WORK	11/99 DELIVERY	03/00
SC MAGNET SYSTEM	MODEL COIL SUCCESSFULLY TESTED	9/99 DELIVERY	first coil ready 11/99 2nd coil
CRYOSTAT Incl. CURRENT LEADS	BEING ORDERED	10/99 DELIVERY	ordered, 12/99 delivered 01-03/00 assembl
MODULATOR CONSTRUCTION		12/99 - 2/00	- 03/00
SYSTEM TEST AT FZK	PREPARATIONS	3/00 - 4/00	04-05/00
TRANSPORT & MOUNTING		5/00	06/00
SYSTEM TEST AT DESY		6/00	07/00

25 MW SMES Modulator Cryostat





The patented modulator scheme is shown:



Simplified diagram

137

A new proposed accelerating structure consists of two standing wave coupling resonator systems

Advantages of new configuration

1. High accelerating gradient

$$\text{Acc.gradient}_{\text{New config.}} \approx 2 * \text{Acc.gradient}_{\text{TESLA}}$$

2. No problem with trapped modes

a) transverse

b) longitudinal

3. Easy tolerance (according to P. Avrakhovs simulations)



$$\downarrow \delta_m \downarrow \gamma_m$$



0.5 ÷ 1 MHz - for accelerating resonators

4 ÷ 8 MHz - for coupling resonators

4. Few input couplers

(1 per 8 meters)






Progress on the FEL (DESY) gun

- new location of test stand (operation during linac shutdown)
- rt gun 2 (tuned to 1.3 GHz) conditioned
 - 5 Hz, 30 μ s FT (total 40 μ s) \rightarrow 2.7 MW (circulator, clystron)
 - 5 Hz, 490 μ s FT (total 500 μ s) \rightarrow 2.0 MW (higher $\langle P \rangle$, cooling)
- continue until July 12th
- next shut down of linac:
 - \rightarrow operation with beam (cathode system)
- future: HGF application (M81, BESSY, TUD, DESY)
 - \rightarrow independant test stand (hall II) for • rt guns (low E, small G_s)
 - FEL injector
 - flat beams (damping rings)

Low energy test beam line



MODE MEASUREMENTS AT THE WARM TTF - MODULE 1 AND INFLUENCE OF INPUT COUPLERS

NICOLETA BABOI, HANS-WALTER GLOCK, GUENNADIE KREPS,
FRANK MARHAUSER

(DESY, UNI - ROSTOCK, UNI - FRANKFURT)

REVIEW: "COLD" & "WARM" MEASUREMENTS
TRANSMISSION MEASUREMENTS AT THE WARM MODULE
INFLUENCE OF INPUT COUPLERS
EFFECT OF CHANGING BELLOW LENGTHS

NICOLETA BABOI
TTF-MEETING, DESY, 7-9 JULY '99

REVIEW

"WARM" EXPERIMENTS (WITH BEAM) AT MODULE 1

SOMMER '98: S. FARTOUKH, O. NAPOLY ET AL. (SACLAY)

CHARGE MODULATION; 800 μ s;


\Rightarrow CAVITY 3 $f = 2.584980$ GHz $Q \approx 10^6$

CAVITY 6 $f \approx 2.586$ GHz $Q \sim 10^5$

FEBRUARY '99: CAVITY DETUNING ($f_{\text{HOM}} = n f_b$)

30 BUNCHES;

\Rightarrow CAVITY 3 $f = 2.584970$ GHz $R/Q \stackrel{?}{=} 15.3 \Omega/\text{cm}^2$



MODULE 1
 CAVITY 3
 COLD
 (JAN. 199)

MEASUREMENTS AT THE WARM

TTF - MODULE 1

(TRANSMISSION BETWEEN PAIRS OF HOM COUPLED)

- FREQUENCY SHIFT COLD - WARM :
 ~ -55 MHz (AT ~2,58 GHz)
- PASSBAND SLIGHTLY WIDER
- FOR CAVITY 3 , THE HIGH-Q MODE
 ($Q_{COLD} \approx 10^6$, $Q_{WARM} \approx 8000$) AT
 2.579 GHz CAN STILL BE SEEN
 AND DISTINGUISHED FROM THE OTHER
 POLARISATION
- MODE PATTERN OVER 3 CAVITIES

143

MEASUREMENTS AT THE WARM

TTF - MODULE 1 WITH

NO INPUT COUPLERS IN PLACE

MODE PATTERN OVER 3 CAVITIES

DISAPPEARED

INFLUENCE OF INPUT COUPLER ON THE

HIGH-Q MODE, BUT NOT ON THE OTHER

POLARIZATION


CHANGE OF BELLOW LENGTHS

MODES MOVE TOGETHER IN FREQUENCY

NO CHANGE IN FIELD PATTERN

EFFECT OF BELLOW LENGTH CHANGING ON MODES FREQUENCY

MODULE 1
WARM
C3K1-C4K1



ΔL_{23} } - VARIATION IN TUBE LENGTH
 ΔL_{34} } BETWEEN CAV. 2 & 3 AND 3 & 4

CONCLUSIONS

- INPUT COUPLERS INDUCE
 - COUPLING OF MODES TO THE NEIGHBOURING CAVITIES
 - CHANGE IN FREQUENCY OF THE HIGH-Q MODE, BUT LESS INFLUENCE ON THE OTHER POLARIZATION
- IN THE WARM MODULE 1
 - MODE PATTERN STILL EXTENDS OVER 3 CAVITIES
- IN TESTS WITH A 4 CAVITIES CHAIN WE COULD NOT REPRODUCE A FIELD PATTERN OVER 3 CAVITIES, BUT ONLY ONE INPUT COUPLER AND FEW HOM COUPLERS

FUTURE PLANS



(+ FRENCH TEAM)

- 5 CAVITIES STRING
(MODULE 1 - 3 GOOD D-CAVITIES)
- FIELD MEASUREMENTS (3 CAVITIES)
- POLARIZATION OF HOMs INDUCED BY INPUT COUPLERS
(CAVITIES FROM MODULE 1 + COPPER CAVITY)



Johann Wolfgang Goethe-Universität
Frankfurt am Main

Institut für Angewandte Physik




New Results on Trapped Modes in 9-cell TESLA-Cavities

Frank Marhauser
Peter Hülsmann
W.F.O. Müller

TESLA-Meeting
7.-9. July 1999
DESY, Hamburg


Frequency Shift of Monopole-TM Modes in Dependence on the Length of the Beampipes

- MAFIA-Calculation: Reference-Length: Cavity with 37,292 cm Beampipes -




Trapped Monopole-TM Modes - Asymmetric Cavity -


5. Monopole-TM Passband (π -like mode)



8. Monopole-TM Passband ($\pi/9$ -like mode)



10. Monopole-TM Passband (π -like mode)



passband	frequency f [GHz]		R/Q [Ω]' without phasefactor		difference [%]	R/Q [Ω]' v=c	loss-factor $\kappa = \omega_p / 4 \cdot R' / Q$ [V/nC]
	calculated	measured	calculated	measured			
5	3,856	3,853	716	514	28	51,5	311,9
8	4,866	4,865	1414	1020	28	0,09	0,7
10	5,519	5,533	1565	974	38	0,09	0,8
11	5,893	5,915	1826	900	51	0,2200	2,0
11	5,897	5,921	1814	1305	28	0,4500	4,2
11	5,904	5,926	1894	1157	39	1,3900	12,9
11	5,913	5,936	1973	963	51	8,2600	76,7
11	5,923	5,942	1978	1621	18	4,4000	40,9
11	5,932	5,948	1982	1959	1	0,1600	1,5
11	5,941	5,964	1932	1657	14	0,1100	1,0
11	5,948	5,969	1931	1700	12	0,0400	0,4
11	5,955	5,970	1735	1622	7	0,0100	0,1
15	6,693	6,712	1396	1210	13	4,33	45,5
18	7,342	7,362	1767	353	80	0,03	0,3

W-G. CAVITIES (I)

- 1 - Cavities for modules I* and 4
- 2 - Superstructure - Discussions -
- 3 - "Trapped modes" in module I
results of measurements (N. Baboi)
- 4 - Trapped modes in 9-cell cavity
(Frankfurt)
- 5 - New Structure - V. Balakin

Superstructures

- Discussion on some technical points:

* Tuner

* SC GasBets: only for prototype
future: find a "clean" welding technique

* HOM couplers:

→ one or two btw cavities?

* one may be sufficient

* evaluate risk vs cost

→ Worry about power on fundamental mode

CAVITIES for next MODULES

2 modules to be prepared:

- module I* → module III
- module IV → tunnel extension → **Expo**

Problem under lively discussion:

= if module IV equipped with 8 cavities installed before march 2000

⇒ No chance to install module III with high gradient cavities !!!

Decision (strong recommendation!)

- Install Module III with 25 MV/m cavities (around spring 2000)
- Find a scenario for module IV (install 8 "average" cavities (520 MV/m) or just dummy things)


Measurements in module I
(2.58 GHz mode)

- * Measurements made on warm module and string of cavities.
- * Influence of input coupler, beam tube.
- * Next measurements with some cavities -

Discussion:

- * Pb: explain transmission of the mode in the chain of cavities
 - Rotation of the polarisation of the mode?
 - Field pattern different for the two polarisations ($\Delta f \approx 400 \text{ kHz}$)
- * (consider the 8 cavities as a "superstructure")


Summary:
DESY 9-cell Cavity P-1



KEK


Cornell 2-cell

[at Cornell; 1300°C HT, CP 200 μm , expected RRR=800?]




ASO

Summary: DESY 9-cell Cavity P-1



BCP cavities



05.07.99


Lutz Lilje DESY -FDET-

151

1-cells

'EP' cavities

EP, welding at CERN




05.07.99

Lutz Lilje DESY -FDET-

Electropolishing

Lutz Lilje (DESY)

KEK's Best Cavities



152

*Cavity
Stiffening by
Thermal
Spraying*



I.P.N. - ORSAY

S.Bousson, A. Caruette, M.Fouaidy, H.Gassot,
N.Hammoudi, J.C. Lescomet, J. Lesrel, T. Junquera




L.A.L. - ORSAY

J.L. Borne, L. Grandsire, J. Marini



C.E.A. - SACLAY

H. Safa, J.P. Charrier, M. Boloré, Y.Gasser, J.P. Poupeau



CAVITY STIFFENING BY THERMAL SPRAYING

Introduction
Goal

GOAL: Cavity stiffening without lowering RF performances

1. Cavity RF Tests
"Rough APS"
HVOF
APS

↳ the cavity sensitivity to Lorentz forces detuning

↳ do not affect the cavity thermal stability

2. Mechanical Tests
Thermal stress
Young modulus



3. Thermal Tests
Simulations
Procedure

1. Single-cell cavity tests (1.3 and 3 GHz)
Cu "rough" APS, Cu HVOF, and Cu APS

Results
Conclusion
Future

2. Thermal characterization of different coatings:
Cu HVOF, Cu "rough" APS and Ti APS

3. Young modulus of different coatings:
Cu HVOF, Cu "rough" APS and Ti APS
Thermal stress (measured on Nb tube with Cu coating)

Jean-Louis
Sebastien BOUSSON

IPJ
7-2007

TESE



SINGLE-CELL CAVITY PROTOTYPES

Up to now, 3 different cavity prototypes have been realized:


Introduction
Goal

1. Cavity RF Tests
"Rough APS"
HVOF
APS
2. Mechanical Tests
Thermal stress
Young modulus
3. Thermal Tests
Simulations
Procedure

Results
Conclusion
Future

Jean LESRIVE
Sebastien BOISSY
DESY
7-9 July 2002
TESLA

Process	Performer	Frequency	Comments
"Rough APS"	French Firm Mallard	1.3 GHz & 3 GHz	Hand-made, Bonding Layer,
HVOF	LERMPS Laboratory	1.3 GHz	Low Porosity, High oxidation.
APS	Ecole des Mines Laboratory	3 GHz	



1.3 and 3 GHz Nb
and Cu/Nb cavities



THE NON-OPTIMIZED APS RESULTS

Sum-up of RF tests on APS coated cavities

Introduction
Goal

1. Cavity RF Tests
"Rough APS"
HVOF
APS
2. Mechanical Tests
Thermal stress
Young modulus
3. Thermal Tests
Simulations
Procedure



Results
Conclusion
Future

Jean LESRIVE
Sebastien BOISSY
DESY
7-9 July 2002
TESLA

3 Ghz Cavities:

Cavity	Eacc Max before coating	Eacc Max After Cu coating
#3	-	10 MV/m
#4	16.5 MV/m	16.5 MV/m
#5	14.5 MV/m	13.5 MV/m

1.3 Ghz Cavities:





The H.V.O.F. RESULTS

1.3 Ghz Cavities:

Introduction
Goal



1. Cavity RF Tests
"Rough APS"
HVOF
APS

2. Mechanical Tests
Thermal stress
Young modulus

3. Thermal Tests
Simulations
Procedure

Results
Conclusion
Future

Jean LESRE
Sebastien BOUSS
DES
7-31-15
TESLA



During the test with copper there was electron emission

- Great stiffening improvement with Cu HVOF
- Qo level almost not affected



MEASUREMENTS RESULTS

Introduction
Goal

1. Cavity RF Tests
"Rough APS"
HVOF
APS

2. Mechanical Tests
Thermal stress
Young modulus

3. Thermal Tests
Simulations
Procedure

Results
Conclusion
Future

Jean LESRE
Sebastien BOUSS
DES
7-31-15
TESLA

	RRR Coating	Porosity	ΔRg K.m ² /W	$\Delta Rg/Rg$ (Nb)	Young modulus GPa	Estimated Eacc,max
Cu APS Non-opt.	3	~ 20 / 30 %	$6 \cdot 10^{-4}$	~ 4	27	Stiffening 33 MV/m
Ti APS	3	> Cu APS non-opt.	$4.2 \cdot 10^{-4}$	~ 3	18	Stiffening
Cu HVOF	3	2 %	$1.2 \cdot 10^{-3}$	~ 10	53	Thermal 30 MV/m
Cu APS	4		-	-		
GOAL			$2.8 \cdot 10^{-4}$	2	95	Stiffening 40 MV/m

- Layer thermal conductivity is closely related to the porosity
- Cu HVOF has to be improved (reduced oxidation)

P. MICHELATO
INFN-LASA

PRELIMINARY RESULTS ON

THERMAL SPRAY OF Cu on Nb

① INFN + ENEL (CISE) + SAES GETTERS

+ CHOICE OF THE DEPOSITION TECHNIQUE

↳ MODIFIED ARC

↳ HVOF

④ ANALYSIS

↳ METALLOGRAPHIC MICROSCOPE

- Nb-Cu INTERFACE

- Nb

- Cu -> POROSITY → { << 1% HVDF
≈ 6% ARC }

↳ SEM - (SECONDARY ELECTRONS
SAMPLE CURRENT)

- ELEMENT IDENTIFICATION (XRAY)

↳ SURFACE ANALYSIS (AES)

- Nb-Cu INTERFACE

- O₂ on Cu

- O₂ on Nb

- O₂ on Cu INTERFACE

AES
IMAGING

"ARC" TECH

Cu



0.1 mm

457


HVOF

Cu

?




Nb



200 μm

SEM

HVOF - Cu



O₂

158

Commissioning and Experimental Program for the TTF Linac

M. Castellano, T. Garvey, G. Schmidt

Topics:

- Status of components
- Time schedule

1) Status of components

- Status of cold and warm cavity BPM's (R. Lorenz) ✓ *new electronics*
- Status of stripline BPM's (F. Tazzioli) ✓
- Status of OTR and screens (M. Castellano) ✓
- Status of ~~Reentrant~~ ^{pick up} Cavity BPM's (M. Wendt) *Number of slots → scope*
- Status of Waveguide Monitors and (Re)entrant Cavity BPM's (R. Lorenz) *2 in August → September / October → scope or electronic*
- Status of Wire Scanners (G. Schmidt) ✓ *new timing for ADC*
- Status of Toroids (H. Schlarb) ✓
- Status of collimator diagnostics (H. Schlarb) ✓ *ready for BPM electronics might be late*
- Status of timing system and fast ADC (K. Rehlich) *6 ADC boards upgrading of timing*
- New Tools for the optics and orbit of TTF (P. Castro) *- slow orbit feedback - optic calculation available*

⇒ 2 hrs

⇒ Delay of nearly all electronics of the undulator BPM's

⇒ No beam based alignment available

Some new tools for TTF control

Pedro Castro / MPY

1. Optics on-line, Beam-based alignment, Orbit correction
2. Data-base, documentation
3. Orbit feedback
4. What's done and What needs to be done.

2) Time schedule until FEL conference (23.-28 August) and beyond

With Goal: Electron beam through the undulator before the FEL Conference 99

- Startup of the injector (F. Stephan)

Goal: Reproduce settings of last run. Not optimizing everything, only get reasonable beam for FEL test.

-> injector ready to deliver beam (1nC, 8nC for rf calibration) 6.8.99 // undulator alignment

starting day at 12:00

- 4 shifts needed for phase adjustment of cavities in module 1

and 2. Calibration of gradient with an

8 nC beam with 10 pulses

only if the charge is not sufficient pulse length could be up to 30 pulses

Equal power distribution between module 1 and 2 will be used.

Goal energy is 260 MeV. 15 MV/m

- Then without longer investigations try to get beam through the collimator/undulator.

Bunch compressor should be off for first test.

Can then if necessary be switched on during one shift.

- Hasylab could look onto the photon beam.

Optimize angle and position in the undulator with the diagnostics available.

... to be decided depending on situation

What has to be done for α (quick and dirty) startup of the injector until Mo. August 9th, 1999 ?

F. Stephan,

TTF meeting, July 8th

week 1: Mo. July 12th → Fr. July 16th

• switch DESY gun → FNAL gun

- solenoids

- technical interlock

- water

- rf system: WG, llrf, cable attenuation need power meter, GPIB interface

• change capton foil in WG

(• new directional coupler ← check for leak tightness)

• enable laser beamline (remove aluminium)

• test of llrf system (changes were done)

• pull cable for fast technical interlock and fast DSP control to klystron 3

• check frame grabber, motors and video signals of screens in injector

• check injector magnets (running or not, hall probe)

• prepare CC for operation (hardware changes?)

• MBI people set up the laser

week 2: Mo. July 19th → Fr. July 23rd

- finish installation of persons interlock in complete tunnel
- get CC modulator working
- check laser interlock
- Tu. July 20th: tunnel closure
 - check persons interlock (klystron needs to be working)
- get solenoids running (technical interlock, hardware, control system)
- check gun solenoids (current measurement, hall probe, field profile (M. Schmitz))
- put rd in the gun: condition with DSP control up to 100ns with 2.2 MW ($\approx 35 \text{ MV/m}$)
(~ 2 days ?!)
- check dark current

week 3: Mo. July 26th → Fr. July 30th

- Mo. July 26th: modules and CC cold
- get CC working (new electronics, 2-3 days, Mo. → Wed. ?)
- in parallel:
 - get laser beam on cathode (2 fixed points on entrance window and wall)
 - check QE
- get correct timing for ICT integrators
- check ICT connection, calibration
- phase scan of rd gun cavity with 1nC and 8nC
- phase scan of CC (1nC / 8nC)
- get beam in dispersive section
- measure + optimize: energy + energy spread (1nC)
- get beam to FC in front of first module

Week 4: Mo. August 2nd → Fr. August 6th

- each day: check gun phase
- check CC phase
- check energy + energy spread
- get beam to FC in sector 600

• Mo. → Th.: 1 nC, Fr.: 8 nC

- get new pepperpot working
- do emittance scans with pepper pot (sector 400)
- " " " tomography (sector 400)
- " " " " (sector 600)

↑ scan parameters: - main solenoid current
- secondary " "
(- gun phase)
(- ...)

162

do this with a fixed choice
for the laser iris diameter (e.g. 3mm)

- Friday: get 8nC or more to the first module

General remarks

Continuous operation over longer periods to reduce the time to set up the machine for different experiments.
Improve the stability.
Special experiments at the end of the run or in blocks between work on the FEL.

Requests for beam time for special experiments
-HOM, measure without rf in cold module (parallel to injector work (September?))
if HOM exists close to beam frequency: 1 week measurement time.

- Balakin (?), pulse length needed, charge?)
- Processing time for modules (maybe during the FEL conference)
- Kryo Loss measurements (if possible at the end of the run)
- Wake field experiment (in November), vacuum chamber must be exchanged, → to be decided.
- September time needed for experiment with diffraction radiator (1 week roughly).
- end of the run: prepare and test 54 MHz modulation of the laser beam (3 weeks)

- Discussion on Emittance or/and Entrance diagnostic problem.

→ No clear answer

→ Many questions

→ Investigations needed for FEL
i.e. mode number for FEL

TESLA Working Group Summary

TESLA-500 Working Group, Thursday/July 8,
Room 5 Bld. Ib, 9.00h

Morning Session 9.00h, convener: R. Brinkmann

	Spent beam line and collimation	E. Merker, I. Yazynin
	Positron injector linac	V. Paramonov
~10.30h	Coffee break	
	Damping ring design update	W. Decking
	Multi-bunch instabilities in the damping ring	C. Burnton
	Positron source before the IP	R. Brinkmann
	Discussion on spent beam losses, extraction lines and related issues	all participants
~13.00h	Lunch break	

Afternoon Session 15.00h, convener: O. Napoly

	Multi-bunch beam dynamics in main linac	N. Baboi
	Beams with different energies (FEL/collider)	V. Tsakanov
	Estimate of beam halo	R. Brinkmann
~16.30h	Coffee break	
	Beam position measurement at the IP	T. Scholz
	Discussion on work to be done for TDR	all participants

e^+ source

V. Paramonov: Positron injector linac

E. Merker, I. Yazynin: e^- capture after IP

R. Brinkmann: Positron source before IP?

Damping rings

W. Decking: Design for the high luminosity parameters

C. Burnton: Multibunch dynamics

LINAC

N. Baboi: Multibunch dynamics with superstructure

V. Tsakanov: FEL/collider beam aubstratic

R. Brinkmann: Estimate of beam halo

IP

T. Scholz: IP Beam position monitor

e^+ source

V. Paramonov: Positron injector linac

- 260 MeV Linac, 18 x LBand SW cavities + 9 x 10MW Klystrons

+ (e^- separation, e^+ collimation) optics

• $\rightarrow \sim 22\%$ capture efficiency

$$L_{\text{Tot}} = 60 \text{ m}$$

$$P_{\text{Tot}} = 600 \text{ kW}$$

104

V. Paramonov

"Positron injector linac"

E. Meker, I. Yazvin: Spent from fine collimation

- 9% e^- losses, 7% e^+ losses $\rightarrow \sim 1 \text{ MW}$ on collimators

- 7 x 4 m long Al collimators (profile optimisation)

- IP instability $\sim 10 \sigma_x^2 \Rightarrow$ collimator damaged in 1 pulse

R. Brinkmann: e^+ source before IP

- pro: e^+ polarisation, localized dumps, e^- commissioning
- con: e^- , $AP/p \sim 3 \cdot 10^3$, e^+ transport through detector hall

... .. e^- extraction lines: BDS redesign

Institute for Nuclear Research
 Russian Academy of Sciences
 60th October Anniversary Prospect, 7A
 Moscow, 117 312, Russia

Conceptual Design of a Positron Pre-Accelerator for TESLA Linear Collider

Moscow-Hamburg, 1999




Figure 8.1. The PPA general scheme.




Figure 2.4.1: Particle loss distribution along the PPA.




Figure 8.2: The proposal scheme for the PPA beginning design. 1- 'pancake' in the solenoid, 2- yoke, 3- support, 4- lowcarbon steel plate, 5- short AS, 6- long AS, 7- AS position adjustment, 8- solenoid adjustment.

Table 2.3.1: Accelerating sections parameters

Section type	Type #1	Type #2
Number of sections	4	14
Number of cells per section	5	17
Accelerating gradient E_0T , MV/m	< 14,88	< 8,5
Shunt impedance Z_{sh} , M Ω /m	31,92	35,38
Transit time factor, T	0,78393	0,79657
Length, m	0,5765	1,9602
Dissipated power, MW	< 4	< 4
Quality factor	~23690	~23580
Aperture diameter, mm	52	52

Aperture diameter of the cavity $D = 52$ mm
 Field strength of the solenoid $B = 0,24$ T
 AMD length $0,8$ m

In this case PPA acceptance will be about twice the DR acceptance. This reserve permits to optimize the capture efficiency carefully. If it will be necessary the transverse phase space can be cut out of PPA.

Table 3.4.1: CDS structure parameters.

Parameter	Unit	$E_0T = 14.8$ MV/m	$E_0T = 8.5$ MV/m
Operating frequency	MHz	1300.0	1300.0
Phase velocity	relative	1.0	1.0
Aperture radius a	mm	26.0	26.0
Total web thickness	mm	30.0	30.0
Gap length g	mm	75.863	69.984
Drift tube cone angle	deg.	20.0	20.0
Lower drift tube radius r_1	mm	8.41	2.62
Upper drift tube radius r_2	mm	8.41	2.62
Upper cell radius r_3	mm	12.0	12.0
Outer cell radius R_c	mm	89.13	87.70
Effective shunt impedance Z_c	MO/m	34.35	37.45
Coupling coefficient k_c	%	5.1	8.9
Quality factor Q_0		24100	23800
Transit time factor T		0.780	0.790

P_A kW/m	η W/(m ² C ^o)	I_A C ^o	δf_a kHz	δf_c kHz	S_{atmax} kg/cm ²
5.7	7250	18.55	76	91	460
5.7	9000	17.44	68	84	418
26.0	9000	47.30	-255	296	980
26.0	12600	44.16	-210	221	901
26.0	12600	44.16	-210	221	901




Figure 3.6.2: The cup of the CDS structure with straight channel.

107




Figure 3.6.4: The cooling scheme for the second CDS cup option.

2.4 Proposal of the CDS structure design. Manufacturing and tuning procedures

The tuning procedure for the CDS structure was developed and described in [?]. As usual, tuning of compensated accelerating structure should have three procedures:

- tuning of the accelerating mode frequency f_a to f_0 one;
- tuning of the coupling mode frequency f_c to confine with f_a (closing of the stop-band);
- tuning of the accelerating field distribution (if needed).

Due to large k_c value, during the mode frequencies tuning there is no tuning of individual cells.


3 RF power system based on TESLA standard equipment

To reduce the total linac cost, to simplify maintenance it is supposed that the PPA rf system should be based on standard powerful TESLA equipment [?] - the same 10MW klystron with two waveguide outputs, powerful circulators after the klystron output windows, anode modulator and standard WR650 waveguide as Transmission Line (TL).

3.1 Special requirements

But PPA rf system should take into account PPA particularities. Differing from regular TESLA rf system, for PPA each klystron feeds only two normal conducting Accelerating Sections (AS); which parameters (wall rf power dissipation, Q -factor) are identical. Due to not so big AS Q_0 -factor value (≈ 23000), the field rise-time for PPA AS is short enough

168



beta 1.0 25 K/m 1.26

```

ANSYS 5.4
APR 22 1999
11:50:37
PLOT NO. 1
NODAL SOLUTION
STEP=1
SUB =6
TIME=1
TEMP (AVG)
RSYS=0
PowerGraphics
EFACET=1
AVRES=Mat
SMN =21.487
SMX =64.146
21.487
26.227
30.967
35.707
40.447
45.187
49.927
54.666
59.406
64.146

```

E. Merker,
I. Yazygin

"Spent beam line"
 collimation"




Figure 2.6.5. Output positron phase space portraits for PPA with collimating separator.

69




Fig.2: Angle beam deviation versus beam separation in IP.




Fig.3: Average dP/P beam value versus beam separation in IP.




Fig. 2: Layout of variant A.








Fig. 3: Layout of variant B.



172




Fig. 30: Change of temperature in collimator in horizontal direction in section with max dE/dV .




Fig. 31: Change of temperature in collimator in horizontal direction in the section with max dE/dV ($I = 2.8\%$, $Nb = 2.8 \times 10^{-1} \text{c}$).




Fig. 14: Distribution of deposited energy in additional to collimator 4 jaws (variant a) with 1,2,4 cm separation.




Fig. 14a: Distribution of energy density deposition in Al collimator 4 with 5 cm of copper (variant a).




Fig. 18: Layout of variant C.

174




Fig. 20: Distribution of energy deposition in collimator 4 (variant c).




Fig. 21: Distribution of energy density deposition in collimator 4 (variant c).




Fig. 19: Changing of H along collimator 4 (variant c).




Fig. 22: Layout of variant D.




Fig. 23: Changing of L along collimator 4 (variant d).




Fig. 1: Layout of electron beam line.

N collim.	1	2	3	4(up)	4(down)	5(up)	5(down)
L (%)	2.79	1.07	1.26	0.70	0.78	1.14	1.08
X [mm]	-10.5	-18.0	14				
Y [mm]	4	4	4	3	-3	1.5	-1.5
S [m]	82.01	117.42	242.33	453.71	453.71	546.86	546.86
Δ [mm]	6.13	3.84	6.06	-1.3	1.65	1.40	1.46

Table 1: Parameters of the collimators for electron beam line.

Material	A	Z	$\rho, g/cm^3$	L_{rad}, cm	L_{loss}, cm	R_{loss}, cm	R_{res}, cm
Be	9.01	4.0	1.848	34.69	369.69	99.66	24.33
Cl (graphite)	12.01	6.0	1.73	24.68	460.6	188.9	23.7
Mg	24.305	12.0	1.74	14.39	207.43	54.66	29.26
Al	26.98	13.0	2.7	8.9	190.8	74.2	16.8
Ti	47.88	22.0	4.54	3.56	59.53	15.54	10.95
Fe	55.85	26.0	7.87	1.76	42.4	15.8	6.36
Cu	63.55	29.0	8.96	1.43	34.9	12.9	5.7
Be-Al-Ti	9.44	4.23	1.92	31.80	558.67	234.99	23.28
Be-Al-Ti	18.05	8.34	2.6	13.65	273.20	109.46	17.53

Table 2: Atomic and nuclear properties of evaluated materials




Fig.8: Beam losses on the collimators versus beam separation in IP.

176




Fig.9: Beam losses on the collimators versus beam separation in IP.




Fig.34: Change of temperature in collimator 2 in horizontal direction in section with max dE/dV.




Fig.35: Change of temperature in collimator 2 in section with max dE/dV (I = 1.07 %).




Fig.36: Change of temperature in collimator 3 in horizontal direction in section with max dE/dV.




Fig.37: Change of temperature in collimator 3 in section with max dE/dV (I = 1.25 %).




Fig.38: Change of temperature in collimator 4 in vertical direction in section with max dE/dV.




Fig.39: Change of temperature in collimator 4 in section with max dE/dV (I = 0.7 %).

R. Brinkmann

" Positron source before
the IP

AFV

Concept: concentrate all large beam losses (10MW main beam, 300kW beamstrahlung, ~150kW γ 's from e+ target, parasitic e- from e+ target (?)) in main beam dump hall at ~250m from IP

Advantage for the site-layout: reduced spacing between dump halls (now ~500m), makes the site more compact (smaller) if we shift the IP ~300m north-wards

It looks feasible to use this solution, but there are many details concerning beam line layout to be studied (e.g. for modified beam delivery system, e+ transfer under the experimental hall, etc.)

Urgent: layout of spent beam line \rightarrow dump without boundary conditions for e+ production (must avoid excessive beam loss!)


Re-consider this option mainly for the following reasons:

- Collimation of ~1MW spent beam power (average) is a serious technical problem
- Even if collimators work, strong activation of beam line components unavoidable
- Several meter concrete shielding required for radiation protection of soil/ground water
- Shower of particles from collimators may make beam diagnostics difficult or impossible

87

In addition, there are advantages of the upstream-source:

- Excellent beam quality of incoming beam allows for polarized positrons
- Limitations on beamstrahlung from e+ source point of view removed (room to move in parameter space for optimum luminosity)
- Can commission e+ damping ring and linac without need of sending e- beam through the IR




E_{beam} [GeV]	250
B_{rms} (wiggler) [T]	0.9
L_w [m]	60
λ_w [cm]	2.5
$\sigma_{r,\gamma}$ (target) [mm]	1
η_{capture} [%]	17
N_{e^+}/N_e	2
$\langle dE(e^-)/E \rangle$ [%]	-1.6
$\sigma_E(e^-)/E$ [%]	0.18
$\gamma \Delta E(e^-)$ [m]	$<10^{-8}$

W. Decking

"Damping ring design
update"

Positron Source Layout
Draft 25.06.99
T. Stoye - WI-



Positron Source Layout created by stoye on 27 Jul 99 23:02:13:46 (GMT+01:00)

LEV

Damping Rings

W. Decking: DR design update

- E_0 : 3.2 GeV \rightarrow 5 GeV removes space-charge tune-shift instability (?)
- Optimisation of (Arc & Wigglers & Straight Section) Cells
- Dynamic aperture OK
- Problems:
 - tolerances (time varying B_x stray field)
 - injection/extraction kickers (stability over 1ms)

180

C. Bunton: Multibunch dynamics

- new parameters \rightarrow RF \times 2 w.r.t CDR (16 or 23 cavities)
- HOM instability OK
- "nearby-mode" instability faster than damping

New Parameters To Allow For Increased Luminosity:

determined by	new set	CDR	
luminosity	8×10^{-6} m	12×10^{-6} m	hor. extracted emittance $\gamma \epsilon_x$
luminosity	0.02×10^{-6} m	0.2×10^{-6} m	ver. extracted emittance $\gamma \epsilon_y$
bunch compressor	< 0.01 m	< 0.01 m	eq. bunch length σ_z
bunch compressor	$\approx 0.1\%$	$\approx 0.1\%$	eq. momentum spread σ_p/P_0
$> 5 \times \gamma \epsilon_{x,y;int}$	> 0.05 m	> 0.05 m	transverse acceptance $\gamma A_{x,y}$
repetition rate	200×10^{-3} s	200×10^{-3} s	momentum acceptance A_p
bunch train	2820	1130	cycle time T_c
kicker raise/fall time	20×10^{-9} s	50×10^{-9} s	number of bunches n_b
luminosity	2×10^{10}	3.6×10^{10}	bunch spacing $\Delta \tau_b$
			particles per bunch N_p



Problem: Incoherent Space Charge Tune Shift

- Large ring length and relative low energy leads to huge incoherent space charge tune shift:


$$\Delta Q_{y;incoh} \approx - \frac{r_e N_e C}{(2\pi)^{3/2} \sqrt{\epsilon_x \epsilon_y} \sigma_z \gamma^2}$$

- $\Delta Q_{y;incoh} \approx 0.2$ for CDR parameters
 - $\Delta Q_{y;incoh} \approx 0.43$ for high luminosity parameters
 - Cures:
 - * Increase ring energy
 - Needs lattice redesign
 - Higher rf-costs
 - + Need less wiggler length
 - * Decrease ring circumference
 - Kicker technology not available (?)
 - * Increase bunch volume through local coupling and/or dispersion
 - Additional coupling in a small coupling ring
 - + Probably low cost solution
- ⇒ Needs more study



4

Arc Cell




- 'detuning' $\epsilon_r \approx 4$
- long dipole to increase β, η, α_c
- QF split for best placement of sextupole
- $\nu_x = 0.4, \nu_y = 0.1$ cancels 1st order nonlinear terms after 5 cells
- $\theta = 6$ deg gives $\gamma \epsilon_{x;0} = 35 \mu\text{m}$ at 5 GeV
- $U_0 = 1.1 \text{ MeV/turn}$



184

9

Wiggler Cell




- $B = 1.5 \text{ T}$,
 $\lambda = 0.4 \text{ m}$
- cell length of 10 m
and $\nu_x = 0.166$ gives
 $\langle \beta_x \rangle \approx 10 \text{ m}$
- $\varepsilon_{x,wig} = 7 \mu\text{m}$ at
5 GeV
- Total of 36 cells leads
to
 $U_0 = 18 \text{ MeV/turn}$



11

Straight Section Cell




- long cell length reduces
 $\#_{Quads}$
- $\nu_x = \nu_y = 0.125$
to reduce chromaticity
contribution
- enough space
for injection,
circumference
correction, RF, ...
- due to high β very
sensitive to errors (stray
fields, ...)



182

12

Dynamic Aperture





- tracked with sextupoles misaligned to introduce optics distortion and coupling



13

Layout



- Arc length 920 m
- Wiggler length 288 m
- $\xi_{x;arc} = -90,$
 $\xi_{x;straight} = -30$
- $\xi_{y;arc} = -32,$
 $\xi_{y;straight} = -30$



183

15

Tolerances

- Tolerances as in CDR allow to reach $\gamma\epsilon_{y;0} = 0.1 \mu\text{m}$

transverse position of elements : 0.1 mm

roll angle : 0.2 mrad

BPM resolution : 0.01 mm

- For $\gamma\epsilon_{y;0} \approx 0.01 \mu\text{m}$ vertical dispersion correction is needed to a level of $D_{y;rms} \leq 2\text{mm}$ (need a 0.5% momentum shift to measure with BPMs with 0.01 mm resolution)
- Tolerances for time-varying stray fields in the long straights are a few nT; first measurements (Jensen, Pillat) show values up to $100 \mu\text{T}$ in typical accelerator environments
- Need of circumference correction to adjust for tides, wiggler on/off (?)

$$\frac{\Delta C}{C} = \alpha_c \frac{\Delta p}{P} \leq 0.1 \times \sigma_p / P \rightarrow \Delta C \leq 270 \mu\text{m}$$



14

C Burton
" Multi-Bunch instabilities
in the damping ring "

124

	Parameters	
	CDR	New (WD)
E_b / GeV	3.2	5
σ_E	0.1×10^{-2}	0.13×10^{-2}
U_0 / MeV	10.3	20.3
$V_{\text{rf}} / \text{MeV}$	25	50
α_c	3.4×10^{-4}	1.2×10^{-4}
σ_z / mm	9.5	(6)
$\alpha_\epsilon / \text{Hz}$	(59)	(71)

C. Burnton, July 1999

6

Major Cavity HOM

$Q = 1100$ (damped), $R \approx 60 \text{ k}\Omega$, $f_{\text{HOM}} \approx 782 \text{ MHz}$

$$N_{\text{cav}} \sum_{p=-\infty}^{+\infty} \frac{f_{pk}}{\text{GHz}} \frac{\Re Z_{\parallel}^{\text{cav}}(\omega_{pk})}{\text{k}\Omega} e^{-(\omega_{pk}\sigma_z/c)^2} < \begin{cases} \text{cdr : } 930 \\ \text{new : } 2450 \end{cases}$$

$$\text{HOM: } \begin{cases} \text{cdr : } 380 \\ \text{new : } 760/1090 (N_{\text{cav}} = 16, 23) \end{cases}$$

$$\text{or HOM growth rate } \begin{cases} \text{cdr : } 24 \text{ Hz} \\ \text{new : } 22 \text{ Hz}/31 \text{ Hz} \end{cases}$$

C. Burnton, July 1999

185

7

Nearby-mode Growth rate

$f_{\text{rf}} / \text{MHz}$	ν_s	16 Cavities		23 Cavities	
		$ \Delta f / \text{Hz}$	τ^{-1} / Hz	$ \Delta f / \text{Hz}$	τ^{-1} / Hz
433.33	0.065	4530	91	6512	306
400	0.063	4182	67	6012	221
350	0.059	3661	41	5263	131
325	0.056	3400	31	4888	98

Note: $\nu_s \propto \sqrt{f_{\text{rf}}}$; $R/Q = 225 \Omega$

N. Babai
 " Multi-Bunch Beam
 dynamics in main linac "

LINAC

N. Baboi: Multibunch dynamics with Superstructures

- HOTs R/Q & Q from Jank's calculations
- Slightly better than with 9-cell cavities

V. Tsarev: Beam with different energies (FEL / Collider)


- $E_{acc} = 18 \text{ MV/m}$ for FEL (w/ 25 MV/m)
- $\mu_{coll} = 60^\circ \rightarrow \mu_{FEL} \approx 90^\circ$
- Vertical dispersion oscillates if linac is "curved"
- Rephase "curved" linac by 18m, 7mm dipole @ ~50 GeV
- Beam dynamic studies

R. Brinkmann: Estimate of Beam R.D.s

Do from DR
 sum over scatt's
 intrabeam scatt's
 dark current

- Important for μ^{\pm} background in detector
- $< 10^4 \text{ p/bunch} \Rightarrow < 6 \mu^{\pm}$ in TPC
- Dark current rates negligible at 5 GeV injection (7 p/bunch) !!

SUPER - STRUCTURE




4 x 7 CELLS → IN SIMULATION AS ONE ACCELERATING STRUCTURE

3 SUPER-STRUCTURE / MODULE



TESLA CAVITY : 10 MOST "DANGEROUS" HOMs FROM CDR

9 CELLS




SUPER-STRUCTURE : MOST "DANGEROUS" MODES (MEASURED)

7 x 4 CELLS (FACTOR 3 COMPARED TO TESLA)



BUNCH TRAIN AT END OF LINAC

SOME RESULTS



V. Tsakanov

"Beams with different energies (FEL/Collider)"

Beams with different energies (FEL/Collider)

V.M. Tsakanov

Yerevan Physics Institute, Armenia

1. Introduction
2. Present performance (CDR)
 - * Linear optics
 - * Emittance preservation
 - * Conclusions
3. Wide TESLA/FEL energy spread
 - * New parameter set
 - * Linear optics
 - * Emittance preservation
 - * Conclusions

559




Figure 3.10.3: Expanded profile of the Linear Collider area North-Northwest of DESY.

1 Linear optics

$$\sin(\mu_F/2) = \frac{U_T}{U_F} \sin(\mu_T/2) \quad (1)$$




Fig.2 The betatron functions of the TESLA and FEL beams.

The phase ellipses of injected beams for TESLA and FEL operations have to be matched with machines ellipses to prevent the emittance dilution of the beta-mismatch

$$\frac{\Delta \varepsilon}{\varepsilon} = \frac{1}{2} \left[\frac{\beta}{\beta^*} + (\alpha - \alpha^*)^2 \frac{\beta^*}{\beta} + \frac{\beta^*}{\beta} \right] \quad (2)$$

where α, β machine initial Twiss parameters, α^*, β^* the Twiss parameters at the end of injection channels. As an example, if the matching point is at the middle of the quadrupole ($\alpha = 0$), for the 5% of emittance dilution we get

$$\alpha^* \leq 0.22, \quad 0.75 \leq \frac{\beta^*}{\beta} \leq 1.27 \quad (3)$$




Fig.3 The periodic dispersion functions of the TESLA (solid line) and FEL (dashed line) beams.





Fig. 4 The FEL beam design periodic orbit (a) and the coherent oscillations of the beam with initial zero amplitudes (b)(on axis injection).

1.1 Emittance preservation

a) Dispersive effects. Coherent oscillations

Fig.5 shows the emittance dilution of the beam caused by injection jitter and initial uncorrelated energy spread for one sigma offset of the injected beam with respect to FEL beam design orbit. For comparison we show also the dispersive emittance dilution when the FEL beam is injected along the axis of the main linac. Thus, to stabilize the emittance dilution of the FEL beam with the accuracy better than 5%, the uncorrelated energy spread limited by 1% and the injection jitter by one sigma offset with respect to FEL design orbit.




Fig.5 The dispersive emittance dilution caused by initial uncorrelated energy spread and injection jitter. Shown are the cases of one sigma initial offset (solid line) and on-axis injected (dashed line) FEL beam.

b) Wake fields effects.

The wake fields caused emittance dilution of the TESLA and FEL beams is shown in Fig.6. The high energy beam performs coherent betatron oscillation with one standard initial offset. For the FEL beam are shown the cases when the beam follow the design orbit (matched beam) and the beam injected at the axis of the main linac. The effect is in order of few percent for TESLA beam and negligible (in order of 10^{-1}) for FEL beam.




Fig.6 The wake field emittance dilution of the TESLA and FEL beams. Coherent oscillations with matched and on-axis injected FEL beam.

c) *Trajectory correction*

The quadrupole misalignments of the linac affect both trajectories of the TESLA and FEL beams. Note, that if one of the beams is corrected, the second beam with the large energy shift experiences an additional kick in quadrupoles which is proportional to the corrected trajectory offset of the first beam $\Delta x_2' \approx kx_1$. Thus the second beam not follow the dispersion trajectory but performs additional beating, the amplitude of which could be substantially growth leading to large emittance growth. We will return to this problem in the next section. Fig.7 shows the TESLA and FEL beams trajectories when the high energy beam is corrected by using one-to-one correction technique. Note, that the dispersion functions exactly follow the trajectory of the beams.




Fig.7 The beating of the FEL beam with the one-to-one correction of the TESLA beam. Shown the quadrupoles misalignment-dashed line, and the TESLA one-to-one corrected trajectory solid line (top) and the coherent oscillations of the FEL beam (bottom).

1.2 Machine performance

Beam dynamics:

- * the FEL beam should be matched with the design orbit to prevent the emittance dilution of injection jitter;
- * the dispersions of the TESLA and FEL beams should be matched to obtain the minimum periodic dispersion of the machine;
- * the periodic dispersion is still large (2.5 mm) and the application of the beam based trajectory correction becomes problematic.

Machine performance:

- * each FODO cell should be geometrically curved by about 0.05 mrad to be linked with the design trajectory of the TESLA beam. In turn, the each cell should be aligned with the accuracy better than 100 microm;

* the option of the further colliding of the TESLA electron beam with HERA proton beam needs some reconstruction of the machine elements as far as the correction dipoles with the maximum magnetic field 44 m T could not provide the corresponding bend of the electron beam at energies 250-500 GeV.

To prevent all these aspects of the machine performance and beam dynamics issues, the part of the main linac with parallel operation of collider and FEL beam is reasonable to be straight with further bending of the collider beam by angle 7.5 m rad in achromat cell after the separation of colliding and FEL beams (Fig.1). The energy of the collider beam is then at the level of 70 GeV. The FEL beam is extracted from the linac at the different energies by the fast kicker setup at energies 15, 25 and 50 GeV and is transported to the user laboratories.

193

2 Wide band energy spread and high luminosity TESLA

TABLE 1: Parameter list

1. TESLA (FEL) injection energy - 5 GeV (2.2 GeV).
2. Vertical emittance $\gamma_{z,y}^2 - 0.03 \text{ mm} \cdot \text{mrad}$, ($0.7 \text{ mm} \cdot \text{mrad}$)
3. Charge per bunch - $2 \cdot 10^{10}$, ($6 \cdot 10^9$)
4. Bunch length - 0.4 mm (25 μm)
5. Initial uncorrelated energy spread - 0.01 (0.01)

a) Linear optics

$$\sin(\mu_T/2) = \sin(\mu_I/2) \left(\frac{E_{0T} E_F(n)}{E_{0F} E_T(n)} \right)^\alpha \quad (4)$$

$$\sin(\mu_F/2) = \sin(\mu_I/2) \left(\frac{E_{0F}}{E_{0T}} \right)^\alpha \left(\frac{E_T(n)}{E_F(n)} \right)^{1-\alpha} \quad (5)$$




Fig.7 The betatron functions for TESLA and FEL beams.

b) Free coherent oscillations. Dispersive effects

$$\frac{\Delta \varepsilon}{\varepsilon}(\pm) = 2\delta_0^2 \tan^2(\mu/2) \left(\frac{\gamma_0}{\Delta\gamma} \right)^2 \ln^2 \frac{\gamma(z)}{\gamma_0} \quad (6)$$




Fig.8 The dispersive emittance dilution caused by injection jitter and initial uncorrelated energy spread. The beam performs free coherent oscillations with one sigma initial offset ($\sigma_T = 15 \mu\text{m}$, $\sigma_F = 120 \mu\text{m}$). The dashed line shows the analytical prediction for TESLA beam with constant beta lattice ($\mu = 60^\circ$).

c) Free coherent oscillations. Wakefield effects

$$\frac{\Delta \varepsilon}{\varepsilon}(\pm) = \frac{1}{2} \frac{q_0^2}{\varepsilon_0} \left(\frac{cQ W_{a,c}}{8G} \right)^2 \frac{1}{\sin^2 \mu} \ln^2 \frac{\gamma(z)}{\gamma_0} \quad (7)$$




Fig.9 The wakefield caused emittance dilution. The beam performs free coherent oscillations with one sigma initial offset. Dashed line - analytical prediction for TESLA beam.

d) Accelerator section misalignments

$$\frac{\Delta \varepsilon(z)}{\varepsilon} = \frac{\langle y^2 \rangle}{2N_{\text{car}} \varepsilon_0} \left(\frac{eQW_D}{4C} \right)^2 \frac{\Delta \gamma}{\gamma_0} \frac{L_c}{\sin \mu} \ln \frac{\gamma(z)}{\gamma_0} \quad (8)$$




Fig 10. Emittance dilution of the TESLA beam because of the cavity misalignments. Dashed line - analytical prediction.

e) On-to-one correction

$$\frac{\Delta \varepsilon}{\varepsilon} = 8 \delta_{\text{rms}}^2 \frac{\langle y^2 \rangle}{\varepsilon_0 L_c} \tan \frac{\mu}{2} \cdot \ln \frac{\gamma(z)}{\gamma_0} \quad (9)$$




Fig 11. Uncorrelated dispersive emittance dilution of the TESLA beam with on-to-one correction ($\sigma_y = 100 \mu\text{m}, \sigma_x = 100 \mu\text{m}, \sigma_r = 10 \mu\text{m}$). Dashed line - analytical prediction.

f) Two beam operation

$$\langle \Delta y^2 \rangle = \delta^2 \langle y^2 \rangle + \frac{\beta(z)}{\gamma(z)} \sum_k K^2 L_q^2 \beta_x \gamma_k \sin^2[\phi(z) - \phi(z_k)] \quad (10)$$




Fig.12 The TESLA beam corrected trajectory (one-to-one correction, $\sigma_y = 0.5 \text{mm}, \sigma_x = 0.1 \text{mm}, \sigma_r = 10 \mu\text{m}$) and the coherent oscillations of the FEL beam.

Summary

- * the two-beam operation part of the main linac need to be straight to prevent the dispersion caused errors for beam based correction technique;
- * the use of the one-to-one correction technique for one of the beams accompanies by the large coherent oscillations of the second beam ;
- * the operation of the machine with two beams with different energies - use to use on-line two-beam based trajectory correction.

R. Binkmann

" Estimate of beam halo "

196

Halo from damping ring

As (pessimistic) estimate for beam halo in the D.R. I assume a fraction of 10^{-3}

A low-energy collimation system reduces that by at least a factor 10^4 (according to calculations for high-energy system)

→ expect $\sim 10^3$ halo particles/bunch at linac entrance

Beam-gas in the linac

1. single Coulomb scattering

total cross section for scattering angle larger than acceptance θ_A :

$$\sigma(\gamma) = 2\pi \left(\frac{2Zr_e}{\gamma} \right)^2 \cdot \int_{\theta_A}^{\pi} d\theta \frac{\sin \theta}{\theta^4}, \quad \theta_A = n_\sigma \sqrt{\frac{\epsilon_y}{\gamma \cdot \beta}}$$

approximately:
$$\sigma(\gamma) \approx \frac{4\pi Z^2 r_e^2 \beta}{n_\sigma^2 \epsilon_y \gamma}, \quad \sigma_{tot} = \int_{L_{linac}} \sigma(\gamma) ds$$

gas density (@2K): $n_{\text{gas}} = 3.6 \cdot 10^{24} \text{ m}^{-3} \cdot P/\text{mbar}$, example
 $P(\text{He}) = 10^{-10} \text{ mbar}$, $\beta = 100 \text{ m}$, $\epsilon_y = 3 \cdot 10^{-8} \text{ m}$, $n_e = 30$:

of Coulomb scattering events p. electron = $5.7 \cdot 10^{-8}$

→ $1.2 \cdot 10^3$ halo particles per bunch

2. Bremsstrahlung

→ negligible compared to Coulomb scattering

Touschek effect

Hard intra-beam scattering with momentum transfer $> 3\%$
(BDS acceptance)


→ negligible (~ 1 particle per bunch)

Dark current

Phase space distribution of dark current obtained from PhD thesis by C. Stolzenburg (using field emission model for one 9-cell resonator)

Question: how much of that is transported to high energy in the TESLA linac?


Depends strongly on the “nominal” (i.e. main beam) energy at which the field emission takes place (most particles get lost downstream due to over-focusing in the linac lattice)



One 9-cell cavity, $g = 25 \text{ MV/m}$:

$\langle E \rangle = 11 \text{ MeV}$, $\langle \phi_{rf} \rangle = 40 \text{ deg.}$, $\epsilon = 4 \cdot 10^{-4} \text{ m}$

determine fraction of stable phase-space volume by tracking large # of particles through the linac, as function of main beam energy at the position of the emitting cavity assume 60 deg. FODO lattice, 16 cavities between quads, 1st cav. is d.c. source




Fit function:

$$\frac{I_{stable}}{I_{initial}} = \exp(-1.7E_0^{1.35})$$

total dark current at end of linac:

$$I_{d.c.}(E_0) = \int_{E_0}^{E_f} I_{stable}(E) \frac{dI_{emit.}}{dE} dE$$

rough estimate: $dI/dE = 40 \mu A/GeV$ (i.e. $1 \mu A$ p. cavity)



→ # of halo particles p. pulse

$4 \cdot 10^7$ for 3 GeV damping ring (1.4 · 10³ p. bunch)
 $2 \cdot 10^4$ for 5 GeV damping ring (7 p. bunch)

+ low-energy particles from the last few GeV of the linac

INTERACTION POINT

T. Scholz: BPM for IP feedback.

- needs 2 x 3 BPM in test doublet
- compact design fits in cryostat
- 5 μm resolution possible (one dimension)
- can measure both incoming e^+ & outgoing e^-
beams: $\Delta T = 20\text{ns}$
- e^+e^- pair background ??


T. Scholz

" Beam position measurement at the IP "

Design of a Beam Position Monitor for the Interaction Point (IP) in TESLA

Principle of Working


- technical drawings



- prototypes




- coupling in / out, magnetic field of the dipole mode



- alternatives for coupling:

- waveguides
- inductive loops

- 3D-configuration:



- modes



mode	monitor A		monitor B	
	calculat. [GHz]	measur. [GHz]	calculat. [GHz]	measur. [GHz]
TE ₀₁₁	0.944	1.000	1.171	1.147
TE ₀₂₁	1.372	1.520	1.949	1.936
TE ₀₁₂	1.605	1.677	1.748	1.729

- quality numbers:


- prototype A: 5600,
- prototype B: 850 (500).

201


- prototype B



- mask for radiation shielding:




- proposed arrangement of the 3 planned BPM:



Time Response

- time structure at the BPM's:
 - periodic signals for the distances
 $20ns, 33ns, 43ns$ ($\nu = 1.95GHz, Q = 850$):



22