

TESLA COLLABORATION

Transparencies from the Meeting on

Cold- and Beam Test of the First Nb Superstructure Prototypes

DESY, February 25 and 26, 2002



March 2002, TESLA 2002-04

The meeting on "Cold- and beam test of the first Nb Superstructure prototypes"
 February 25 and 26 in Seminar Room 292, Building Id.

February 25, 2002

Talks on the test cryomodule components (Convener: D. Proch)

9:15	A. Matheisen	"Status of the test cryomodule: short overview of components and preparation of final assembly"	1
9:30	R. Lange	"Schedule of the cryomodule assembly"	15
9:45	R. Lange	"Cold test of new tuner"	17
10:00	J. Sekutowicz	"Summary of RF measurements at room temperature"	26

10:30 Coffee break

Talks on the test program (Convenors: H. Schlarb/M. Huening)

10:50	J. Sekutowicz	"Preliminary program of the cold test, what do we like to measure ?"	45
11:10	M. Huening	"Short summary of the HOM experiments in TTF linac"	66
11:25	N. Baboi	"What can we improve in HOM measurements ?"	89
11:40	M. Ferrario	"Estimation of bunch-to-bunch energy variation in TTF linac with two superstructures and standard cryomodule"	96
11:55	H. Schlarb	"Limits in energy measurements at the injector region and at the end of linac"	102
12:10	S. Simrock	"Limits in the amplitude and phase control for 2x7-cell superstructure and for standard cryomodule at 2MV/m and 15 MV/m operation"	112

12:30 Lunch

Talks on the TTF linac preparation (Convenors: P. Castro/S. Schreiber)

13:30	P. Castro	"Proposed re-arrangement of TTF linac for the beam test of superstructures"	130
13:45	S. Schreiber	"Injector: stability of charge at operation at 1 MHz and at 54 MHz"	133
14:00	S. Choroba	"RF power distribution system for the test cryomodule and 1* cryomodule at ACC2 position"	140
14:15	M. Wendt	"BPMs, electronics and automatic data read-out for the HOM experiment and for the FM experiment"	145

14:30 Coffee break

14:50	K. Rehlich	"Diagnostics: re-arrangement for the beam test of superstructure"	160
15:05	H. Schlarb	"Interlock re-arrangement for the test"	162
15:20-16:00		Discussion on: Other technical aspects of the test	

February 26, 2002

9:00- 12:00 Discussion on : Other technical aspects of the test, schedule, manpower and AOB.

I

Nr.	Vorlängeschema	Dauer	Anfang	Ende	18. Jul. 02	15. Jul. 02	22. Jul. 02	29. Jul. 02	05. Aug. 02	12. Aug. 02	19. Aug. 02	26. Aug. 02	02. Sep. 02	09. Sep. 02	16. Sep. 02	23. Sep. 02	30. Sep. 02	07. Oct. 02	14. Oct. 02	21. Oct. 02	28. Oct. 02
1	Cool-down	5 Tage	Fr 12.07.02	Fr 17.07.02																	
2	RF-measurements without beam	9 Tage	Do 18.07.02	Do 26.07.02																	
3	Cable calibration & pickups/GHOMS	1 Tag	Do 18.07.02	Do 18.07.02																	
4	Field flatness adjustment SST#1 (2 Methods)	2 Tage	Fr 19.07.02	Mo 22.07.02																	
5	Field flatness adjustment SST#2 (2 Methods)	2 Tage	Di 23.07.02	Mo 24.07.02																	
6	FM+passb. SST#1 and SST#2 +field flatt.	vs. F	Fr 26.07.02	Fr 26.07.02																	
7	IOM measurements: Qs and F: SST#1	1 Tag	Fr 26.07.02	Fr 26.07.02																	
8	IOM measurements: Qs and F: SST#2	1 Tag	Mo 29.07.02	Mo 29.07.02																	
9	FM coupler conditioning SST#1 and SST#2 , 1*	10 Tage?	Di 30.07.02	Mo 13.08.02																	
10	Linac commissioning	8 Tage?	Di 13.08.02	Do 21.08.02																	
11	Energy variation in measurements with beam	10 Tage	Fr 23.08.02	Do 03.09.02																	
12	SST#1	3 Tage	Fr 23.08.02	Di 27.08.02																	
13	SST#2	3 Tage	Mo 25.08.02	Fr 30.08.02																	
14	SST#1+SST#2	4 Tage	Mo 05.09.02	Do 05.09.02																	
15	IOM measurements with beam	22 Tage	Fr 05.09.02	Mo 02.10.02																	
16	Active HOM Measurements/Calibration of BPMs	7 Tage	Fr 05.09.02	Sa 14.09.02																	
17	Re-arrangement of laser from 1 MHz to 54 MHz	2 Tage?	Mo 16.09.02	Di 17.09.02																	
18	Re-calibration for 54 MHz	1 Tag?	Mo 18.09.02	Mo 19.09.02																	
19	HOMs search of SST#1 and SST#2	11 Tage?	Do 19.09.02	Mo 02.10.02																	
20	Reserve	10 Tage?	Do 03.10.02	Mo 16.10.02																	
21																					
22	Linac activities	65 Tage?	Fr 12.07.02	Fr 10.11.02																	
23	RF-gun cavity conditioning	5 Tage?	Fr 12.07.02	Mo 17.07.02																	
24	(Capture cavity conditioning	5 Tage?	Do 18.07.02	Mo 24.07.02																	
25	(Injector commissioning for long pulses	18 Tage?	Di 25.07.02	Mo 19.08.02																	
26	Linac commissioning	8 Tage?	Di 20.08.02	Do 29.08.02																	
27	Linac operation for the FM and HOM experimenter	33 Tage?	Fr 30.08.02	Do 10.10.02																	
28	ACC2 activities [1]*	5 Tage?	Fr 12.07.02	Fr 17.07.02																	
29	Warm conditioning of couplers off resonance	5 Tage?	Fr 12.07.02	Fr 17.07.02																	
30	Cold conditioning of couplers	10 Tage?	Di 30.07.02	Mo 12.08.02																	
31	High gradient 1 Hz	8 Tage?	Di 13.08.02	Do 22.08.02																	
32	High gradient 1 Hz	22 Tage?	Fr 06.09.02	Mo 10.10.02																	
33	High gradient long pulse 5/10 Hz	22 Tage?	Do 03.10.02	Fr 01.11.02																	
34																					
35	Linac interlock closed 24 h	5 Tage?	Fr 12.07.02	Mo 17.07.02																	
36	Linac interlock closed 24 h	72 Tage?	Di 30.07.02	Fr 01.11.02																	
37	Linac interlock closed for the night shift	8 Tage?	Do 18.07.02	Mo 29.07.02																	
38	Need for Klystron 1	60 Tage?	Di 30.07.02	Mo 16.10.02																	

1

A. Matheisen


"Status of the test cryomodule: short
overview of components and preparation of
final assembly"


tooling


item	status	expected	Comment
frame	OK		only one available
Chemistry	OK		cleaning rinsing ongoing
High pressure rinsing	OK		overloaded equipped with additional fixed points
carts and carrier	OK	KW 10.02 final adaptation	occupied by module 5
assembly line in clean room	95 % ready		


module


item	status	expected	
beam line components	Ok	under cleaning KW9-10	
HOM test absorber	OK	under cleaning KW 9-10	
gate valves	1 OK	No 2 under leak test/ KW 10-11	adaptation of middle part necessary
magnetic schielding	90% done	KW 10.02	
Quadrupole	under welding and leak check	KW 9-10.02	
























Status of equipment for Cavity Preparation

A.Matheisen 25.2.02

Cavities	welding of structure	Rf measurement s in lab done	Chemical treatment	assembly to module	testrun to qualify infrastructure
2*7 cell No 1					
Status	December 01	February 02	stand by		
Expected			KW 9.02	KW 11.02	
2*7 cell No 2					
Status	January 02	on going			
Expected		KW 9.02	KW 9-10.02	KW 11.02	
2*7 cell test cavity					
Status	none		KW 8-9.02		on going
expected				test KW 9.02	KW 8-9

R. Lange

"Schedule of the cryomodule assembly"

**Time-Schedule for Superstructure-Module Assembly, Installation
in Linac, Warm Tests, Cool Down and Cold Tests together with Module 1*.**

What has to be done , untill superstructure module assembly can be started?

-String superstructure ready	==> HP/Cleanroom work	on the way
-All parts ready	==>Vacuum vessel Cold mass Thermal shields Superinsulation Flanges, screws etc. Tubing partly different Quad incl. Hom-Ads, BPMs Current lead Super-Tuners tests Cabling, Sensors... Magnetic Shielding? Decision	o.K. o.K. o.K. o.K. o.K. on the way on the way on the way on the way on the way on the way necessary!
-Preparation/check all components	Start 28-March-02	
-Tooling set for module type 2	Start 28-March-02 ==>Preparation area incl. Surveyors (Posts, reference points,cold mass, rail..) ==>Cantilever area (Railway)	

**Module 5 and Superstruktur cryostats are of different types and need different tooling !
(Vacuum-vessel, distances supports/posts, cavity vessel, alignment...)**

Module 4, 5 and... are of module-type 3

Module 2, 3, 1* and .. are of module-type 2

Module Superstructure is of module-type 2 and contains some specials

==>Superstructure tooling cannot be set up before Module 5 is ready!!!

After setting up the tooling, superstructure assembly can be started.

Up to now for module 5 assembly there is a delay of 9 days.


- Start Superstructure module assembly==>04-April-02
- Superstruktur e module ready ==>10-May-02 Must be ready!!!! Or delay!!!!
- Installation superstructure in linac ==>28-May-02
- Final Test superstructure /M1* ==>25-June-02
- Cool Down Linac (Capt/Super/M1*) ==>09-July-02
- Start Cold Tests ==>12-July-02

-----This Schedule is very optimistic but possible-----


Steps until TTF 2

Current Status
TTF 1
until End April-02
(since June - Q2)


22-Feb-02 Ranger M5s




Test Superstructure and M1*
with beam
until End Oct-02




Test M3, M4, M5
without beam
until End Jan-03




TTF 2
Begin July - 03








R. Lange


"Cold test of new tuner"











Status:22-Feb-01 Albrecht/Lange -MKS1-

Tests of Cold Tuners for Supersucture Cavities.

Where/how do we test superstructure tuners?

- On old 9-cell cavity with He-vessel
Modifications for He-vessel necessary(bellow, flanges, bolts..)
To fix the cavity length installation of standard tuner necessary!(instead of clamps)
- At 300K in our workshop before and after CHECHIA tests.
(fr, alignment, survey , motor/gear..)
- In CHECHIA at 300K, 4K and 2K and again at 300K.

What do we test in CHECHIA? Using Video/NWA/Computer

- 300K fr= f(Cav-pressure, He-vessel-pressure..)
- Cool Down fr= f(T, He-P)
- 4K fr= f(motor-steps)
- 2K fr= f(motor-steps)
- 300K fr= f(Cav-Pressure, He-Pressure)

How many superstructure tuners have been/will be tested?

- 1 prototype in Feb-02 (expensive version)
- 1 superstructure tuner (modified, final version)
- ==>All 4 superstructure tuner will have a cold test in CHECHIA.

Second superstructure tuner already prepared for CHECHIA test.

Some results and comparisions

	Super-Tuner	Standard-Tuner
Tuning range max . Length	1.1 mm	1.9 mm
Tuning range max. Frequency	430 kHz	820 kHz
Tuning motor-steps/Hz	0.38-0.42	0.74
Delta f(warm/cold)=fr(300K)-fr(2K)	2000kHz	2000kHz
Delta f(4.3K/2K=fr(4.3K)-fr(2K)	70kHz	30kHz
Adjust Cav. 300K to get fr equ. 2K	<1.3Ghz	>1.3Ghz
Tuning at 2K means	Length>	Length<
Tuning at 2K means	fr>	fr<

Comparision Superstructure-Tuner/Standard-Tuner stiffness difficult, for both are installed.

Conclusion:

Test results show, the superstructure -tuner is able to tune superstrukturs at 2K.
Important :Correct adjustment at 300K is necessary.



Summary of RF Warm Measurements

J. Sekutowicz

DESY, February 25, 2002

Colleagues involved in the presented work:


R. Bandelmann, T. Büttner, J. Iversen, D. Kostin,
G. Kreps, W.-D. Möller, H.-B. Peters, S. Zheng

1. FM passband and FM Couplers
2. Tuning of the FM rejection filter of HOM couplers
3. HOM measurements

Two Nb prototypes of 2x7-cell superstructure have been built:

SST_I made of subunits 7Z1 and 7Z5

SST_II made of subunits 7Z6 and 7Z3




All 4 subunits had been tested in the vertical cryostat before they were sent to ZANON for final welding.

All have reached Eacc of 18 MV/m, limitation was still in the superconducting gaskets, placed 90 mm apart from the end-cell.

1 FM passband and FM Couplers

Field flatness of both superstructures, after the final welding, is still better than 90 %, in spite of milling, transportation and welding, performed on subunits equipped with LHe-vessels (no access to cells for tuning even if it is necessary):





Conclusions here:

- + we can pre-tune cavities providing field flatness (ff) of 99 %
- + we can weld LHe vessel keeping ff better than 98 %
- final BCP must be less than 20-25 μm to keep ff better than 95 %,
the removal rate of the chemical treatment seems to be difficult to control,
- + we can achieve much better field flatness when sequence of preparation steps will be similar
to the sequence used for 9-cell structures.



FM couplers

Expected operation at gradients in the range of :


2 MV/m (HOM experiment) up to 18 MV/m (energy gain measurements)
and the beam current $I_b = 4$ mA define the range of Q_{ext} :

Table 1. Range of Q_{ext} for the superstructure experiment

No.	Beam parameters : q, f_{rp}	2 MV/m	18 MV/m
1	4 nC 1 MHz	$5.5 \cdot 10^5$	$5 \cdot 10^6$
2	74 pC 54 MHz	$5.5 \cdot 10^5$	$5 \cdot 10^6$

SST parameters : active length $L = 1.614 \text{ m}$, $R/Q = 1457 \Omega$

Q_{ext} of FM coupler vs. penetration depth measured on SST_I



The whole required range of Q_{ext} is covered by the mechanical adjustment of the penetration depth and, in addition, we will have a 3-stub tuner at the front of input coupler.





Other modes from FM passband; frequencies and Q's

Table 2. Q_{ext} of all modes from the FM passband


	SST_I			SST_II		
Mode No.	f [MHz]	$Q_{ext\ coupler}$	f [MHz]	Q_{ext}	Q_{ext}	
1	1274.244	4.3E+06	1274.432	4.0E+06		
2	1274.594	9.6E+09	1274.491	4.5E+08		
3	1277.857	1.4E+06	1277.882	1.2E+06		
4	1278.012	5.8E+07	1277.983	1.3E+07		
5	1282.843	7.9E+05	1282.822	7.1E+05		
6	1282.955	3.1E+06	1282.922	2.7E+06		
7	1288.408	5.1E+05	1288.256	9.1E+05		
8	1288.424	1.8E+06	1288.426	1.3E+06		
9	1293.046	1.3E+06	1293.116	1.4E+06		
10	1293.309	1.4E+06	1293.379	1.0E+06		
11	1296.385	1.4E+06	1296.444	1.7E+06		
12	1296.717	1.0E+06	1296.774	8.5E+05		
13	1297.595	2.8E+06	1297.649	2.6E+06		
14	1297.882	6.0E+06	1297.938	5.5E+06		

32

Mode No. 2 in both superstructures has big external Q of FM coupler because there is no stored energy in the subunit next to the FM coupler.




This situation was simulated with HOMDYN in 1998, and there was no influence on the beam, even half of the FM pass-band with $(R/Q)_s$ near to zero and Q_s about 10^9 , hits exactly spectral lines.





Is there any additional damping of these modes ?

The rejection filter of HOM coupler is adjusted to suppress 1300 MHz thus rejection of 1275 MHz is ~ 30 dB weaker !!!




This will give some damping to Qext of the order of $5 \cdot 10^8 \div 10^9$.

We expect additional damping of this mode by the HOM couplers No 2 and No 3.

The expected Qext will be in the range of: few 10^8


2. Tuning of the FM rejection filter of HOM couplers

- Adjustment of filters of the HOM coupler No. 1 and No. 3 which are attached to the end beam tubes is similar to the adjustment of filters for TTF cavities.
- Situation is different for the HOM coupler 2, which is attached to the interconnection. In the interconnecting tube, 0-modes (both subunits in phase) have different field pattern from π -modes (both subunits in contra phase)




$\pi-\pi$ mode
magnetic field in the interconnection

Strong overlapping of modes due to low quality factor of warm Nb makes difficult direct optimising of the rejection filter for the suppressing of accelerating mode. The tuning procedure is shown stepwise below.



Transmission signal from the HOM coupler before suppressing of FM mode (2nd from the right).

Transmission signal from the HOM coupler when filter is partially tuned.



38

Signal from the HOM coupler when filter is further tuned. The FM mode is shadowed and can hardly be seen between two resonances. The most left peak, the $6\pi/7 - 0$ mode is still visible.

The method of tuning has been proposed by G. Kreps. The filter will be adjusted first for the $6\pi/7 - 0$ mode and then slightly detuned towards higher frequency.

Conclusion:

The method was never tested before and could not be verified since cold test of 2x7 cell structures is, with the present infrastructure at DESY, impossible.



Adjustment of 4 pick-ups

The 4 pick-ups in each SST are mechanically adjusted to have the same penetration depth. We would like to keep Q_{ext} of all in the range of $2 \cdot 10^{11}$.

Table 4. Pick-up transmission for FM pass-band: SST_I


Mode	Pickup 1 [dB]	Pickup 2 [dB]	Pickup 3 [dB]	Pickup 4 [dB]
$\pi-7/7 \pi$	-34,0	-30,6	-32,5	-40,0
0-7/7 π	-31,0	-31,2	-32,7	-32,2
$\pi-6/7 \pi$	-22,8	-24,2	-26,2	-24,8
0-6/7 π	-25,3	-25,3	-25,8	-25,7
$\pi-5/7 \pi$	-23,9	-24,3	-25,4	-24,7
0-5/7 π	-23,3	-23,2	-25,0	-24,6
$\pi-4/7 \pi$	-26,1	-26,4	-26,5	-26,1
0-4/7 π	-21,4	-21,4	-26,2	-26,0
$\pi-3/7 \pi$	-31,3	-31,6	-33,3	-32,7
0-3/7 π	-25,4	-25,2	-33,2	-32,9
$\pi-2/7 \pi$	overlapping		-48,7	-48,6
0-2/7 π	-31,2	-31,1	-48,5	-48,7
$\pi-1/7 \pi$	-	-	-	-
0-1/7 π	-41,6	-42,0	<-80	<-80

59



3. HOM measurements

122 dipole modes of the warm SST1 have been measured. All modes are damped sufficiently below the BBU limit (solid line). The most dangerous modes are listed in Table 3.



Longitudinal impedance of dipole modes. The red line shows BBU limit: $Z_{\max} = (R/Q)_{\max} 10^5$ (computation done by Nicoleta).




Table. 4 Most dangerous dipole modes of SST1

F MHz	R/Q $[\Omega/c]$	Z	Polariz.
1708,113	17, 40		
1709,778			
1712,771	13, 20		
1714,451			
1748,715	12,1	156	1,3E+04 60
1750,547			
1848,868	5, 1		
1849,470			
1865,490	10, 20		
1866,220			
1871,330	6,1	29	4,8E+03 overlap.
1872,534		18	3,0E+03 overlap.
1906,968	2, 6		
1921,455			
2568,736	26, 20		
2569,000			
2643,646	4, 4		
2646,035			
3079,063	1,(4)		
3079,996			
3081,647	2,(2)		
3082,403			

 Σ

We must note here that accurate measurements of dipole modes are very difficult since many of modes overlap for warm Nb cavities. The measurements become more and more difficult when frequency increases. The overlapping also makes measurements of polarisation very difficult.

18 monopole modes



72

Power of monopole modes at resonant excitation.

The damping is sufficient and total power stays below power capability of the output line of HOM couplers.



Test of the final tuner position

Final Remarks

SST_I

We have tuned SST1 to 1297.72 MHz, the frequency which after:

final	6 μm BCP	($\Delta f = -0.060$ MHz)
evacuation		($\Delta f = -0.390$ MHz)
cool-down		($\Delta f = 1.950$ MHz)

should lead to the operation frequency of 1300.000 MHz.

- + At this position sub-unit 7Z5 was pulled by the tuner by about 0.5 mm, exactly as required.
- sub-unit 7Z1 was at force-free position and the tuner was at position with maximum hysteresis
To avoid backlash we will make more final BCP, about 15 μm instead of 5 μm , to lower the frequency of the 7Z1.

f3

SST_II

The same situation is expected for the SST_II because the sub-unit 7Z6 had less BCP treatment than 7Z3. Also here additional 10-15 m BCP will help us to avoid backlash of the tuner.



Summary

- Both superstructures have reasonable field flatness, better than 91 %
- Qext FM coupler can be reached in the whole required range
- Damping of HOMs in SST_I is good (140 modes have been measured)
- HOM measurements in SST_II in progress, should be ready next week
- Polarization measurements are difficult due to overlapping of modes
- Tuning of the rejection filter of the HOM coupler attached to the interconnection must be done very carefully. Unfortunately the result of tuning procedure will be known first after cool down in the TTF linac.
- Slightly more final BCP treatment is needed for the subunits 7Z1 and 7Z6, to avoid backlash of tuners

J. Sekutowicz

"Preliminary program of the cold test, what
do we like to measure ?"



Preliminary program of the cold test, what do we like to measure ?

J. Sekutowicz

DESY, February 25, 2002

Colleagues involved in the presented topics:


P. Castro, M. Ferrario, A. Gössel, M. Huening, M. Liepe, H. Schlarb,
S. Simrock, S. Schreiber, K. Rehlich, M. Wendt.



We will have 3 types of measurements. For all measurements SST must be cooled down

- RF-measurements
- FM measurements with beam
- Interaction between beam and HOMs

The test cryomodule will be placed at ACC1 position. Cryomodule 1* will be installed at ACC2 for the high gradient test.



Whole re-arrangement of the TTF linac will be coordinated by:
P. Castro/S. Schreiber



- RF-measurements without beam (*group a*)
 - spectrum of the fundamental mode passband
 - spectrum of HOMs and damping
 - test of two methods proposed to balance field
 - sensitivity of the field profile vs. frequency of each sub-unit
 - maximum E_{acc} : is the limitation in cavities or in HOM couplers ?

Table 1. Group α : List of data to be measured for each superstructure

No.	Measurement	List of data to be measured	apparatus	accuracy
1	spectrum of the fundamental mode passband	Frequencies, Q_{ext} of 14 modes 4 Pick ups signals	NA	
2	spectrum of HOMs and Q_{ext}	Frequencies and Q_s 120 dipole modes: 1 st , 2 nd , 3 rd and 5 th passband TM011 monopole passband Signals from HOM couplers	NA	
3	test of two methods proposed to balance field	Signals of 4 pick-ups for FM, Number of steps of stepping motors, Signals of 4 pick-ups for other 13 modes	NA, PM ?	NA, PM
4	sensitivity of the field profile vs. frequency of each sub-unit	Number of steps of stepping motors Signals of 4 pick-ups for FM		
5	Maximum E_{acc} :	Signals of 4 pick-ups for FM Incident power in FM coupler Signals from HOM couplers for FM Signals of Temperature sensors (V and I)	PM V-meter	



This group of measurements is a replacement for the cold test in Chechia or in Cryomodule Test Stand.

It will be the first check at 2 K:


- of fully equipped 4 subunits with tuners after the final cleaning and the final assembly
we will have all components tested individually before the assembly(cavities, tuners, FM couplers...), but there will not be a Chechia-like test !!!!
- of the rejection filter adjustment of the both HOM couplers placed at interconnections
the proposed adjustment method has never been verified
- if there are cold leaks in subunits, couplers and beam line....

The modification of the infrastructure built for the 9-cell cavities was minor. This made the project less expensive and less time consuming but there is a risk.

The RF-group of measurements will be coordinated by:
S. Simrock/M. Liepe/G. Kreps/JS



- EM measurements with beam = re-filling process of stored energy in cells (group b)
 - End-cells signals vs. time
 - Energy variation within one train (expected variation $< 5 \cdot 10^{-5}$)




52

Figure shows whole the “new” TESLA train. It is similar for the “old” TESLA train of 800 bunches



Indirect measurements of the re-filling process (all signals normalized):



53

Figure displays end-cells signals (pickups) vs. time
in 2x7-cell SST with an ideal beam loading compensation

This method was never tested before. The big advantage is that presence of other accelerating structures in the linac is of "no meaning"



Energy variation within one train: direct measurements (*more information from Holger, Massimo and Siggi*)

For this test we would like to operate linac with 800 μ s long pulses and with following beam parameters:

- 1 MHz bunch frequency
- nominal charge of 4 nC/bunch
- bunch length about 1mm

Presence of the second cryomodule at ACC2 makes this measurements more difficult (*study in progress, some modification of HOMDYN code needed, Massimo*)

Roughly (qualitatively):

- Energy variation for a 9-cell cavity is lower than in SST, when the beam loading compensation is ideal.
- The main reason for the energy variation is the mode beating in accelerating cavity

$8\pi/9$ modes in standard cavities will have different frequencies
and

$6\pi/7$ groups will have different frequencies for both superstructures

one may expect that energy variation for whole linac will be uncorrelated (?) $\rightarrow 1/\sqrt{n}$ (n number of cavities)



- To estimate energy variation we will perform two measurements:
 1. ACC2 will be operated at Eacc of $\sim 2 \text{ MV/m}$ and ACC1 at $\sim 2 \text{ MV/m}$ and
 2. ACC2 will be operated at Eacc of $\sim 2 \text{ MV/m}$ and ACC1 at $\sim 18 \text{ MV/m}$
(it will be easier to vary gradient of ACC1 because both 3-stub tuners will be for this cryomodule remote controlled)
- Change in the measured energy variation at the end of TTF linac should give estimation for each cryomodule.

55

But:

we need to know how good is the control of amplitude and phase for different gradients ? (Stefan's talk)

Both measurements: direct and indirect will be done in parallel

Table 2. Group b of measurements: List of data to be measured for each superstructure

No.	Measurement	List of data to be measured/additional information	apparatus	accuracy
1	Indirect End-cells signals vs. time for the whole train of bunches	Signals of 4 pick-ups, 1 MHz, status of 3-stub phase shifters, status of tuners (position, steps ...) E_{acc} , P_{inc} , Q_{ext} , HOMs signals (TM011) mode.	ADCs	$\sim 10^{-4}$
2	Direct Energy variation within one train	Energy measurements at the injector region: Signals from BPMs for the whole train of 800 bunches Energy measurements at the end of TTF linac: Signals from BPMs for the whole train of 800 bunches Both SSTs: HOMs signals of TM011 modes Status of ACC2: E_{acc} , Q_{ext} , P_{in} of 8 cavities, signals of 8 pickups, HOMs signals (TM011) mode Beam quality: q /per bunch and its stability within whole train bunch length ...	BPMs	$\sim 10^{-4}$



Coordinators:

The FM measurements with beam will be coordinated by:
H. Schlarb / M. Ferrario / S. Simrock



••• Interaction between the beam and HOMs (group d)

1. energy deposition in monopole modes
2. active excitation of HOMs up to 3.1 GHz with amplifier (50 W)
3. search for deflecting trapped modes (as proposed by S. Fartoukh and S. Simrock)

58 ad. 1. Energy deposition in monopole modes without modulation of charge will be done simultaneously with previous group b.


ad. 2. Active excitation of HOMs : What is the idea behind this measurements ?

With this measurements we can calibrate setup (BPMs) for the search of deflecting trapped modes.

The accelerated beam (1 MHz or 54 MHz) will be injected on axis.

HOMs will be excited via one of HOM couplers (phase lock possible when we use one of two others couplers)

An example: $P_{in} = 10 \text{ W}$, Gradient in Superstructure 2 MV/m , Injection energy 16 MeV



Maximum radial position of the deflected beam



ad. 3. Search for deflecting trapped modes (group c)

Beam parameters: 54 MHz bunch frequency + modulation of charge

Beam position: 10÷20 mm off axis (this time in both planes)

Gradient: 2 MV/m

This test has been done already twice for standard TTF cavities.


In both runs some modes have been found with the same frequency (~2.58 GHz) in the whole tested cryomodule. No clear explanation up to now.

Is the following phenomenon a possible explanation ?




Bunches injected at 20 mm off axis in 9-cell structure are exposed to deflecting force which results from strong radial electric and angular magnetic field of the fundamental mode.

Example: $E_r(r=20\text{mm})$ and H_φ ($r=20\text{mm}$) when 9-cell cavity is operated at 2.2 MV/m





The deflecting force depends on the injection phase, but both components from the electric and the magnetic field add up.





Maximum energy gain (2.2 MeV)

Almost no energy gain (-0.1 MeV)



The radial position of bunches is as follows:


Bunch Radial Position, $E_{inj}=16\text{MeV}$, $G=2.2\text{MV/m}$, $r_{inj}=20\text{ mm}$



Energy gain: oscillation (60 μm) + focusing

No energy gain : oscillation (30 μm)

Similar result was computed by Holger¹ (code Astra).



Mean wave length of this oscillation corresponds to $f = 2586 \text{ MHz} ! \dots ? \dots !$

- Is this a reason why some modes almost at this frequency are present in all cavities ?
- Is this a reason why some modes decay much faster than expected ?

If this is true: can we build special 3.9 GHz cavity ($\lambda = 35 \text{ mm}$) operate it at 25 MV/m to have an undulator ??

¹ Thanks for the correction of my first wrong result

Conclusion: we should look closer to this phenomenon in the next HOMs measurements

Table 3. Group of measurements c: List of data to be measured for each superstructure

No.	Measurement	List of data to be measured	apparatus	accuracy
1	Energy deposition in monopole modes Without modulation (simultaneously with b)	Signals from 3 HOM couplers	PM SA	
2	Active excitation of HOMs up to 3.1 GHz with amplifier (50 W).	Signals of BPMs Power of amplifier Beam parameters Gradient	BPM electronics PM	
3	Search for deflecting trapped modes	Signals of BPMs Signals from 3 HOM couplers Modulation frequency Beam parameters		

Interaction between the beam and HOMs will be coordinated by:
N. Baboi/M. Huening / M. Wendt/O. Napoli/J. S.

M. Huening

"Short summary of the HOM experiments in
TTF linac"


HOM Experiment

Markus Hüning

10. Januar 2002

Higher Order Modes

The longitudinal field



Dipole Mode

$$\begin{aligned} E_z &= J_1(k_r r) \cos \phi e^{-ik_z z} \\ E_r &= -i \frac{k_z}{2k_r} [J_0(k_r r) - J_2(k_r r)] \cos \phi e^{-ik_z z} \end{aligned} \tag{1}$$

Close to the center this can be approximated by

69

$$\begin{aligned} E_z &\approx \frac{k_r}{2} r \cos \phi e^{-ik_z z} \\ E_r &\approx -i \frac{k_z}{4} \cos \phi e^{-ik_z z} \end{aligned} \tag{2}$$

Dipole Mode

A loss factor can be defined

$$k_d = \left(\frac{\omega}{c}\right)^2 \frac{\omega}{4} \left(\frac{R}{Q}\right) \quad (3)$$

With the energy lost by a bunch

$$U_q = k_d q^2 \rho^2 \quad \rho = \text{offset} \quad (4)$$

and the transverse kick

$$V_{\perp} = \frac{\omega^2}{2c} \left(\frac{R}{Q}\right) \rho q. \quad (5)$$

⇒ Study modes simultaneously with HOM-coupler and BPM.

Dipole Mode

Definition of Q_L from Energy


$$Q_L = \frac{\omega U}{P_d} \quad (6)$$

(Energy) time constant


$$\tau_E = \frac{\omega}{Q_L} \quad (7)$$

Then the power coupled out of the cavity is


$$P_d = \frac{U}{\tau_E} = k_d q^2 \rho^2 f_b \quad (8)$$




Setup




Observe beam deflection after modulation has been turned off






Locate the HOM


TESLA 2002-04




Trigger



A second trigger for τ is required











Steps of Scan

















about 20 HOM candidates with strong deflection
 (dipole D mode and quadrupole mode Q assignment - preliminary)
 about 60 other excited modes with weak deflection



∴ Examples of time domain spectra:




the excited mode
is present in
all cavities



several modes in
different cavities
are excited

Modulation Frequency : 24.205 MHz

TESLA 2002-04



N. Baboi

"What can we improve in HOM measurements ?"

WHAT CAN WE IMPROVE in HOM MEASUREMENTS with MODULATED BEAM?


Nicoleta Baboi

Reminder of principle
Past problems
What could we do ?

Basic principle

Excite mode when: $\omega_{\text{mod}} = |\omega_i - m \cdot \omega_b| \leq \omega_b/2:$

$$\Delta x'_{\text{res max}} = c \frac{e}{E} \delta x_0 \left(q_0 \frac{\omega_b}{2\pi} \right) \lambda \frac{1}{\omega_i} \left(\left(\frac{R}{Q} \right)^2 \right)^{1/4}$$



- Assumptions:
 - steady state: bunch train length $\gg \tau = 2Q/\omega$
 - exactly on resonance
 - horizontal polarization
- Requirements:
 - low energy
 - large beam offset
 - high average current
 - high modulation amplitude
 - long bunch train \Rightarrow reach steady state
 - high bunch frequency \Rightarrow avoid resonance overlap
 - low frequency step \Rightarrow not to miss high-Q modes

Problems in the last measurements

- many quadrupole modes excited much stronger than dipole ones
- instabilities of the beam (position, charge, etc.)
- calibration
- instrumentation limitation
- time and men power
- too much automatization?

What can we improve?

- We need more information!

- polarization ✓
- vertical plane
- check mode character


➢ increase BPM resolution

- Possible changes:

- reduce beam deflection ⇒ avoid quadrupole modes
 - but we loose sensitivity; which can be regained by:
 - increase current
 - increase bunch frequency
 - more sensitive BPMs
- Make complementary measurements (e.g. use two BPMs)
- It needs lots of time! But we have fewer cavities and HOM couplers and a bit more experience


What can we improve? (2)

TESLA 2002-04

- Measure R/Q with 
 - > no superimposed resonances, as seen at BPM
 - > need calibration of cables at higher frequencies
- Will be better prepared
 - > know more problems
 - > use RF measurements of HOMs \rightarrow dipoles + quadrupoles ? (+ monopoles)

5th Dipole Passband Trapped Mode

Prediction for : $f = 3068 \text{ MHz}$, $R/Q = 1.1 \Omega/\text{cm}^2$, $Q = 3.4 \cdot 10^7$
 in cavity C7, as a function of the modulation frequency



M. Ferrario

"Estimation of bunch-to-bunch energy
variation in TTF linac with two
superstructures and standard cryomodule"

THE HOMDYN MODEL

M. FERRARIO
INFN-LNF

LONG TERM MULTI-BUNCH BEAM CAVITY INTERACTION FOR RELATIVISTIC AND NON RELATIVISTIC BEAMS: TRANSIENTS, BEAM LOADING & SPACE CHARGE EFFECTS

* NORMAL MODES EXPANSION OF CAVITY FIELDS


we describe the field amplitude evolution under the slowly varying envelope approximation for each resonant mode

analytical propagation of field from bunch to bunch, including external generator

* CURRENT DENSITY DESCRIPTION OF BUNCHES BY UNIFORM MULTI-SLICE CYLINDER

we describe the transverse dynamics by the bunch envelope equation for each bunch slice

analytical computation of slice space charge fields



RELATIVISTIC BEAM





Figure 2: Total accelerating voltage during the entire TESLA beam pulse. The residual oscillations, are mainly caused by the nearest mode of the pass-band, decaying according to the time constants of the modes. The induced bunch-to-bunch energy spread is very small, from $3 \cdot 10^{-6}$ at the beginning to $0.5 \cdot 10^{-6}$ at the end.

$E_0 \approx 16 \text{ MeV}$

$E_{\alpha} \approx 25 \text{ MeV}/\mu$

TESLA 2002-04




100

$$\mathcal{E}_0 = 58.7 \text{ MeV}$$

$$\mathcal{E}_{\text{kin}} = 20 \text{ MeV}$$

9-cell structure




$$\frac{\int E}{E} \sim 1 \cdot 10^{-3} \quad \frac{\Delta E}{E} \sim 10^{-4}$$

H. Schlarb

"Limits in energy measurements at the
injector region and at the end of linac"

Beamline EXP1 & EXP3



Orbit Independent Measurement

Momentum of bunch can be written in first order approximation

$$p = p_0 + \Delta p \approx p_0 \cdot \left(1 + \frac{\Delta x_3}{D_x(s_3)} \right)$$

Collective betatron motion occurs as small perturbation of the measured beam position:

$$\downarrow \\ x_3 = \Delta x_3 + \delta x_\beta$$

To remove the betatron motion, two bpms in front of the spectrometer dipole can be used. One finds:

$$\frac{\Delta p}{p_0} = a_1 x_1 + a_2 x_2 + a_3 x_3 \quad \text{with}$$

Transfer Matrix

$$a_1 = \frac{1}{D_x l_{12}} \cdot (M_{11} l_{2d} + M_{12}) = -0.958 \text{ m}^{-1}$$

$$a_2 = -\frac{1}{D_x l_{12}} \cdot (M_{11}(l_{12} + l_{2d}) + M_{12}) = 1.380 \text{ m}^{-1}$$

$$a_3 = \frac{1}{D_x} = -0.672 \text{ m}^{-1}.$$

Dispersion


If the bpm's are calibrated and the resolution known, then the rms energy resolution yields:

$$\frac{\delta p_{res}}{p_0} = \sqrt{\sum_i (a_i \delta x_{i,res})^2} = \frac{\text{rms resolution of bpm's}}{1.2 \cdot 10^{-4}}$$


(assumption: bpm noise is statistically independent)

Resolution of BPM's in the experimental area

Experimental setup:




- Measurement (10/01) resolution bunch to bunch at 1 Hz:



- Jitter from electronic noise within a bunch train is expected to be smaller
- Measurements are planned this week (requires long pulse operation)

Calibration of BPM's


Using well known steerers to induce kicks to the beam



Example BPM1EXP1:

Umrechnungsfunktion für BPM1
 $x = -6.38 U^3 - 4.83 U^2 - 9.99 U - 1.56$

(11/01)



Results for the bpm electronic response functions:

$$x_{\text{BPM}1} = -6,38 \cdot U^3 - 4,83 \cdot U^2 - 9,99 \cdot U - 1,56$$

$$x_{\text{BPM}2} = -17,93 \cdot U^3 - 6,37 \cdot U^2 - 17,30 \cdot U - 0,02$$


$$x_{\text{BPM}3} = -12,74 \cdot U^3 - 7,32 \cdot U^2 - 10,31 \cdot U - 0,13$$

BPM_X 1EXP3

[mm]

BPM_X 1EXP3

[mm]



[s]

[mm]

Energy of bunches in a macro pulse


M

Mean: 220.14 MeV

Number of Bunches: 176

1st Bunch: 219.20 MeV

8



[MeV]

Feedback: Nikolay.Sturm@desy.de

Test of Energy Server


Dipole calibration:

wavelength
calculated
from bunch energy



Sase spectrum
averaged over
several bunches

$$E_0 = \frac{2438,5 \pm 1}{\sqrt{\lambda_{\text{Photon}}}}$$

$$E_0 = (8,09 \pm 0,1) \cdot I_{B1}$$




Induced artificial betatron oscillation:



Correction reduces the influence of betatron motion by more than a factor of 10 (in limited meas. range).

Measured Energy Stability

- Varies from time to time and depends on the machine parameters
- Intra-bunch energy spread during the measurements about 1 %
- Energy jitter bunch to bunch at 1 Hz operation.



mean E = 245.35 MeV

rms E = 0.09 MeV


rms dE/E = $4 \cdot 10^{-4}$

@ Nikolay Sturm

time = 40 min.

⇒ Energy stability is more than an order
in magnitude smaller than the intra-bunch
energy spread

Cross-Talk to trailing Bunch



Required Steps for High Precision Energy Measurement

- Adjustment of ADC timing
- Recalibration of BPMs with beam
(inj & exp \Rightarrow 4 hours stable beam conditions)
- Measurement of the intra-macro pulse resolution
(2 hours beam time/ parasitically possible)
- Implementation to the server
(is a server also for the injector desired ?)
- Test of servers
(2 hours stable beam conditions)
 \Rightarrow major hardware changes are not expected

S. Simrock

"Limits in the amplitude and phase control
for 2x7-cell superstructure and for
standard cryomodule at 2MV/m and
15 MV/m operation"

112

LLRF for Superstructure Test

Stefan Simrock

DESY



— Superstructure Test, Feb. 2002 —


— Stefan Simrock —

LLRF Parameters

- Operational
 - Medium (15 MV/m) and low gradient (2.5 MV/m)
 - ... for ACC1(SS) and ACC2
 - Long beam pulses (up to 8 mA, 800 μ s)
 - ... 1 MHz and 54 MHz with current modulation
- Expected field stability with adaptive feedforward
 - $\Delta E_{acc} < 0.02$ MV/m
 - $\Delta \phi < 0.05$ deg. (15 MV/m), 0.3 deg. (2.5 MV/m)

Note : assumes $\Delta I_b/I_b < 5\%$ within bunch train at 8 mA
 $\Delta I_b/I_b < 0.5\%$ pulse to pulse at 8 mA





LLRF for Superstructure (SS) Test

- RF Control

- Separate klystron for SS- and 8 cav. cryomodule
- Split 24 cav. LINAC system (24 cav.) in 2 x 8 cav. systems
 - ... 8 probes for 2 x 2x7-cell cavity superstructure
- control vector sum of 2 SS cavities
 - implement bandpass filter at downconverter output
 - modify LO tables for continuous phase shift
 - remote controlled waveguide tuners

- RF diagnostic

- precise detuning measurements
 - ... for cavity field flatness, microphonics, Lorentz force
- high resolution and wide band gradient detection
 - ... measure excitation of passband modes
- measurement of IQ or A&P transfer function with lock-in



LLRF Tests with Superstructure

Contact Person: V. Ayvazyan (x4912), Stefan Simrock (x4556), H. Weddig (x4910)

Objectives:


1. Determine LLRF performance limitations in presence of beam loading at low (2 MV/m) and medium (10-15 MV/m) gradients with/without passband filter.
 - Note : expected stability is 0.25 MV/m (rms) at all gradients
2. Measure excitation of other passband modes by beam and generator

Prerequisites:


- Modified LLRF control with/without bandpass filters for 2 probe signals.
 - filter from 50-150 kHz around 250 kHz
 - Modify LO for sinusoidal operation ($9^*4 = 36$ points on circle at 9 MHz)
- Remote control for waveguide tuners
 - Adjust phase of incident wave and loaded Q
- Monitoring of all 8 probe signals (2 per cavity)
- Detector for excitation of other passband modes (8 cavity probe signals).
 - Diode bandwidth few MHz
 - Downconverter bandwidth 30 MHz with 0.5 deg. rms phase noise (= 1 %)
 - Need digital lock-in to measure with high resolution of measurement.
- Precise detuning measurement for superstructures (accuracy 1 Hz averaged).
- Beam energy measurement (to resolve 1e-4 fluctuations of cavity field for individual bunches).
- List of passband modes with coupling to beam and generator.
- Precise measurement of bunch charge (1%) and bunch to bunch fluctuations.

Detailed Procedure:


1. Gradient and phase stability
 - Feedforward only
 - Feedback, determine maximum gain with/without bandpass filter
 - Gradient and phase calibration with beam
2. Waveguide tuner
 - adjust for on-crest operation in both superstructures
 - adjust loaded Q equally
3. Excitation of passband modes
 - generator and/or beam, with/without filter, different beam currents, feedback gain, and gradients.
 - time domain and spectrum, identify which modes are excited
 - determine coupling of beam and generator to passband modes.
4. Cavity tuning
 - Adjust for best field flatness. Requires to know Hz/step each tuner and to determine ratio of stored energies (proportional to frequency change of SS versus detuning of individual cavities).




RF generator





(a) pick-up antenna signal before down-conversion



(b) pick-up antenna signal after down-conversion









(a) 2x7-cell superstructure

TESLA 2002-04





(b) 2x9-cell superstructure





LLRF Measurements

- RF Control Performance
 - gradient and phase stability
 - ... rf and beam energy measurements
 - ... noise sources (beam, microphonics, Lorentz force)
 - ... Adaptive feedforward
 - ... Loop stability with/without bandpass filter
- Cavity Tuning
 - field flatness
 - resonance frequency
- Other RF measurements
 - excitation of passband modes by rf and beam
 - gradient and phase calibration (beam based)







125



Vectorsum ACC1




Vectorsum ACC1




127

Excitation of Passband Modes



Bandwidth = 3 MHz
 Signal = 1-2 V
 Noise = $50 \mu\text{V}_{\text{rms}}$ ($\Delta f = 1 \text{ MHz}$)



Superstructure Test, Feb. 2002

Stefan Simrock

INTERPOLATION METHODS FOR SPINNING

INTERPOLATION METHODS FOR SPINNING

16. 15] 4. 2e+04
4. 2e+04

4. 1e+04
4. 1e+04

4. 8e+04
4. 8e+04

5. 5e+04
5. 5e+04

5. 2e+04
5. 2e+04

5. 9e+04
5. 9e+04

5. 6e+04
5. 6e+04




P. Castro

"Proposed re-arrangement of TTF linac for
the beam test of superstructures"

Aperture limitations :

Present status




ACC 3

TESLA 2002-04

beam

Acc 4





S. Schreiber

"Injector: stability of charge at operation
at 1 MHz and at 54 MHz"


Typical Measurement of the Charge Stability

- Charge measured at ICT B1 rf gun exit
Laser energy from photodiode (green)



- In this case:
charge av = 2.3 nC, 5.7 % rms
(smallest 3 %, seen also > 10%)
laser = 1.7 % rms
(have to check linearity of the diode)


Example of charge fluctuation in a flat pulse train



.. In this example:

- pulse train length 100 us (1 MHz)
- average charge over the train 2.2 nC
- rms fluctuation along the train 0.014 nC = 0.6 %

Example of charge fluctuation in a less flat pulse train




∴ In this example, the train is less flat:


- pulse train length 150 us (1 MHz)
- average charge over the train 2.1 nC
- rms fluctuation along the train 0.06 nC = 2.8 %

To Expected Charge Fluctuations

- Data from the long pulse run 17-Feb-2002
Collected over 8 hours (8229 trains of > 50 us)




- the relative fluctuation for short trains is 1 % rms
for longer trains 3 % rms



Injector layout for HOM SStructure experiments

Modifications:

- laser beam spot diameter 10 mm
- KCsTe if possible
- button BPMs equipped with electronics from the undulator
- additional stripline BPM in the spectrometer arm to measure energy along the train
- additional vertical steerers around dogleg
- reestablish BIS long pulse operation mode in analysis mode




Resolution of the Injector Spectrometer

PSI-4002-04


- Dispersion: $13.66 \text{ mm} = 1 \% \text{ dE/E at OTR screen}$
(at SEM grid 16 mm)
-> with a 500 um resolution BPM we achieve
an energy resolution of $\text{dE/E} = 0.04 \%$
- The resolution of the present OTR screen with the
present camera magnification is
 $1 \text{ pixel} = 0.48 \text{ mm} / 13.66$
 $= 0.035 \pm 0.004 \% \text{ dE/E}$

We add a stripline here




S. Choroba

"RF power distribution system for the test
cryomodule and 1* cryomodule at ACC2
position"





3 Stub Tuner (IHEP, Bejing)



RF System TTF Phase 1

142





M. Wendt

"BPMs, electronics and automatic data read-out for the HOM experiment and for the FM experiment"

Instrumentation Requirements for the Superstructure HOM Measurements

Manfred Wendt

February, 2002




Contents



Contents

- Measurement of the HOM-coupler signals
- Measurement of the BPM signals
- Measurement of beam orbit and energy



Measurement of the HOM-coupler signals

Semi-automatic search for:

$$f_{\text{HOM}} = n f_{\text{bunch}} \pm f_{\text{mod}}$$



Realisation:

- Measurement of the HOM-coupler signals in the **time-domain** with a spectrum-analyser set to zero-span.
- Analysis the signal decay after the bunch passage to determine the Q-value of the mode.


HOM Measurement Setup

accelerating structures:

2 superstructures (2 * 7-cell 1.3 GHz cavities) with 6 HOM-couplers



Measurement of the HOM-coupler signals



5

Instrumentation details:

- 10 dB attenuators in the HOM-coupler signal path to reduce reflections and prevent overload of the spectrum-analyser.
- Measurement (network-analyser) of the insertion loss: HOM-coupler output – to – spectrum-analyser input of each HOM branch.
- GPIB-controlled SP6T microwave relais
(Keithley S46 microwave switch system).
- The spectrum-analyser (*HP E8563E*) has to be external triggered (plus evt. appropriate gating of the video signal), resolution and video bandwidth has to be set to moderate values (typ. ≥ 100 kHz).

Measurement of the HOM-coupler signals


GPIB instrument control and software:

- Spectrum analyser (plus evt. added power meter) and microwave switches are computer controlled through a LAN/GPIB gateway.
- A semi-automatic measurement procedure “*HOM Search*” (written in *Agilent VEE Pro*), running on a HP workstation, controls the instruments and stores the data.
- The driver sections for the new *Keithley* switch unit have to be rewritten, new drivers for the power meter have to be included!
- Other features could be further included into the procedure, like online Q-value determination...



Measurement of the HOM-coupler signals

7



Semi-automatic HOM measurement procedure "HOM Search".

Beam-test for the superstructure

152



Measurement of the BPM signals

Beside (!) the re-entrant cavity BPM (C. Magne), a **stripline BPM** (DESY-Zeuthen) will be used for the dipol mode search and analysis:

- The stripline BPM delivers high-level (100 mV range) broadband pulse signals, keeping the bunch structure.
- The read-out electronics of the undulator BPM's (with very little modifications) will be used for the signal processing.
- Both planes (horizontal and vertical) can be analysed simultaneously.

Measurement of the BPM signals

9

TESLA 2002-04

- Single bunch position resolution is expected to be
50...100 μm @ 10 ns (!) **measurement time.**
- Limitations of the present electronics:
Intensity dynamics may be limited to only 3...4.
Beam position range is limited to 30...50 % of the aperture.
- For the data acquisitions a oscilloscope (*Tektronix 7404*) is foreseen, it can be computer controlled directly over the LAN.
- The setup of all this new hard- and software requires approx.
3 weeks of preparation!




154



Measurement of the BPM signals

10

TESLA 2002-04




Schema of the “monopulse” AM/PM BPM read-out electronics:
Major modifications TBD: Bypass of the LNA's and the T&H amp.

Beam test of the Superstructure

155

11

Measurement of the BPM signals



The BPM electronics is implemented as modular hardware


DESY
Festina Lente
Detector
BPM Structure



I. Measurement of the BPM Signals

12

The single bunch analogue position signal of the BPM electronics (between LP and T&H amp) resolves the beam displacement within 10 ns!



For the data acquisition of the individual beam positions of all bunches in the train a commercial oscilloscope (*Tektronix 7404*) will be used.



154

Measurement of beam orbit and energy

At least 6 Beam position monitors (BPM) are located along the linac. Button BPM's at the injector, stripline BPM's (Zeuthen type) at the accelerating structures and in the spectrometer.

- The read-out electronic system of the undulator BPM's will be re-arranged and used for beam orbit / energy measurements.
- Data-acquisition time is limited to the usual $1 \mu\text{s}$ ($\equiv 1 \text{ MHz}$), the resolution is expected to be $\approx 100 \mu\text{m}$.



Measurement of beam orbit at 1 energy



14

TESLA 2002-04


- All hardware components are available; analogue read-out electronics, VME ADC- and trigger-boards, VXI- and VME-crates...
- Cabling will be an issue, only a few cables may be re-used.
Good BPM performance requires well matched (electrical length) cables of high quality.
- The setup of the new infrastructure **needs time and manpower!**

159

K. Rehlich

"Diagnostics: re-arrangement for the beam
test of superstructure"

Kai Rehlich, 25.2.2002



H. Schlarb

"Interlock re-arrangement for the test"

Requirements on the interlock system for Super Structure Tests

- Instantaneous temperature rise not critical for moderate β -function:

Example: $\beta \approx 20$ m, $\varepsilon \approx 1e-5$ m, $E = 250$ MeV, $Q = 4nC$

$$\Rightarrow \sigma = 450 \mu\text{m}$$

\Rightarrow # bunches ≈ 400 until steel cracks

Hence with weak quadrupoles the risk to damage the beam pipes is relatively small.

\Rightarrow sufficient time to switch off the linac

- To limit the neutron production at energies above the geant resonance threshold:

Beam Losses $< 10\text{-}20$ W (point-like source)

For 5Hz, 8mA, 800 μ s beam parameters:

\Rightarrow BC2 @ 80MeV: losses $< 0.4\% \cdot I$

\Rightarrow ACC3 @ 250MeV: losses $< 0.1\% \cdot I$

\Rightarrow Can only be achieved by photomultiplier based interlock (BLM)


- To guarantee the functionality of the Beam Loss Monitor System (BLM) based on photomultiplier toroids are required for supporting.

- Safety of exit window (to be discussed)

Photomultiplier Interlock System for Super Structure Test

H.Schlarb 24.02.2002
D.Pugachov


TESLA 2002-04



- 10 photomultipliers are required

- cables exist as well as required PM types

Fast Protection System based on Toroids for Super Structure Test



165

- For linac operation same combination of toroids can be used as before
- Macro-pulse operation in analysis mode => B1-T3 have to be commissioned
- Only for diagnostic purpose: B2, B3, T2, and T5,T6 which have to be reinstalled to the beamline
- 30–50 us active protection by FPS is sufficient
- for high gradient tests in ACC2 the protections is more seriously