



Status of the optical synchronization system

Holger Schlarb DESY
for the LbSyn team



V. Arsov, M. C. Behrens, Bock, P. Gessler, M. Felber, K. Hacker, F. Loehl, F. Ludwig,
K-H. Matthiesen, B. Schmidt, S. Wesch, A. Winter, J. Zemella
(Deutsches Elektronen-Synchrotron)



S. Schulz, L. Wissmann
(Universität Hamburg)





J. Szewinski
(Warsaw University of Technology Institute of Electronic Systems)



W. Jalmuzna
(Technical University of Lodz)




Optical synchronization system




■ Main issue: **robustness, stability and maintainability** \Rightarrow Prototype at FLASH

Layout of synchronization system at FLASH




- Implementation of entire system 06/2008 - 2010




- Backbone: beam based stabilization of arrival time
- Conjunction with high precision synchronization of lasers
- Synchronization of all timing critical devices (~ 14 incl. FLASHII)
- Point-to-point synchronization ~ 10 fs rms (e- < 30 fs rms)
- Permanent operation and long term stability /availability investigation

Layout of synchronization system at FLASH



- Implementation of entire system 06/2008 - 2010



- Short link to server more end-stations
- Synchronization of both photo injector lasers &
- Providing RF for 3th cavity (monitoring/source)
- Monitoring for 1.3GHz at Kryo hall
- Engineered version ~ spring 2010


Key experiment




To verify method, the mechanical and electrical designs and for software development before assembly

- Fiber link stabilization in accelerator environment ☺
 - Complete system test: MLO, one LINK and Beam Arrival Monitor ☺
 - Consistency check: two BAM against each other ☺
 - Intra-train feedback system (ACC1) partially ☺
 - Consistency check: BAM versus EO partially
-
- Supply to many links + infrastructure
 - Optical lock of Ti:Sa laser to fiber laser (OCC-EO)
 - High precision Energy Measurement (EBPM)
 - L2RF conversion at 1.3GHz with sub 10fs long term stability
 - Short link implementation
 - Synchronization of photo-injector laser (OCC-NdYLF)
 - ...

Key experiment: - BAM versus BAM




6




- two Bunch Arrival time Monitor in drift section (~60 m distance)
- evaluation of integrated timing jitter (Hz-MHz)
- evaluation of drifts and offsets
- commissioning of two links with precision laser timing requirement
- test of arrival time FB by regulating ACC1 amplitude


Optical synchronization system: Link



- Installation of two fiber links at FLASH





Long term behavior of link






■ Installation of two fiber links at FLASH


- Much smoother correction
- For 6 month in operation
- Day/night periods & spring -> summer observable
- Smooth operation (interruptions understood)



Operation principle bunch arrival time monitor




The timing information of the electron bunch is transferred into a laser amplitude modulation. This modulation is measured with a photo detector and sampled by a fast ADC.





New pickup design &
Improved readout
⇒ resolution < 10 fs

Courtesy: K. Hacker



Courtesy: F. Loehl

Arrival time correlation between two BAMs




Arrival time difference contains:


- high frequency laser noise (~ 3 MHz – 108 MHz)
- stability of two fiber links
- two BAMs

Single bunch resolution of entire measurement chain: **< 6 fs (rms)**


Arrival time correlation between two BAMs




stability over **1.5 hours**:
13.1 fs uncorrelated jitter
→ **9.3 fs resolution** of a single BAM



stability over **4.5 hours**:
19.4 fs uncorrelated jitter
→ **13.7 fs resolution** of a single BAM




Front-end: bunch arrival time monitors



First prototype of bunch arrival monitor

Courtesy: F. Loehl

Distribution and optical table layout



13

Final implementation design

MLO1

Free space opt.
distribution

- Switching unit
- Invar base plate
- Vibration isolated
- 16 outputs



Fiber link
stabilization
units
(max 14)

Distr. With EDFA
for each link
-Special passive
thermal stabilization
-One output for
MLO lock based
on Sagnac loop
at 1.3GHz

MLO2

Courtesy: B. Beyer

Master laser oscillator (MLO)




Original design:
J. Chen et. al., Opt. Lett. **32**,
1566-1568 (2007)


Specification

- mode-locked erbium-doped fiber laser
- repetition rate of 216.66MHz
- average power > 100mW
- pulse duration < 100 fs (FWHM)
- integrated timing jitter < 10 fs [10Hz,40MHz]
- amplitude noise < $2 \cdot 10^{-4}$ [10Hz,40MHz]


1st generation MLO





2nd generation MLO




3st generation MLO




Distribution system





Distribution system



16





Distribution system



- Tolerance tight:
Lateral shift ~ 50um maximum
Lens L1-L2 only ~2um
- New telescope system with z-translation stage and different lenses
- Good incoupling achieved ~ 85-90%
- Drift test need to be carried out
(first test was reduction at 1 coll. Of 10% observed)
- However, second lens system still missing
(next week produced)
- To be proven if this concept is optimal

Components test: Timing jitter added by erbium-doped fiber amplifiers




The balanced cross-correlator can be used to measure with sub-fs resolution the timing jitter added by an EDFA.

Added timing jitter in femtoseconds
(500 Hz – 4.5 MHz)


An optimized EDFA adds
less than **500 as** timing jitter!

TODO: careful drift investigation







Courtesy: F. Loehl, J. Mueller

Engineered version of link (not yet tested)





19


3 Links are completely assembled
Installation scheduled Feb/March 2009



Piezo driver




Piezo driver




21




Piezo driver




22



Piezo driver




23




- New piezo driver chassis
 - New power supply
- Separation of $\pm 150V$ & $\pm 15V$
Fuses accessible, control LEDs

Optical synchronization of Lasers



Test set for optical synchronization of Ti:Sa



Reference laser: EDFL

$$\lambda = 1550 \text{ nm}$$

$$\Delta\lambda = 90 \text{ nm}$$

$$\langle P_{\text{EDFL}} \rangle = 15 \text{ mW}$$

$$f_{\text{rep,EDFL}} = 40:5 \text{ MHz}$$

$$\tau_{\text{EDFL}} = 110 \text{ fs (FWHM)}$$

Diagnostic Laser: Ti:sapphire

$$\lambda = 800 \text{ nm}$$


$$\Delta\lambda = 70 \text{ nm}$$

$$\langle P_{\text{Ti:Sa}} \rangle = 560 \text{ mW (OXC } 50 \text{ mW)}$$

$$f_{\text{rep,Ti:Sa}} = 81 \text{ MHz}$$


$$\tau_{\text{Ti:Sa}} = 40 \dots 60 \text{ fs (FWHM)}$$

Working principle of balanced optical cross-correlator





- sum frequency generation in a BBO crystal (type-I($\square\square$), ooe)
- application of a group delay to back-reflected input pulses
- measurement of both SFG intensities
- difference highly sensitive to timing changes
- independent of laser amplitude changes (balanced detection)
- input signal for control loop

Optical synchronization of Lasers



First measurement results:



- individual SFG signals at fixed delay Δt
- equal amplitude \Rightarrow balanced case
- amplitude change direct measure for timing changes
- vector modulator scan (scan timing between laser)
- slope of 8.7 mV/fs (amplifier and ADC noise est. < 1 mV)
- sufficient for control loop
- peak distance of 280 fs
- Optical lock for short times established

Using this scheme a Ti:Sa and a Cr:forsterite laser were locked with 300as precision!!!

See: Opt. Letter, 2003 / Vol. 28, No. 11 p. 947



Courtesy: S. Schulz, V.Arsov


Status of Implementation



- Piezo driver: 6 board can be operated, remaining 9 boards need to be repaired
electronic error found
- Motor boxes from link commissioned (16 x 3 Motors)
- Motor box MLO (added T-sensors, and ADCs for Temperature control)
- LDD drivers (32 in operation now, all cables checked)
- Almost all cable work done
- RF lock box in production (old one did not work because of 54MHz laser)

- Preparation of first link is ongoing (this week hopefully)
- BAM DBC3 next
- Installation of free space distribution about 1 month
- New BAM version construction drawing
- L2RF current produced (second loop)
- Good result on short link version





Thanks for your attention